

## OPERATIONS & MAINTENANCE



**US Army Corps  
of Engineers** ®  
San Francisco District

### **Project Map**

## **MOSS LANDING HARBOR CALIFORNIA**

CONGRESSIONAL DISTRICT: 17<sup>th</sup> District, Rep. Sam Farr

PROJECT DESCRIPTION: Provides for maintenance of an entrance channel 200 feet wide and -15 feet deep, and a lagoon channel 100 feet wide and -15 feet deep and about 3,200 feet long, with widening at the junction of the entrance and lagoon channels and at the inner end of the lagoon channel. Two jetties are also maintained.

FISCAL YEAR 03 BUDGET: \$0

PRESENT STATUS: Maintenance dredging was conducted in November 1998 for the outer portion of the harbor. Dredging of the inner portion of the harbor was completed as scheduled in March 2000 utilizing upland disposal. A FY02 Congressional Budget Add provided funding to continue an environmental risk analysis study for aquatic disposal initiated under the funding appropriated by the FY01 Congressional Add.

FUTURE EFFORTS: Continue with the aquatic disposal study, funds permitting. The maintenance dredging cycle is every three years. The next dredging episode is scheduled for June 2003, funds permitting.