

**HUMBOLDT HARBOR AND BAY
OPERATIONS AND MAINTENANCE**

PROJECT LOCATION AND DESCRIPTION: This project is located at Eureka, California, about 280 miles north of San Francisco. Project operations and maintenance provides for annual inspection and periodic repair of the North and South jetties, and annual maintenance dredging of the Bar and Entrance Channels to -48 feet Mean Lower Low Water (MLLW); the North Bay Channel to -38 feet MLLW; the Samoa Channel, including the Turning Basin, to -38 feet MLLW; the Eureka Channel to -35 and -23 feet MLLW; and the Fields Landing Channel to -26 feet MLLW. The permanently designated Humboldt Open Ocean Disposal Site (HOODS) is utilized for disposal of all dredged materials.

TOTAL FUNDING:

TOTAL COST:	\$	N/A
FEDERAL COST:	\$	N/A
NON-FEDERAL COST:	\$	N/A

TOTAL FEDERAL COST FY04:	\$	6,393,000
FISCAL YEAR 05 BUDGET:	\$	2,864,000
COST TO COMPLETE:	\$	N/A

FY 04 AND 05 ACCOMPLISHMENTS: Maintenance dredging of entire project to authorized project depth by Government hopper dredges 'Essayons' and 'Yaquina'. Bar and Entrance may also be dredged under West Coast Regional Hopper Dredge Contract being developed.

ISSUES AND OTHER INFORMATION: Shortfall in dredging budget for FY05 as a result of elimination of Interior Channels dredging by Government hopper dredge 'Yaquina'.

CONGRESSIONAL INTEREST: 1st District, Rep. Mike Thompson

DISTRICT: San Francisco