



US Army Corps  
of Engineers®

---

# **OAKLAND HARBOR TURNING BASINS WIDENING, CA**

## **NAVIGATION STUDY**

### **DRAFT INTEGRATED FEASIBILITY REPORT & ENVIRONMENTAL ASSESSMENT**

## **APPENDIX B5: Cost Engineering**

Contents

1. Introduction..... 3  
    Table 1: First Costs Table Tentatively Selected Plan ..... 3

2. Basis of Costs..... 4  
    2.1. Navigation Ports & Harbors ..... 4  
    2.2. Sediment & Soil Assumption ..... 4  
    2.3. Lands & Damages..... 5  
    2.4. Environmental Mitigation ..... 6  
    2.5. Planning, Engineering and Design..... 6  
    2.6. Construction Management ..... 6

3. Construction Contingency ..... 6

4. Total Project Cost Summary (TPCS) ..... 7  
    TPCS Tentatively Selected Plan ..... 8

5. MCACES (MII) Construction Estimate..... 10

6. Construction Schedule ..... 11

# 1. Introduction

This cost appendix corresponds with the Oakland Harbor Turning Basins Widening Navigation feasibility study. The appendix provides a summary explanation of the project assumptions and other cost related aspects of the project. Greater detail on many project topics can be found in the other technical appendices.

**Table 1: First Costs Table Tentatively Selected Plan**

Oakland Harbor Turning Basins Widening Navigation Study							
01	LANDS AND DAMAGES	1	LS	\$149,047,000	0%	\$0	\$149,047,000
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$410,000	5.0%	\$20,000	\$430,000
02	RELOCATIONS	1	LS	\$1,753,000	36.0%	\$631,000	\$2,384,000
06	FISH& WILDLIFE FACILITIES	1	LS	\$3,240,000	36.0%	\$1,166,000	\$4,406,000
12	NAVIGATION PORTS & HARBORS	1	LS	\$175,596,000	36.0%	\$63,215,000	\$238,811,000
18	CULTURAL RESOURCE PRESERVATION	1	LS	\$0	0%	\$0	\$0
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$35,053,000	36.0%	\$12,619,000	\$47,672,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$14,447,000	36.0%	\$5,201,000	\$19,648,000
	<b>TOTAL</b>			<b>\$379,546,000</b>	<b>21.8%</b>	<b>\$82,853,000</b>	<b>\$462,399,000</b>

## 2. Basis of Costs

### 2.1 Navigation Ports & Harbors

The basis of the majority of the cost estimate for the recommended plan rests with the work associated with the excavation and removal of material to deepen and widen the harbor turning basins. These construction activities include concrete pavement removal, land excavation, bulkhead removal, bulkhead installation, dredging and hauling.

### 2.2 Sediment & Soil Assumptions

#### Howard Terminal:

- Top 15' (Below Ground Surface (BGS) to lowest level of groundwater contact); Assume 90% material will require disposal at a Class II Landfill; assume the remaining 10% of material requires Class I Landfill disposal.
- 15' BGS to contact with Old Bay Mud/Merritt Sand/Posey Formation (OBM/MS) Suitable for Wetland Non-Cover (Montezuma Wetlands).
- Below contact point with OBM/MS, suitable for any reuse (wetland cover, construction, ocean disposal)
- Groundwater can be released to the Bay during construction unless the historic sheetpile wall behind the wharf is breached for construction. In that case, groundwater will require treatment prior to release to the Bay (or alternative disposal). Further, the new bulkhead will need to be constructed to prevent discharges to the Bay unless the groundwater is completely remediated.

#### Alameda:

- Top 15' BGS to lowest level of groundwater contact; Assume 95% material will require disposal at a Class II Landfill and 5% of the volume will require Class I landfill disposal.
- 15' BGS to contact with OBM/MS Suitable for Wetland Non-Cover (Montezuma Wetlands).
- Below contact point with OBM/MS, suitable for any reuse (wetland cover, construction, ocean disposal).
- Groundwater can be released to the Bay during construction.

### **Schnitzer Steel:**

- Assume 75% of the volume of the soil down to 15' BGS requires Class II landfill disposal and 25% requires Class I disposal.
- Material from 15' BGS to contact with OBM/MS will need Class II landfill disposal.
- OBM/MS suitable for any reuse or disposal.
- Groundwater within the site liner will require treatment and offsite disposal. Groundwater below monitoring wells can be discharged to the Bay.
- Any bulkhead will need to be designed to meet environmental mitigation needs (contain and possibly treat groundwater).

### **All Exposed Inner Harbor Sediments (currently not under land):**

- Young Bay Mud (and Recent Bay Mud) acceptable as Wetland Non-Cover at Montezuma Wetlands.
- OBM/MS Suitable for any reuse.
- For the basin area between Schnitzer and Howard Terminal assume 20% of the volume excavated between Schnitzer and Howard require Class II disposal. That is, this material will require placement at Berth 10 – dredge rehandling site – for drying prior to landfill disposal.

### **All Exposed Outer Harbor Sediments (currently not under land):**

- Young Bay Mud (and Recent Bay Mud) acceptable as Wetland Non-Cover at Montezuma Wetlands.
- OBM/MS Suitable for any reuse.

## **2.3 Lands & Damages**

Cost estimates for real estate activities associated with the recommended plan were provided by the Real Estate specialists and appraisers of the PDT. Real Estate costs include all anticipated government labor, such as for property appraisers and attorneys, demolition and disposal of impacted private properties and estimated business impacts or required relocations (separate from utility relocations).

## **2.4 Environmental Mitigation**

Costs associated with environmental mitigation (Fish & Wildlife Facilities, WBS Account 06) were provided by biologists from the study PDT. See the appropriate appendices for discussion of these costs.

## **2.5 Planning, Engineering and Design**

The cost was developed for all activities associated with the planning, engineering and design effort. The cost for this account includes the preparation of Design Documentation Reports, plans, and specifications for the Oakland Harbor Turning Basins Widening Navigation, and engineering support during construction through project completion. It includes all the in-house labor based upon work-hour requirements, material and facility costs, travel, and overhead.

## **2.6 Construction Management**

The cost was developed for all construction management activities from pre-award requirements through final contract closeout. This cost includes the in-house labor based upon work-hour requirements, materials, facility costs, support contracts, travel and overhead. The cost was developed based on the input from the construction division in accordance with the Civil Works Breakdown Structure (CWBS) and includes, but is not limited to, anticipated items such as the salaries of the resident engineer and staff, surveyors, inspectors, drafters, clerical, and custodial personnel; operation, maintenance and fixed charges for transportation and for other field equipment; field supplies; construction management, general construction supervision; and project office administration, distributive cost of area office and general overhead charged to the project.

## **3. Contingencies**

An Abbreviated Risk Analysis (ARA) has been performed to generate risk based contingency rates for utility relocations, environmental mitigations, construction, PED (planning, engineering and design), and construction management.

#### **4. Total Project Cost Summary (TPCS)**

The TPCS was prepared using the latest TPCS excel spreadsheet provided by the USACE, Walla Walla District. The TPCS incorporates the construction cost developed in the MCACES (MII), the project markups, and the functional costs.

The TPCS presents the project first cost and the total project cost (fully funded with inflation).

The project first cost is the cost estimate used in feasibility reports for congressional funding requests.

The total project cost is the constant dollar cost fully funded with escalation to the estimated midpoint of construction. The total cost of construction of general navigation features is the cost estimate used in Project Partnership Agreements and integral determination reports. Total project cost is the cost estimate provided non-federal sponsors for their use in financial planning as it provides information regarding the overall non-federal cost sharing obligation.

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING  
 PROJECT NO P2# 476976  
 LOCATION: OAKLAND, CALIFORNIA

DISTRICT: San Francisco District  
 POC: CHIEF, COST ENGINEERING, Warren Tan  
 PREPARED: 8/26/2021

This Estimate reflects the scope and schedule in report: OAKLAND HARBOR TURNING BASIN WIDENING

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)			
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	Program Year (Budget EC): 2021 Effective Price Level Date: 1 OCT 20					NFLATEI (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
						ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Spent Thru: 1-Oct-20 (\$K) K				
02	RELOCATIONS	\$1,753	\$631	36.0%	\$2,384	0.0%	\$1,753	\$631	\$2,384	\$0	\$2,384	\$748	\$2,827	
04	DAMS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	\$0	\$0	
05	LOCKS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	\$0	\$0	
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,166	36.0%	\$4,406	0.0%	\$3,240	\$1,166	\$4,406	\$0	\$4,406	\$1,412	\$5,253	
07	POWER PLANT	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	\$0	\$0	
12	NAVIGATION PORTS & HARBORS	\$175,596	\$63,215	36.0%	\$238,811	0.0%	\$175,596	\$63,215	\$238,811	\$0	\$238,811	\$74,951	\$283,147	
18	CULTURAL RESOURCE PRESERVATION #N/A	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	\$0	\$0	
	<b>CONSTRUCTION ESTIMATE TOTALS:</b>	<b>\$180,589</b>	<b>\$65,012</b>		<b>\$245,601</b>	<b>0.0%</b>	<b>\$180,589</b>	<b>\$65,012</b>	<b>\$245,601</b>	<b>\$0</b>	<b>\$245,601</b>	<b>\$77,111</b>	<b>\$291,227</b>	
01	LANDS AND DAMAGES	\$149,047	\$0	0.0%	\$149,047	0.0%	\$149,047	\$0	\$149,047	\$0	\$149,047	\$0	\$176,718	
01	NFS Admin Cost	\$229	\$11	5.0%	\$240	0.0%	\$229	\$11	\$240	\$0	\$240	\$14	\$285	
01	FED Admin Cost	\$181	\$9	5.0%	\$190	0.0%	\$181	\$9	\$190	\$0	\$190	\$11	\$225	
30	PLANNING, ENGINEERING & DESIGN	\$35,053	\$12,619	36.0%	\$47,672	0.0%	\$35,053	\$12,619	\$47,672	\$0	\$47,672	\$15,110	\$57,083	
31	CONSTRUCTION MANAGEMENT	\$14,447	\$5,201	36.0%	\$19,648	0.0%	\$14,447	\$5,201	\$19,648	\$0	\$19,648	\$6,427	\$24,278	
	<b>PROJECT COST TOTALS:</b>	<b>\$379,546</b>	<b>\$82,853</b>	<b>21.8%</b>	<b>\$462,399</b>		<b>\$379,546</b>	<b>\$82,853</b>	<b>\$462,399</b>	<b>\$0</b>	<b>\$462,399</b>	<b>\$98,672</b>	<b>\$549,817</b>	

\_\_\_\_\_  
 CHIEF, COST ENGINEERING, Warren Tan

\_\_\_\_\_  
 PROJECT MANAGER, Erika Powell

\_\_\_\_\_  
 CHIEF, REAL ESTATE, Adam Olso

\_\_\_\_\_  
 CHIEF, PLANNING, Thomas Kendall

\_\_\_\_\_  
 CHIEF, ENGINEERING, Son Ha

\_\_\_\_\_  
 CHIEF, OPERATIONS, Nicholas Malasavage

\_\_\_\_\_  
 CHIEF, CONSTRUCTION, Jere Harper

\_\_\_\_\_  
 CHIEF, CONTRACTING, Mary Fronck

\_\_\_\_\_  
 CHIEF, PM-PB, xxxx

\_\_\_\_\_  
 CHIEF, DPM, xxx

**ESTIMATED TOTAL PROJECT COST: \$549,817**



\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING  
 LOCATION: OAKLAND, CALIFORNIA  
 This Estimate reflects the scope and schedule in report; OAKLAND HARBOR TURNING BASIN WIDENING

DISTRICT: San Francisco District  
 POC: CHIEF, COST ENGINEERING, Warren Tan  
 PREPARED: 8/26/2021

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
		Estimate Prepared: <b>26-Aug-21</b>		Effective Price Level: <b>1-Oct-20</b>		Program Year (Budget EC): <b>2021</b>		Effective Price Level Date: <b>1 OCT 20</b>						
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	RISK BASED				ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Mid-Point Date P	INFLATED (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
		COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F									
<b>02</b>	RELOCATIONS	\$1,753	\$631	36.0%	\$2,384	0.0%	\$1,753	\$631	\$2,384	2026Q4	18.6%	\$2,078	\$748	\$2,827
	#/N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
	#/N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>06</b>	FISH & WILDLIFE FACILITIES	\$3,240	\$1,166	36.0%	\$4,406	0.0%	\$3,240	\$1,166	\$4,406	2026Q4	18.6%	\$3,842	\$1,412	\$5,253
<b>07</b>	POWER PLANT	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>12</b>	NAVIGATION PORTS & HARBORS	\$175,596	\$63,215	36.0%	\$238,811	0.0%	\$175,596	\$63,215	\$238,811	2026Q4	18.6%	\$208,196	\$74,951	\$283,147
<b>18</b>	CULTURAL RESOURCE PRESERVATION	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
	#/N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		<b>\$180,589</b>	<b>\$65,012</b>	<b>36.0%</b>	<b>\$245,601</b>		<b>\$180,589</b>	<b>\$65,012</b>	<b>\$245,601</b>			<b>\$214,116</b>	<b>\$77,111</b>	<b>\$291,227</b>
<b>01</b>	LANDS AND DAMAGES	\$149,047	\$0	0.0%	\$149,047	0.0%	\$149,047	\$0	\$149,047	2026Q4	18.6%	\$176,718	\$0	\$176,718
<b>01</b>	NFS Admin Cost	\$229	\$11	5.0%	\$240	0.0%	\$229	\$11	\$240	2026Q4	18.6%	\$272	\$14	\$285
<b>01</b>	FED Admin Cost	\$181	\$9	5.0%	\$190	0.0%	\$181	\$9	\$190	2026Q4	18.6%	\$215	\$11	\$225
<b>30</b>	PLANNING, ENGINEERING & DESIGN													
1.0%	Project Management	\$1,806	\$650	36.0%	\$2,456	0.0%	\$1,806	\$650	\$2,456	2025Q4	19.0%	\$2,150	\$774	\$2,924
2.0%	Planning & Environmental Compliance	\$3,612	\$1,300	36.0%	\$4,912	0.0%	\$3,612	\$1,300	\$4,912	2025Q4	19.0%	\$4,300	\$1,548	\$5,848
7.0%	Engineering & Design	\$12,641	\$4,551	36.0%	\$17,192	0.0%	\$12,641	\$4,551	\$17,192	2025Q4	19.0%	\$15,048	\$5,417	\$20,465
1.4%	Reviews, ATRs, IEPs, VE	\$2,546	\$917	36.0%	\$3,463	0.0%	\$2,546	\$917	\$3,463	2025Q4	19.0%	\$3,031	\$1,091	\$4,122
1.0%	Life Cycle Updates (cost, schedule, risks)	\$1,806	\$650	36.0%	\$2,456	0.0%	\$1,806	\$650	\$2,456	2025Q4	19.0%	\$2,150	\$774	\$2,924
2.0%	Contracting & Reprographics	\$3,612	\$1,300	36.0%	\$4,912	0.0%	\$3,612	\$1,300	\$4,912	2025Q4	19.0%	\$4,300	\$1,548	\$5,848
1.0%	Engineering During Construction	\$1,806	\$650	36.0%	\$2,456	0.0%	\$1,806	\$650	\$2,456	2026Q4	23.6%	\$2,232	\$803	\$3,035
2.0%	Planning During Construction	\$3,612	\$1,300	36.0%	\$4,912	0.0%	\$3,612	\$1,300	\$4,912	2026Q4	23.6%	\$4,463	\$1,607	\$6,070
1.0%	Project Operations	\$1,806	\$650	36.0%	\$2,456	0.0%	\$1,806	\$650	\$2,456	2025Q4	19.0%	\$2,150	\$774	\$2,924
1.0%	Adaptive Management and Monitoring	\$1,806	\$650	36.0%	\$2,456	0.0%	\$1,806	\$650	\$2,456	2026Q4	19.0%	\$2,150	\$774	\$2,924
<b>31</b>	CONSTRUCTION MANAGEMENT													
7.0%	Construction Management	\$12,641	\$4,551	36.0%	\$17,192	0.0%	\$12,641	\$4,551	\$17,192	2026Q4	23.6%	\$15,620	\$5,623	\$21,243
0.0%	Project Operation:	\$0	\$0	36.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
1.0%	Project Management	\$1,806	\$650	36.0%	\$2,456	0.0%	\$1,806	\$650	\$2,456	2026Q4	23.6%	\$2,232	\$803	\$3,035
<b>CONTRACT COST TOTALS:</b>		<b>\$379,546</b>	<b>\$82,853</b>		<b>\$462,399</b>		<b>\$379,546</b>	<b>\$82,853</b>	<b>\$462,399</b>			<b>\$451,145</b>	<b>\$98,672</b>	<b>\$549,817</b>

<u>Description</u>	<u>Quantity</u>	<u>UOM</u>	<u>ProjectCost</u>
<b>All Construction WBS Accounts</b>			<b>180,589,261.04</b>
<b>WBS Account Number 02 Relocations</b>	<b>1.0000</b>	<b>LS</b>	<b>1,753,000.00</b>
<b>WBS Account Number 06 Fish &amp; Wildlife Facilities</b>	<b>1.0000</b>	<b>LS</b>	<b>3,240,000.00</b>
<b>WBS Account Number 12 Navigation Ports and Harbor</b>	<b>1.0000</b>	<b>LS</b>	<b>175,596,261.04</b>
<b>INNER HARBOR</b>	<b>1.0000</b>	<b>LS</b>	<b>129,513,741.04</b>
<b>OUTER HARBOR</b>	<b>1.0000</b>	<b>LS</b>	<b>46,082,520.00</b>

**Howard Terminal**

Activity	QTY	SV	Crew No.	Working Day(s)	Per Day																		
					Backhoe/Front Ldr	Concrete Saw	Crane	Dozer	Dump Truck	Drilling Rig	Barge Ship	Dive Vessel	Dredging Vessel	Diesel Hammer	Excavator	Vibratory Hammer	Tug Boat	Compressor	Generator	Torch	Equipment Operator	Labor	Driver
01H Concrete Pavement Removal Area	12,780	SV	1	13																4	4		
02H Sheertpile/ Bulkhead Installation	42,250	SF	1	121	1	1														3	5		
04H Howard Pile Removal Activity	300	EA	1	33																5	8		
10H Pile Hauling	300	EA	1	17			1													1	2		1
03H Land Excavation	72,407	CY	1	48					0	2										4	6		
04H Hauling	72,407	CY	1	48					75											2	4		75
05H Anchor/Tie back Installation	1,900	LF	1	6	1															2	6		
06H Sheertpile/ Bulkhead Removal	18,500	SF	1	59																6	8		
08H Dredging	191,667	CY	1	27						1										2	5		

**Alameda**

Activity	QTY	SV	Crew No.	Working Day(s)	Per Day																		
					Backhoe/Front Ldr	Concrete Saw	Crane	Dozer	Dump Truck	Drilling Rig	Barge Ship	Dive Vessel	Dredging Vessel	Diesel Hammer	Excavator	Vibratory Hammer	Tug Boat	Compressor	Generator	Torch	Equipment Operator	Labor	Driver
00A Warehouse Demol Activity	260,000	SF	1	26																3	10		2
01A Concrete Pavement Removal Area	24,000	SF	1	24	1	1				1	2									4	4		
02A Sheertpile/ Bulkhead Installation	68,250	SF	1	195	1															3	5		
03A Land Excavation	135,370	CY	1	90					0	2										4	6		
04A Hauling	135,370	CY	1	90					75											2	4		75
06A Alameda Pile Removal Activity	2,300	EA	1	128																5	8		
10A Pile Hauling	2,300	EA	1	128																1	2		1
05A Anchor/Tie back Installation	2,100	LF	1	7	1															2	6		
06A Sheertpile/ Bulkhead Removal	81,250	SF	1	81																6	8		
07A Dredging	358,333	CY	1	51																2	5		

**Schnitzer Steel**

Activity	QTY	SV	Crew No.	Working Day(s)	Per Day																		
					Backhoe/Front Ldr	Concrete Saw	Crane	Dozer	Dump Truck	Drilling Rig	Barge Ship	Dive Vessel	Dredging Vessel	Diesel Hammer	Excavator	Vibratory Hammer	Tug Boat	Compressor	Generator	Torch	Equipment Operator	Labor	Driver
01S Concrete Pavement Removal Area	1,200	SF	1	1	1	1														4	4		0
02S Sheertpile/ Bulkhead Installation	20,150	SF	1	58	1															3	5		0
03S Land Excavation	6,256	CY	1	4					0	2										4	6		0
04S Hauling	6,256	CY	1	4					75											2	4		75
04S-A Land Excavation DBM/MS (Class II)	7,407	CY	1	5					0	2										4	6		0
04S-A Hauling DBM/MS (Class II)	7,407	CY	1	5					75											2	4		75
05S Anchor/Tie back Installation	700	LF	1	2	1															2	6		0
06S Sheertpile/ Bulkhead Removal	20,800	SF	1	21																6	8		0
07S Dredging	16,667	CY	1	2																2	5		0

**Inner Harbor Sediments**

07N-D Dredging - Class II	63,704	CY	1	9																2	5		
11+12N Berth 10 Class II Handling	63,704	CY	1	9						38										2	5		38
07N-D Dredging - Total	254,815	CY	1	36																2	5		

**Outer Harbor**

07O-D Dredging - Total	862,000	CY	1	123																2	5		
------------------------	---------	----	---	-----	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	---	---	--	--

