


US Army Corps of Engineers®

Appendix G Cost Engineering

South Pacific Division, Continuing Authorities Program San Francisco District



Continuing Authorities Program (CAP), Section 103

TABLE OF CONTENTS

1. INTRODUCTION

2. BASIS OF ESTIMATE

- 3. TOTAL PROJECT COST SUMMARIES
- 4. ABBREVIATED RISK ANALYSIS
- 5. CONSTRUCTION SCHEDULE
- 6. MCACES REPORT

1. INTRODUCTION

The cost estimate for the Lower Colma Flood Protection Project's Feasibility Report was developed using the Micro-Computer Aided Cost Estimating System (MCACES), Second Generation (MII) software and the USACE established Civil Works Work Breakdown Structure (CWWBS). The estimate used quantities provided by the Civil Design Section, and was based on USACE cost estimating standards, and the cost estimating knowledge and judgment of USACE cost engineers as they apply to civil works projects.

Table 1: First Costs Table Tentatively Selected Plan

			_	lma Creek CA ection Feasibilit			
				r 2022 Price Le			
				r 2022 Price Le			
	Feas	sibilit	` *	rt Cost Estimat	<i>,</i>	y	
Feat. Acct.	Description	Qty	UoM	Subtotal	Cont. %	Cont \$\$	Total Cost
01	LANDS AND DAMAGES	1	LS	\$1,344,000	5.0%	\$67,000	\$1,411,000
11	FLOODWALLS	1	LS	\$7,348,000	39.0%	\$2,866,000	\$10,214,000
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$1,129,000	39.0%	\$440,000	\$1,569,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$587,000	39.0%	\$229,000	\$816,000
	TOTAL			\$10,408,000	35.0%	\$3,602,000	\$14,010,000

2. BASIS OF ESTIMATE

BASIS/FACTS/ASSUMPTIONS

The basis for the estimate was the scoping documents provided by the Project Delivery Team (PDT). The unit costs for the construction features were computed by estimating the equipment, labor, material, and production rates suitable for the project.

EFFECTIVE PRICE LEVEL

The cost estimate effective price level is October 2022.

OVERTIME

The estimate assumed that the work will be done during 8-hour shifts, 5 days a week and that no overtime will be required.

ACQUISITION PLAN

The acquisition plan is unknown at this time; however, the cost estimate was developed assuming Invitation for Bid (IFB) competitive bidding, under multiple contracts with a prime contractor and subcontractors. It is assumed that construction will take four to five years to complete, and there will be a five separate contracts, one for each reach.

SITE ACCESS

There are no site access issues for the Contractor for this project, therefore no additional cost impacts have been applied to the IGE for this element.

CONSTRUCTION METHOD

No special construction technologies are required for the job.

UNUSUAL CONDITIONS

No unusual conditions are anticipated.

EQUIPMENT/LABOR AVAILABILITY AND DISTANCE TRAVELED

The project is located within San Mateo County, California. All labor and equipment are assumed available within a 100-miles radius in order to allow for fair competition.

ENVIRONMENTAL CONCERNS

No special environmental concerns beyond those stated in the construction window.

LABOR RATES

The labor rates used are from the Davis-Bacon wage rates tables for the San Francisco Bay Area, California.

EQUIPMENT RATES

Equipment rates are based upon the latest approved U.S. Army Corps of Engineers, Engineer Pamphlet (EP) 1110-1-8, Vol. 07, Construction Equipment Ownership and Operation Expense Schedule.

MATERIAL COSTS

Material prices were obtained from vendor and supplier quotes, discussions with USACE personnel and local government agencies, historical cost data from previous projects, and the MCACES Unit Price Book.

CONTINGENCIES

During development of the cost estimates, sufficient contingencies developed via PDT discussions during Abbreviated Risk Analysis (ARA) were applied to develop the Total Project First Cost. The breakdown of items within each account. The contingency factors used in the two alternatives are summarized in Table 1 and in the Total Project Cost Summary (TPCS).

PROJECT: XXXXXX PROJECT NO: P2 XXXXXX LOCATION: South San Francisco, CA

DISTRICT: SPN

Printed:12/12/2022 Page 1 of 2

PREPARED: 10/1/2022

POC: CHIEF, COST ENGINEERING, WARREN TAN

This Estimate reflects the scope and schedule in report; Report Name and date

Civi	il Works Work Breakdown Structure		ESTIMATE	D COST					OJECT FIRST (nstant Dollar B				TOTAL PROJE	ECT COST FUNDED)	(FULLY
WBS <u>NUMBER</u>	Civil Works Feature & Sub-Feature Description	COST _(\$K)_	CNTG _(\$K)	CNTG _(%)_	TOTAL _(\$K)_	ESC _(%)_		ffective Pric	· (Budget EC): ze Level Date: REMAINING COST _(\$K)_	2023 1-Oct- 22 Spent Thru: 1-Oct-22 _(\$K)_	TOTAL FIRST COST _(\$K)_	ESC _(%)_	COST _(\$K)_	CNTG _(\$K)	FULL _(\$K)_
11	LEVEES & FLOODWALLS	\$7,348	- \$2,866 -	39%	\$10,214	-	\$7,348	\$2,866	\$10,214		\$10,214	- 4.2% - -	\$7,657	\$2,986	\$10,644
	CONSTRUCTION ESTIMATE TOTALS:	\$7,348	\$2,866	-	\$10,214	-	\$7,348	\$2,866	\$10,214		\$10,214	4.2%	\$7,657	\$2,986	\$10,644
01	LANDS AND DAMAGES	\$1,344	\$67	5%	\$1,411		\$1,344	\$67	\$1,411		\$1,411	4.2%	\$1,401	\$70	\$1,471
30	PLANNING, ENGINEERING & DESIGN	\$1,129	\$440	39%	\$1,569		\$1,129	\$440	\$1,569		\$1,569	2.5%	\$1,157	\$451	\$1,608
31	CONSTRUCTION MANAGEMENT	\$587	\$229	39%	\$816		\$587	\$229	\$816		\$816	4.0%	\$610	\$238	\$848
	PROJECT COST TOTALS:	\$10,408	\$3,602	35%	\$14,010	-	\$10,408	\$3,602	\$14,010	·	\$14,010	4.0%	\$10,825	\$3,746	\$14,571
		CHIEF, COS	T ENGINEE	RING, WARI	REN TAN										
		PROJECT M	IANAGER, R	OBERT GR	MES							TED FED	DERAL COST:	65%	\$14,571 \$9,471
		CHIEF, REA	L ESTATE, C	ESPD-SPK									DERAL COST:	35%	\$5,100
		CHIEF, PLAN	NNING, TOM	KENDALL						22		TED FED	DERAL COST:		\$1,170 \$635
		CHIEF, ENG	INEERING, S	SON HA										%	\$535
	CHIEF, OPERATIONS, NICK MALASAVAGE									ESTIN	IATED FEDERA	LCOSI	OF PROJECT		\$10,106
	CHIEF, CONSTRUCTION, JERE HARPER														
		CHIEF, CON	TRACTING,	MARY FRO	NCK										
		CHIEF, PM-	PB, xxxx												
		CHIEF, DPM	, XXX												

Filename: Lower Colma Updated TPCS 11.17.2022.xlsx TPCS

**** CONTRACT COST SUMMARY ****

Printed:12/12/2022 Page 2 of 2

PREPARED: 10/1/2022

PROJECT: XXXXXX LOCATION: South San Francisco, CA

This Estimate reflects the scope and schedule in report; Report Name and date

POC: CHIEF, COST ENGINEERING, WARREN TAN

	WBS Structure ESTIMATED COST Estimate Prepared:					PROJE	CT FIRST COST Dollar E		(Constant	TOTAL PROJECT COST (FULLY FUNDED)				
			nate Prepareo ate Price Lev		1-Oct-22 1-Oct-22	<u> </u>	ram Year (Budge ctive Price Level I	,	2023 1 -Oct-22					
WBS <u>NUMBER</u> A	Civil Works Feature & Sub-Feature Description B PHASE 1 or CONTRACT 1	COST <u>(\$K)</u> C	F CNTG <u>(\$K)</u> D	RISK BASED CNTG <u>(%)</u> E	TOTAL _ <u>(\$K)_</u> <i>F</i>	ESC (%) G	COST _ <u>(\$K)</u> <i>H</i>	CNTG <u>(\$K)</u> I	TOTAL _(\$K) J	Mid-Point <u>Date</u> P	ESC (%) L	COST _(\$K) M	CNTG <u>(\$K)</u> <i>N</i>	FULL <u>(\$K)</u> O
11	LEVEES & FLOODWALLS	\$7,348	\$2,866	39.0%	\$10,214		\$7,348	\$2,866	\$10,214	2024Q3	4.2%	\$7,657	\$2,986	\$10,644
01	CONSTRUCTION ESTIMATE TOTALS:	\$7,348 \$1,344	\$2,866 \$67	39.0% 5.0%	\$10,214 \$1,411	-	\$7,348 \$1,344	\$2,866 \$67	\$10,214 \$1,411	2024Q3	4.2%	\$7,657 \$1,401	\$2,986 \$70	\$10,644 \$1,471
30	PLANNING, ENGINEERING & DESIGN													
1.0%		\$73	\$28	39.0%	\$101		\$73	\$28	\$101	2023Q4	2.3%	\$75	\$29	\$104
1.0%	0	\$73	\$28	39.0%	\$101		\$73	\$28	\$101	2023Q4	2.3%	\$75	\$29	\$104
7.0%	0 0 0	\$514 \$103	\$200 \$40	39.0% 39.0%	\$714 \$143		\$514 \$103	\$200 \$40	\$714 \$143	2023Q4 2023Q4	2.3% 2.3%	\$526 \$105	\$205 \$41	\$731 \$146
1.4% 1.0%		\$103	\$40 \$28	39.0% 39.0%	\$143 \$101		\$103	\$40 \$28	\$143 \$101	2023Q4 2023Q4	2.3%	\$105	\$41 \$29	\$146 \$104
1.0%		\$73 \$73	∍∠o \$28	39.0% 39.0%	\$101 \$101		\$73 \$73	\$28 \$28	\$101	2023Q4 2024Q3	4.0%	\$75 \$76	\$29 \$30	\$104 \$105
1.0%	0 1 0 1	\$73	\$28	39.0%	\$101		\$73	\$28	\$101 \$101	2024Q3	4.0%	\$76	\$30	\$105 \$105
2.0%		\$147	\$57	39.0%	\$204		\$147	\$57	\$204	2023Q4	2.3%	\$150	\$59	\$209
1.0%	•			39.0%										
1.0%	Project Operations			39.0%										
31	CONSTRUCTION MANAGEMENT													
7.0%		\$514	\$200	39.0%	\$714		\$514	\$200	\$714	2024Q3	4.0%	\$534	\$208	\$743
1.070	Project Operation:	ψυι-r	Ψ200	39.0%	Ψιισ		ψυττ	<i>4</i> 2 00	ψιi⊐ť	202100	1.070	φ υ υ η	4200	Ψ. 15
1.0%		\$73	\$28	39.0%	\$101		\$73	\$28	\$101	2024Q3	4.0%	\$76	\$30	\$105
	CONTRACT COST TOTALS:	\$10,408	\$3,602		\$14,010	=	\$10,408	\$3,602	\$14,010			\$10,825	\$3,746	\$14,571

	Project Development Stage/Alternative Risk Categor	Abbreviated Risk Analysis): Lower Colma Creek CAP 103 : Feasibility (Recommended Plan) y: Low Risk: Typical Construction, Simple Total Estimated Construction Contract Cost = [\$	3,232,602		Alternative: Meeting Date:		A 3/10/2022	
	CWWBS	Feature of Work	<u>Es</u>	timated Cost		% Contingency	<u>\$</u>	Contingency	<u>Total</u>
01	LANDS AND DAMAGES	Real Estate	\$	-		0%	\$	- \$	-
1		Alternative 1: North Floodwall + PS4+ early warni	\$	5,528,000		35%	\$	1,921,608 \$	7,449,608
2		Alternative 2: N&S Floodwalls + PS4 + early warni	\$	7,135,000		35%	\$	2,480,223 \$	9,615,223
3		Alternative 3: Nonstructural Plan- raising electrica	\$	72,041,000		107%	\$	77,039,458 \$	149,080,458
4						0%	\$	- \$	-
5						0%	\$	- \$	-
6						0%	\$	- \$	-
7						0%	\$	- \$	-
8			\$	-		0%	\$	- \$	-
9			\$	-		0%	\$	- \$	-
10			\$			0%	\$	- \$	-
11			\$	-		0%	\$	- \$	-
12 AII 0	Other	Remaining Construction Items	\$	(81,471,398)	0.0%	0%	\$	(9,850,934) \$	(91,322,332)
13 30 F	PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$			0%	\$	- \$	-
14 31 0	CONSTRUCTION MANAGEMENT	Construction Management	\$			0%	\$	- \$	-
XX FIXE	ED DOLLAR RISK ADD (EQUALLY DISPERSED TO ALL, MI	JST INCLUDE JUSTIFICATION SEE BELOW)					\$		
		Totals							

	Totals					
	Real Estate \$	-	0%	\$	-	\$ -
	Total Construction Estimate \$	3,232,602	2215%	\$	71,590,355	\$ 74,822,957
	Total Planning, Engineering & Design \$	-	0%	\$	-	\$ -
	Total Construction Management \$	-	0%	\$	-	\$ -
	Total Excluding Real Estate \$	3,232,602	2215%	\$	71,590,355	\$ 74,822,957
			Bas	se	50%	80%
	Confidence Level Ra	ange Estimate (\$000's)	\$3,23	3k	\$46,187k	\$74,823k
				* 50%	% based on base is at 5% CL.	
Fixed Dollar Risk Add: (Allows for additional risk to be added to the risk analsyis. Must include justification. Does not allocate to Real Estate.						
justinication. Does not allocate to Real Estate.						

Lower Colma Creek CAP 103 Alt A

Feasibility (Recommended Plan) Abbreviated Risk Analysis Meeting Dates: 10-Mar-22 17-Mar-22



Risk Register

Risk Element	Feature of Work	Concerns	PDT Discussions & Conclusions (Include logic & justification for choice of Likelihood & Impact)	Impact	Likelihood	Risk Level
Project Ma	inagement & Scope Growth			Maximum Proje	ct Growth	40%
PS-1	Alternative 1: North Floodwall + PS4+ early warning	Refined alignment to be determined	Bedrock is not very shallow and should be ok based on proposed alignment. If unknown underground utilities are discovered, they may need to be relocated, or the alignment may need to be pushed further into the adjacent marsh, which could increase environmental mitigation cost. Sheetpile driving that meets hard material could slow construction. Subsurface sampling showed no hard material at the intended embedment depth, but sampling is limited, so there is a possibility of encountering.	Moderate	Unlikely	1
PS-2	Alternative 2: N&S Floodwalls + PS4 + early warning system	Refined alignment to be determined	Bedrock is not very shallow and should be ok based on proposed alignment. If unknown underground utilities are discovered, they may need to be relocated, or the alignment may need to be pushed further into the adjacent marsh, which could increase environmental mitigation cost. Sheetpile driving that meets hard material could slow construction. Subsurface sampling showed no hard material at the intended embedment depth, but sampling is limited, so there is a possibility of encountering.	Moderate	Unlikely	1
PS-3	Alternative 3: Nonstructural Plan- raising electrical, floodproofing, elevated exits/walkways, early warning system	Costs are conceptual and parametric but refinement would not change plan selection and would likely only increase the cost.	Floodproofing costs were obtained from the North Atlantic Coastal Comprehensive Study and are parametric costs, which may not apply sufficiently to a wastewater treatment facility. Uncertainty is high and further refinement would likely increase the cost. For electrical raising, this cost was provided by the non-federal-sponsor based on similar constructed projects and is a conceptual cost, which is likely to rise based on further refinement. This is not the tentatively selected plan and is outside of the scope of the CAP cost limit. The cost to raise exits and walkways out of the flood depths has not been included and would only raise the cost further. Early warning system costs has also been excluded, as it is neglible compared to overall cost.	Significant	Very LIKELY	5

PS-4	0			Negligible	Unlikely	0
PS-5	0			Negligible	Unlikely	0
PS-6	0			Negligible	Unlikely	0
PS-7	0			Negligible	Unlikely	0
PS-8	0			Negligible	Unlikely	0
PS-9	0			Negligible	Unlikely	0
PS-10	0			Negligible	Unlikely	0
PS-11	0			Negligible	Unlikely	0
PS-12	Remaining Construction Items	Possible mitigation	There is a rough order of magnitude cost included for mitigation. This has a 30% contingency added to it based on it being a rough cost estimate. There is a small possiblity that actual mitigation could exceed this cost estimate.	Marginal	Possible	1
PS-13	Planning, Engineering, & Design	No concerns	A standard percentage cost estimate was applied initially of 35%. This is a simple project and design. After the Abbreviated CSRA, this estimate will decrease. The project was justified even with the higher estimate.	Negligible	Unlikely	0
PS-14	Construction Management	No concerns	A standard percentage cost estimate was applied initially of 35%. This is a simple project and design. After the Abbreviated CSRA, this estimate will decrease. The project was justified even with the higher estimate.	Negligible	Unlikely	0
<u>Acquisitio</u>	n Strategy			Maximum Proje	ct Growth	30%
AS-1	Alternative 1: North Floodwall + PS4+ early warning	One parcel of real estate will need to be acquired from the State.	Part of the WQCP footprint near Colma Creek on the north side of the bank is owned by the State of California. If the City of South San Francisco does not already have a sufficient existing easement, they will need to acquire a permanent easement for this tract. There is a unlikely possibility that real estate will not be able to be attained, or will take prolonged coordination to attain which will cause delays and added project management costs.	Significant	Unlikely	2
AS-2	Alternative 2: N&S Floodwalls + PS4 + early warning system	One parcel of real estate will need to be acquired from the State.	Part of the WQCP footprint near Colma Creek on the north side of the bank is owned by the State of California. If the City of South San Francisco does not already have a sufficient existing easement, they will need to acquire a permanent easement for this tract. There is a unlikely possibility that real estate will not be able to be attained, or will take prolonged coordination to attain which will cause delays and added project management costs.	Significant	Unlikely	2
AS-3	Alternative 3: Nonstructural Plan- raising electrical, floodproofing, elevated exits/walkways, early warning system			Negligible	Unlikely	0

						_
AS-4	0			Negligible	Unlikely	0
AS-5	0			Negligible	Unlikely	0
AS-6	0			Negligible	Unlikely	0
AS-7	0			Negligible	Unlikely	0
AS-8	0			Negligible	Unlikely	0
AS-9	0			Negligible	Unlikely	0
AS-10	0			Negligible	Unlikely	0
AS-11	0			Negligible	Unlikely	0
AS-12	Remaining Construction Items			Negligible	Unlikely	0
AS-13	Planning, Engineering, & Design			Negligible	Unlikely	0
AS-14	Construction Management			Negligible	Unlikely	0
<u>Constructi</u>	ion Elements			Maximum Proje	ct Growth	15%
CON-1	Alternative 1: North Floodwall + PS4+ early warning	There may be a need for utility relocations.	There is a 4' by 4' utility box and a 2' by 2' electrical power unit that may need to be relocated prior to floodwall construction.	Significant	Possible	3
CE-2	Alternative 2: N&S Floodwalls + PS4 + early warning system	There may be a need for utility relocations.	There is a 4' by 4' utility box and a 2' by 2' electrical power unit that may need to be relocated prior to floodwall construction.	Significant	Possible	3
CE-3	Alternative 3: Nonstructural Plan- raising electrical, floodproofing, elevated exits/walkways, early warning system	This alternative includes complicated electrical raising.	The risk of this increasing the cost to implement this measure is already captured in risk element PS-3 and SC-3.	Negligible	Unlikely	0
CE-4	0			Negligible	Unlikely	0
CE-5	0			Negligible	Unlikely	0
				Ī		
CE-6	0			Negligible	Unlikely	0
CE-6 CE-7	o o			Negligible	Unlikely Unlikely	0

CE-9	0			Negligible	Unlikely	0
CE-10	0			Negligible	Unlikely	0
CE-11	0			Negligible	Unlikely	0
CE-12	Remaining Construction Items			Negligible	Unlikely	0
CE-13	Planning, Engineering, & Design			Negligible	Unlikely	0
CE-14	Construction Management			Negligible	Unlikely	0
Specialty (Construction or Fabrication			Maximum Proje	ct Growth	50%
SC-1	Alternative 1: North Floodwall + PS4+ early warning	N/A	Subsurface testing for buried cultural artifacts could reveal artifacts, which would need to be excavated and reburied or documented. This would add to the cost. If listed species are identified prior to or during construction, a monitor or more stringent construction windows could increase the cost.	Moderate	Possible	2
SC-2	Alternative 2: N&S Floodwalls + PS4 + early warning system	N/A	Subsurface testing for buried cultural artifacts could reveal artifacts, which would need to be excavated and reburied or documented. This would add to the cost. If listed species are identified prior to or during construction, a monitor or more stringent construction windows could increase the cost.	Moderate	Possible	2
SC-3	Alternative 3: Nonstructural Plan- raising electrical, floodproofing, elevated exits/walkways, early warning system	Alternative 3 includes specialty construction, which could cause the cost estimate to increase. It is not the TSP, so there is no risk this would change the selected plan.	Raising the electrical system is highly specialized work. Floodproofing this type of infrastructure could also be considered specialty construction and may require custom fabrication, which could increase the cost estimate.	Significant	Very LIKELY	5
SC-4	0			Negligible	Unlikely	0
SC-5	0			Negligible	Unlikely	0
SC-6	0			Negligible	Unlikely	0
SC-7	0			Negligible	Unlikely	0
SC-8	0			Negligible	Unlikely	0
SC-9	0			Negligible	Unlikely	0
SC-10	0			Negligible	Unlikely	0

SC-11	0			Negligible	Unlikely	0
SC-12	Remaining Construction Items			Negligible	Unlikely	0
SC-13	Planning, Engineering, & Design			Negligible	Unlikely	0
SC-14	Construction Management			Negligible	Unlikely	0
<u>Technical</u>	Design & Quantities		•	Maximum Proje	ct Growth	20%
T-1	Alternative 1: North Floodwall + PS4+ early warning	No concerns		Negligible	Unlikely	0
T-2	Alternative 2: N&S Floodwalls + PS4 + early warning system	No concerns		Negligible	Unlikely	0
Т-3	Alternative 3: Nonstructural Plan- raising electrical, floodproofing, elevated exits/walkways, early warning system	No concerns		Negligible	Unlikely	0
T-4	0			Negligible	Unlikely	0
T-5	0			Negligible	Unlikely	0
T-6	0			Negligible	Unlikely	0
T-7	0			Negligible	Unlikely	0
T-8	0			Negligible	Unlikely	0
T-9	0			Negligible	Unlikely	0
T-10	0			Negligible	Unlikely	0
T-11	0			Negligible	Unlikely	0
T-12	Remaining Construction Items			Negligible	Unlikely	0
T-13	Planning, Engineering, & Design			Negligible	Unlikely	0
T-14	Construction Management			Negligible	Unlikely	0
<u>Cost Estin</u>	nate Assumptions			Maximum Proje	ct Growth	25%

EST-1	Alternative 1: North Floodwall + PS4+ early warning	Prime and Subcontractor markup could be greater than estimated	this would increase the cost of construction	Moderate	Possible	2
EST-2	Alternative 2: N&S Floodwalls + PS4 + early warning system	Prime and Subcontractor markup could be greater than estimated	this would increase the cost of construction	Moderate	Possible	2
EST-3	Alternative 3: Nonstructural Plan- raising electrical, floodproofing, elevated exits/walkways, early warning system	Prime and Subcontractor markup could be greater than estimated	this would increase the cost of construction	Moderate	Possible	2
EST-4	0			Negligible	Unlikely	0
EST-5	0			Negligible	Unlikely	0
EST-6	0			Negligible	Unlikely	0
EST-7	0			Negligible	Unlikely	0
EST-8	0			Negligible	Unlikely	0
EST-9	0			Negligible	Unlikely	0
EST-10	0			Negligible	Unlikely	0
EST-11	0			Negligible	Unlikely	0
EST-12	Remaining Construction Items			Negligible	Unlikely	0
EST-13	Planning, Engineering, & Design			Negligible	Unlikely	0
EST-14	Construction Management			Negligible	Unlikely	0
External P	<u>roject Risks</u>			Maximum Proje	ct Growth	20%
EX-1	Alternative 1: North Floodwall + PS4+ early warning	Weather, funding constraints, inflation, supply chain issues, material costs, or workforce availability and other outside factors could impact construction schedule and productivity, increasing cost of construction.	Rain or storms or wet ground could impact the construction schedule. Generally for CAP, the funding can be dropped in full, or by FY. The recent infrastructure bill greatly increased the CAP funding from previous years by orders of magnitude. This decreases the liklihood of funding not becoming available to construct. Workforce availability, supply chain issues, increased material costs, and inflation are more likely to occur than these other outside factors.	Moderate	Possible	2

EX-2	Alternative 2: N&S Floodwalls + PS4 + early warning system	Weather, funding constraints, inflation, supply chain issues, material costs, or workforce availability and other outside factors could impact construction schedule and productivity, increasing cost of construction.	Rain or storms or wet ground could impact the construction schedule. Generally for CAP, the funding can be dropped in full, or by FY. The recent infrastructure bill greatly increased the CAP funding from previous years by orders of magnitude. This decreases the liklihood of funding not becoming available to construct. Workforce availability, supply chain issues, increased material costs, and inflation are more likely to occur than these other outside factors.	Moderate	Possible	2
EX-3	Alternative 3: Nonstructural Plan- raising electrical, floodproofing, elevated exits/walkways, early warning system	Weather, funding constraints, inflation, supply chain issues, material costs, or workforce availability and other outside factors could impact construction schedule and productivity, increasing cost of construction.	Rain or storms or wet ground could impact the construction schedule. Generally for CAP, the funding can be dropped in full, or by FY. The recent infrastructure bill greatly increased the CAP funding from previous years by orders of magnitude. This decreases the liklihood of funding not becoming available to construct. Workforce availability, supply chain issues, increased material costs, and inflation are more likely to occur than these other outside factors.	Moderate	Possible	2
EX-4	0			Negligible	Unlikely	0
EX-5	0			Negligible	Unlikely	0
EX-6	0			Negligible	Unlikely	0
EX-7	0			Negligible	Unlikely	0
EX-8	0			Negligible	Unlikely	0
EX-9	0			Negligible	Unlikely	0
EX-10	0			Negligible	Unlikely	0
EX-11	0			Negligible	Unlikely	0
EX-12	Remaining Construction Items			Negligible	Unlikely	0
EX-13	Planning, Engineering, & Design			Negligible	Unlikely	0
EX-14	Construction Management			Negligible	Unlikely	0

Lower Colma Construction Schedule

					Constru	uction `	Year: 20	024																																							
			Wk #	Wk #	# Wk #	Wk #	Wk #	# Wk	# Wk	# Wk	# Wk	# Wk	# Wk	# Wk	# W	/k# V	Vk #	Wk#	Wk#	Wk #	Wk #	Wk #	Wk#	Wk #	Wk #	Wk#	Wk	Wk #	Wk #	Wk#	Wk #	Wk #	Wk #	Wk#	Wk #	Wk#	Wk #	Wk #	Wk #	Wk #	Wk #	# Wk	# Wk	# Wk #	# Wk	(# W	#
Activity	Start	Finish	1	2	3	4	5	6	7	8	9	10	11	12		13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	2 (_
			7-Jan	14-Jan	n 21-Jan	28-Jan	4-Feb	11-Fe	b 18-Fe	eb 25-Fe	eb 3-Ma	ar 10-Ma	ar 17-M	ar 24-N	1ar 31-	-Mar 7	'-Apr	14-Apr	21-Apr	28-Apr	5-May	12-May	19-May	26-May	2-Jun	9-Jun	16-Ju	23-Jun	30-Jun	7-Jul	14-Jul	21-Jul	28-Jul	4-Aug	11-Aug	18-Aug	25-Aug	1-Sep	8-Sep	15-Sep	22-Sep	p 29-Se	p 6-Oct	t 13-Oct	.t 20-0	Jct 27	.t
Mobilization	7-Jan-24	20-Jan-24																																													
Clear and Grubbing	21-Jan-24	10-Feb-24																																													
Floodwall North	11-Feb-24	27-Jul-24																																													
Floodwall South	28-Jul-24	5-Oct-24																																													
Pump Station 4 Perimeter Wall	1-Sep-24	26-Oct-24																																													
Demobilization	27-Oct-24	2-Nov-24																																													

U.S. Army Corps of Engineers Project : LOWER COLMA CREEK

Cost Progression USACE Report

Time 15:10:34

Title Page

North and South Floodwall Alternative includes an I-wall (sheetpile) floodwall, approximately 3 to 4.5 feet above grade at WQCP at the north side of the WQCP adjacent to the right-bank of Creek, as well as a second shorter approximately two-foot-high floodwall south of plant adjacent to San Francisco Bay. At Pump Station 4, a perimeter sheetpile floodwall, approximately 2 feet above grade, would be constructed, with stop log gate for vehicular access and early warning system so that plant operators would know when to seal the stop log gate.

Estimated by SPN Designed by Prepared by Mike Vo Preparation Date 10/15/2022 Effective Date of Pricing 10/15/2022 Estimated Construction Time 301 Days This report is not copyrighted, but the information contained herein is For Official Use Only.

Cost Progression USACE Report

All Construction WBS Accounts Page 1

Description	Quantity UOM	ProjectCost
All Construction WBS Accounts		7,347,681.59
LOWER COLMA CREEK CONSTRUCTION COST	1.0000 JOB	7,347,681.59
TEMPORARY CONSTRUCTION FENCE	1.0000 JOB	28,187.66
TRAFFIC CONTROL	1.0000 JOB	151,555.35
MOBILIZATION AND DEMOBILIZATION	1.0000 JOB	547,041.80
STORM WATER POLLUTION PREVENTION PLAN	1.0000 JOB	5,000.00
CLEARING AND GRUBBING	1.0000 JOB	67,989.19
CONSTRUCTION TRAILER	1.0000 JOB	66,308.18
FLOOD WALL 1 NORTH (500 YEAR EVENT)	1.0000 JOB	4,453,041.49
FLOOD WALL 2 SOUTH (500 YEAR EVENT)	1.0000 JOB	1,476,010.56
PUMP STATION 4: FULL PERIMETER T-WALL (500 YEAR EVENT)	1.0000 JOB	342,468.89
PUMP STATION 4: SMALL INNER T-WALL (500 YEAR EVENT)	1.0000 JOB	210,078.47