Oakland Harbor Turning Basins Widening

Cost Engineering



May 2024





HILL BURNER

Table of Contents

1. Introduction
Tables 1-4: Alternative Costs 3-6
2. Basis of Costs
2.1. Navigation Ports & Harbors
2.2. Sediment & Soil Assumption
2.3. Lands & Damages
2.4. Environmental Mitigation
2.5. Planning, Engineering and Design
2.6. Construction Management
3. Construction Contingency
4. Construction Equipment and Production
5. References
6. Total Project Cost Summary (TPCS) 18
TPCS Alternative Costs
7. Construction Schedule

1. Introduction

This cost appendix corresponds with the Oakland Harbor Turning Basins Widening Navigation feasibility study. The appendix provides a summary explanation of the project assumptions and other cost related aspects of the project. Greater detail on many project topics can be found in the other technical appendices.

Table 1: First Costs Alternative B (IHTB Only)

	Alt B, I			r Turning Basin ion feasibility st	,	Only				
		(Octobe	r 2022 Price Lev	vel					
	Feas	sibility	y Repo	rt Cost Estimat	e Summar	y				
Feat. Acct.										
01	LANDS AND DAMAGES	1	LS	\$90,846,000	0%	\$0	\$90,846,000			
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$430,000	0%	\$0	\$430,000			
02	RELOCATIONS	1	LS	\$2,285,000	0%	\$0	\$2,285,400			
06	FISH& WILDLIFE FACILITIES	1	LS	\$3,240,000	36.0%	\$1,166,000	\$4,406,000			
12	NAVIGATION PORTS & HARBORS	1	LS	\$182,170,000	36.0%	\$65,581,000	\$247,751,000			
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$30,970,000	36.0%	\$11,149,000	\$42,119,000			
31	CONSTRUCTION MANAGEMENT	1	LS	\$13,139,000	36.0%	\$4,730,000	\$17,869,000			
	TOTAL			\$323,835,000	25.6%	\$82,627,000	\$405,707,000			

Table 2: First Costs Alternative C (OHTB Only)

Alt C, Outer Harbor Turning Basins (OHTB) Only Navigation feasibility study October 2022 Price Level

Feat. Acct.	Description	Qty	UoM	Subtotal	Cont. %	Cont \$\$	Total Cost
01	LANDS AND DAMAGES	1	LS	\$0	0%	\$0	\$0
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$0	0%	\$0	\$0
02	RELOCATIONS	1	LS	\$0	0%	\$0	\$0
06	FISH& WILDLIFE FACILITIES	1	LS	\$0	0%	\$0	\$0
12	NAVIGATION PORTS & HARBORS	1	LS	\$66,422,000	36.0%	\$23,912,000	\$90,334,000
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$10,958,000	36.0%	\$3,945,000	\$14,903,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$4,649,000	36.0%	\$1,764,000	\$6,323,000
31		1	LS	\$4,649,000 \$82,029,000	36.0%	\$1,764,000 \$29,530,000	\$6,323

Feasibility Report Cost Estimate Summary

Table 3: First Costs Alternative D (Combo Inner and Outer Harbor Turning Basins)

Alt D, Combo Inner and Outer Harbor Turning Basins Navigation feasibility study October 2023 Price Level

Feasibility Report Cost Estimate Summary

Feat. Acct.	Description	Qty	UoM	Subtotal	Cont. %	Cont \$\$	Total Cost
01	LANDS AND DAMAGES	1	LS	\$61,550,000	0%	\$0	\$61,550,000
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$240,000	0%	\$0	\$240,000
02	RELOCATIONS	1	LS	\$1,706,000	35%	\$597,000	\$2,303,000
06	FISH& WILDLIFE FACILITIES	1	LS	\$3,240,000	35%	\$1,134,000	\$4,374,000
12	NAVIGATION PORTS & HARBORS	1	LS	\$320,275,000	35.0%	\$112,096,000	\$432,371,000
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$53,849,000	35.0%	\$18,971,000	\$72,630,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$22,765,000	35.0%	\$7,968,000	\$30,733,000
	TOTAL			\$463,625,000		\$140,576,000	\$604,201,000

Table 4: First Costs Alternative D-2, Recommended Plan, Combo Inner and Outer Harbor TurningBasins without Electric Dredging

			•	ecommended					
	Combo			Duter Harbor T	0	asins			
				on feasibility st r 2023 Price Lev					
	Feas	sibilit	y Repo	rt Cost Estimate	e Summar	y			
Feat. Acct.									
01	LANDS AND DAMAGES	1	LS	\$61,550,000	0%	\$0	\$61,550,000		
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$240,000	0%	\$0	\$240,000		
02	RELOCATIONS	1	LS	\$1,706,000	35%	\$597,000	\$2,303,000		
06	FISH& WILDLIFE FACILITIES	1	LS	\$3,240,000	35%	\$1,134,000	\$4,374,000		
12	NAVIGATION PORTS & HARBORS	1	LS	\$323,116,000	35.0%	\$113,091,000	\$436,207,000		
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$54,322,000	35.0%	\$18,946,000	\$73,078,000		
31	CONSTRUCTION MANAGEMENT	1	LS	\$22,965,000	35.0%	\$8,038,000	\$31,003,000		
	TOTAL			\$467,139,000	35.0%	\$141,806,000	\$608,945,000		

2. Basis of Costs

2.1 Navigation Ports & Harbors

The basis of the majority of the cost estimate for the recommended plan rests with the work associated with the excavation and removal of material to deepen and widen the harbor turning basins. These construction activities include concrete pavement removal, land excavation, bulkhead removal, bulkhead installation, dredging and hauling.

2.2 Sediment & Soil Assumptions

Howard Terminal:

• Top 15' (Below Ground Surface (BGS) to lowest level of groundwater contact); Assume 90% material will require disposal at a Class II Landfill; assume the remaining 10% of material requires Class 1 Landfill disposal.

• 15' BGS to contact with Old Bay Mud/Merritt Sand/Posey Formation (OBM/MS) Suitable for Wetland Non-Cover (Montezuma Wetlands).

• Below contact point with OBM/MS, suitable for any reuse (wetland cover, construction, ocean disposal)

• Groundwater can be released to the Bay during construction unless the historic sheetpile wall behind the wharf is breeched for construction. In that case, groundwater will require treatment prior to release to the Bay (or alternative disposal). Further, the new bulkhead will need to be constructed to prevent discharges to the Bay unless the groundwater is completely remediated.

Alameda:

• Top 15' BGS to lowest level of groundwater contact; Assume 95% material will require disposal at a Class II Landfill and 5% of the volume will require Class I landfill disposal.

• 15' BGS to contact with OBM/MS Suitable for Wetland Non-Cover (Montezuma Wetlands).

• Below contact point with OBM/MS, suitable for any reuse (wetland cover, construction, ocean disposal).

• Groundwater can be released to the Bay during construction.

Schnitzer Steel:

• OBM/MS suitable for any reuse or disposal.

• Groundwater within the site liner will require treatment and offsite disposal. Groundwater below monitoring wells can be discharged to the Bay.

• Any bulkhead will need to be designed to meet environmental mitigation needs (contain and possibly treat groundwater).

All Exposed Inner Harbor Sediments (currently not under land):

• Young Bay Mud (and Recent Bay Mud) acceptable as Wetland Non-Cover at Montezuma Wetlands.

• OBM/MS Suitable for any reuse.

• For the basin area between Schnitzer and Howard Terminal assume 20% of the volume excavated between Schnitzer and Howard require Class II disposal. That is, this material will require placement at Berth 10 – dredge rehandling site – for drying prior to landfill disposal.

All Exposed Outer Harbor Sediments (currently not under land):

• Young Bay Mud (and Recent Bay Mud) acceptable as Wetland Non-Cover at Montezuma Wetlands.

• OBM/MS Suitable for any reuse.

2.3 Lands & Damages

Cost estimates for real estate activities associated with the recommended plan were provided by the Real Estate specialists and appraisers of the PDT. Real Estate costs include all anticipated government labor, such as for property appraisers and attorneys, demolition and disposal of impacted private properties and estimated business impacts or required relocations (separate from utility relocations).

2.4 Environmental Mitigation

Costs associated with environmental mitigation (Fish & Wildlife Facilities, WBS Account 06) were provided by biologists from the study PDT. See the appropriate appendices for discussion of these costs.

2.5 Planning, Engineering and Design

The cost was developed for all activities associated with the planning, engineering and design effort. The cost for this account includes the preparation of Design Documentation Reports, plans, and specifications for the Oakland Harbor Turning Basins Widening Navigation, and engineering support during construction through project completion. It includes all the in-house labor based upon work-hour requirements, material and facility costs, travel, and overhead.

2.6 Construction Management

The cost was developed for all construction management activities from pre-award requirements through final contract closeout. This cost includes the in-house labor based upon work-hour requirements, materials, facility costs, support contracts, travel and overhead. The cost was developed based on the input from the construction division in accordance with the Civil Works Breakdown Structure (CWBS) and includes, but is not limited to, anticipated items such as the salaries of the resident engineer and staff, surveyors, inspectors, drafters, clerical, and custodial personnel; operation, maintenance and fixed charges for transportation and for other field equipment; field supplies; construction management, general construction supervision; and project office administration, distributive cost of area office and general overhead charged to the project.

3. Contingencies

An Cost Schedule Risk Analysis (CSRA) has been performed to generate risk based contingency rates for utility relocations, environmental mitigations, construction, PED (planning, engineering and design), and construction management.

4. Construction Equipment and Production

The equipment, labor, and production rate assumptions (Table 12 to Table 28) were created using past construction experience from SPN Chief of Civil Design Section, as well as construction production rates from Texas Department of Transportation (2020).

Concrete Pavement Removal Activity (01)							
Production Rate /8-10 hours/crew	150	CY					
1 Crew Including:							
Backhoe	1	each					
Concrete Saw	1	each					
Dozer/Front Loader	1	each					
Dump Truck	2	each					
Equipment Operator	4	person					
Labor	4	person					

Table 1: Concrete Pavement Removal Activity

Table 2: Sheetpile/ Bulkhead Installation Activity

Sheetpile/ Bulkhead Installation Activity (02)

Production Rate /8-10 hours/crew	700	SF
1 Crew Including:		
Backhoe	1	each
Crane	1	each

Diesel Hammer (Delmag D30)	1	each
Dump Truck	1	each
Equipment Operator	3	person
Labor	5	person

Table 3: Land Excavation Activity

Land Excavation Activity (03)

Production Rate/8-10 hours/crew	1,500	CY
1 Crew Including:		
Excavator	2	each
Dozer	0	each
Dump Truck	2	each
Equipment Operator	4	person
Labor	6	person

Table 4: Hauling Activity

Hauling Activity (04)

Production Rate/8-10 hours/crew	1,500	CY
1 Crew Including:		
Excavator	2	each
Dump Truck with Trailers (10 CY)/ 2 Trips/Truck/day	75	each
Equipment Operator	2	each
Driver	75	person
Labor	4	person

Table 5: Anchor/ Tie back Installation Activity Batter Pile Installation Activity – Land side (05)

Production Rate /8-10 hours/crew	450	LF
1 Crew Including:		
Backhoe/Front Ldr	1	each
Drilling Rig	1	each
Crane	1	each
Pile Hammer	1	each
Vibrator	1	each
Equipment Operator	4	person
Labor	5	person

HOWAIG FILE REINOVALACTIVITY (USH)			
Production Rate/8-10 hours/crew	10	each	
1 Crew Including:			
Barge	1	each	
Dive Vessel	1	each	
Crane	1	each	
Excavator	1	each	
Vibrator	1	each	
Dive Compressor	1	each	
Generator	1	each	
Equipment Operator	5	person	
Labor	8	person	

Howard Pile Removal Activity (06H)

Table 7: Alameda Pile Removal Activity

Alameda Pile Removal Activity (06A)

Production Rate/8-10 hours/crew	20	each
1 Crew Including:		
Barge	1	each
Dive Vessel	1	each
Crane	1	each
Excavator	1	each
Vibrator	1	each
Dive Compressor	1	each
Generator	1	each
Equipment Operator	6	person
Labor	8	person

Table 8: Batter Pile Removal Activity

Al Batter Pile Removal Activity (05A1)

Production Rate/8-10 hours/crew	5	each
1 Crew Including:		
Barge	1	each
Dive Vessel	1	each
Crane	1	each
Excavator	1	each

Vibrator	1	each
Dive Compressor	1	each
Generator	1	each
Equipment Operator	5	person
Labor	8	person

Table 9: Sheetpile/Bulkhead Removal Activity

Sheetpile/Bulkhead Removal Activity (06A-W)			
Production Rate/8-10 hours/crew	1,250	SF	
1 Crew Including:			
Barge	2	each	
Dive Vessel	1	each	
Crane	1	each	
Excavator	1	each	
Torch	1	each	
Dive Compressor	1	each	
Generator	1	each	
Equipment Operator	6	person	
Labor	8	person	

Sheetpile/Bulkhead Removal Activity (06A-W)

Table 10: Dredging Activity

Dredging Activity (08)

Production Rate/24-7/crew	6,000	CY
1 Crew Including:		
Dredge	1	each
Crane w/ Clamshell	1	each
Barge Ship/Scow	2	each
Equipment Operator	21	person
Labor	5	person
Tugboat	2	each

Table 11: Warehouse Demo Activity

Warehouse Demo Activity (09)¹

Production Rate/8-10 hours/crew	10,000	SF
1 Crew Including:		
Excavator	1	each

Roll-off High Dumpster	4	each
Demo Dump Truck	2	each
Concrete Saw	2	each
Torch	2	each
Compressor	1	person
Equipment Operator	3	person
Labor	10	person
¹ - Does not include asbestos abatement. Assume 3-person		

crew, 4,000 SF per day abatement rate.

Table 12: Pile Hauling Activity

Alameda Pile Hauling Activity (10A)

Production Rate/8-10 hours/crew	20	each
1 Crew Including:		
Excavator	1	each
Dump Truck with Trailers/2Trip/Truck/day	1	each
Driver	1	person
Labor	4	person

Table 13: Berth 10 Class II Loading Activity (11)

Berth 10 Class II Loading (11)

	<u>.,, , , ,</u>	
Production Rate/24-7/crew	5,000	CY
1 Crew Including:		
Crane w/ Clamshell	1	each
Barge Ship/Scow	2	each
Excavator	1	each
Dozer	1	each
Equipment Operator	23	person
Labor	5	person
Tugboat	1	each

Table 14: Berth 10 Class II Loading Activity (12)

Berth 10 Class II Hauling (12)

Production Rate/24-7/crew	750	CY

1 Crew Including:		
Excavator	1	each
Dozer	1	each
Dump Truck with Trailers (10 CY) 2 Trips/Truck/day	38	each
Driver	38	person
Equipment Operator	2	person
Labor	2	person

Table 15: Pile Hauling Activity

Pile Hauling Activity (10H)

Production Rate/8-10 hours/crew	10	each
1 Crew Including:		
Excavator	1	each
Dump Truck with Trailers/2Trip/Truck/day	1	each
Driver	1	person
Labor	4	person

Table 16: In-water Pile Driving Activity

In-water Pile Driving Activity (07H2-W, 06A2-W)

Production Rate/ /8-10 hours/crew	350	CY
1 Crew Including:		
Backhoe/Frontloader	1	each
Dive Vessel	1	each
Crane	1	each
Diesel Hammer (Delmag D30)	1	each
Equipment Operator	3	person
Labor	5	person

Table 17: In-water Pile Driving Activity

In-water Pile Driving Activity (02S-W)

Production Rate/ /8-10 hours/crew	350	CY
1 Crew Including:		
Backhoe/Frontloader	1	each
Dive Vessel	1	each
Crane	1	each
Diesel Hammer (Delmag D30)	1	each
Equipment Operator	3	person
Labor	5	person

Using the assumptions above, the construction phasing was created for each impacted area of the project (Table 29 to Table 33).

Table 18: Howard Terminal Construction Phasing

Item No.	Project Item	QTY		Crew No.	Working Days							
01H	Concrete Pavement Removal Area	12,780	SY	1	13							
02H	Sheetpile/ Bulkhead Installation	42,250	SF	1	121							
06H	Howard Pile Removal Activity	300	EA	1	33							
10H	Pile Hauling	300	EA	1	17							
03H	Land Excavation	72,407	CY	1	48							
04H	Hauling	72,407	CY	1	48							
05H	Anchor/ Tie back Installation	1,300	LF	1	4							
07H	Sheetpile/ Bulkhead Removal	58,500	SF	1	59							
08H	Dredging	191,667	CY	1	27							

Howard Terminal

Table 19: Alameda Construction Phasing

Alameda

Item No.	Project Item	QTY		Crew No.	Working Days
09A	Warehouse Demo Activity	260,000	SF	1	26
01A	Concrete Pavement Removal Area	24,000	SY	1	24
02A	Sheetpile/ Bulkhead Installation	68,250	SF	1	195
03A	Land Excavation	135,370	CY	1	90
04A	Hauling	135,370	CY	1	90
06A	Alameda Pile Removal Activity	2,300	EA	1	128
10A	Pile Hauling	2,300	EA	1	128
05A	Anchor/ Tie back Installation	2,100	LF	1	7
06A	Sheetpile/ Bulkhead Removal	81,250	SF	1	81
07A	Dredging	358,333	CY	1	51

Table 20: Schnitzer Steel Construction Phasing

Item No.	Project Item	QTY	(Working Days		
01S-W	Bulkhead Installation - In Water	23,100	SF	1	33	
02S-W	Batter Pile Installation - In Water	2,380	LF	1	5	
03S-W	Rip Rap Installation	5,997	CY	1	19	

Schnitzer Steel

Table 21: All Exposed Inner Harbor Sediments Construction Phasing

Item No.	Project Item	QTY		Crew No.	Working Days								
07IN	Dredging	143,291	CY	1	24								
11IN	Berth 10 Class II Loading	9,690	CY	1	2								
12IN	Hauling (Berth 10)	9,690	CY	1	13								

All Exposed Inner Harbor Sediments (Dredging)

Table 22: Outer Harbor Sediment Construction Phasing

Outer Harbor Sediment Dredging

Item No.	Project Item	QTY		Crew No.	Working Days		
07OH	Dredging - YBM	1,341,853	CY	1	224		

5. References:

Reference materials used to prepare the cost estimate, along with the basis for the estimate and any applicable facts and/or assumptions impacting the estimate, are documented below.

- USACE Engineer Regulation, ER 1110-2-1150, Engineering and Design for Civil Works Projects
- USACE Engineering Regulation, ER 1110-1-1300, Cost Engineering Policy And General Requirements
- USACE Engineering Regulation, ER 1110-2-1302, Civil Works Cost Engineering
- USACE Engineering Technical Letter, ETL 1110-2-573, Construction Cost Estimating Guide for Civil Works
- USACE Engineering Manual, EM 1110-2-1304, Civil Works Construction Cost Index System (CWCCIS)
- USACE Engineering Pamphlet, EP 1110-1-8, Vol. 07, Construction Equipment Ownership and Operating Expense Schedule

6. Total Project Cost Summary (TPCS)

The TPCS was prepared using the latest TPCS excel spreadsheet provided by the USACE, Walla Walla District. The TPCS incorporates the construction cost developed in the MCACES (MII), the project markups, and the functional costs. The TPCS addresses inflation through project completion (accomplished by escalation to mid-point of construction of this project) per ER 1110-2-1302. It is based on the scope of the Recommended Plan and the official project schedule. The TPCS includes Federal and Non-Federal costs for Lands and Damages, all construction features, PED, S&A, along with the appropriate contingencies and escalation associated with each of these activities.

OAKLAND HARBOR TURNING BASIN WIDENING, ALT. B, INNER HARBOR ONLY PROJECT:

DISTRICT: San Francisco District

PREPARED:

PROJECT NO: P2# 476976 LOCATION: OAKLAND, CALIFORNIA POC: CHIEF, COST ENGINEERING, Warren Tan

This Estimate reflects the scope and schedule in report;

OAKLAND HARBOR TURNING BASIN WIDENING


Civil	Works Work Breakdown Structure	ESTIMATED COST							ECT FIRST COS ant Dollar Basis	-		TOTAL PROJECT (FULLY FUNDI			
WBS <u>NUMBER</u> A 02 04	Civil Works Feature & Sub-Feature Description B RELOCATIONS DAMS	COST _(\$K) c \$2,285 \$0	CNTG _(\$K) D \$0 \$0	CNTG (%) E 0.0%	TOTAL (\$K) F \$2,285 \$0	ESC (%) G 0.0%	COST (\$K) H \$2,285 \$0		r (Budget EC): ce Level Date: TOTAL 	2023 1 OCT 22 Spent Thru: 1-Oct-22 (\$K) \$0 \$0	TOTAL FIRST <u>COST</u> <u>(\$K)</u> <i>K</i> \$2,285 \$0	NFLATE _(%)_ _L 12.5%	COST (\$K) M \$2,572 \$0	CNTG _(\$K) N \$0 \$0	
05	LOCKS	\$0	\$0 ·		\$0 \$0	-	\$0	\$0 \$0	\$0	\$0		-	\$0	\$0	
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,166	36.0%	\$4,406	0.0%	\$3,240	\$1,166	\$4,406	\$0	\$4,406	14.6%	\$3,693	\$1,358	
07	POWER PLANT	\$0	\$O ·	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	
12	NAVIGATION PORTS & HARBORS	\$182,170 _	\$65,581	36.0% _	\$247,751	0.0%	\$182,170	\$65,581 _	\$247,751	\$0	\$247,751	15.5%.	\$210,364	\$75,731	
18	CULTURAL RESOURCE PRESERVATION	\$0	\$O ·	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	
	#N/A	\$0	\$O ·	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	
	CONSTRUCTION ESTIMATE TOTALS:	\$187,695	\$66,748		\$254,443	0.0%	\$187,695	\$66,748	\$254,443	\$0	\$254,443	15.4%	\$216,628	\$77,089	
01	LANDS AND DAMAGES	\$90,846	\$0	0.0%	\$90,846	0.0%	\$90,846	\$0	\$90,846	\$0	\$90,846	15.5%	\$104,906	\$0	
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	\$0	\$240	15.5%	\$277	\$0	
01	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	\$0	\$190	15.5%	\$219	\$0	
30	PLANNING, ENGINEERING & DESIGN	\$30,970	\$11,149	36.0%	\$42,119	0.0%	\$30,970	\$11,149	\$42,119	\$0	\$42,119	8.6%	\$33,646	\$12,113	
31	CONSTRUCTION MANAGEMENT	\$13,139	\$4,730	36.0%	\$17,869	0.0%	\$13,139	\$4,730	\$17,869	\$0	\$17,869	13.4%	\$14,900	\$5,364	
	PROJECT COST TOTALS:	\$323,080	\$82,627	25.6%	\$405,707		\$323,080	\$82,627	\$405,707	\$0	\$405,707	14.6%	\$370,577	\$94,566	

CHIEF, COST ENGINEERING, Warren Tan
 PROJECT MANAGER, Erika Powell
CHIEF, REAL ESTATE, Adam Olso
CHIEF, PLANNING, Thomas Kendall
CHIEF, ENGINEERING, Son Ha
CHIEF, OPERATIONS, Nicholas Malasavage
 CHIEF, CONSTRUCTION, Jere Harper
 CHIEF, CONTRACTING, Mary Fronck

CHIEF, PM-PB, xxxx

CHIEF, DPM, xxx

ESTIMATED TOTAL PROJECT COST:



\$465,143

**** CONTRACT COST SUMMARY ****

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING

DISTRICT: San Francisco District


PREPARED:

location: Oakland, California

POC: CHIEF, COST ENGINEERI NG, Warren Tan This Estimate reflects the scope and schedule in report; oakland Harbor Turning Basin Widening

Civil W	/orks Work Breakdown Structure		ESTIMAT	ED COST				FIRST COS Dollar Basis		TOTAL PROJECT COST (FULLY FUNDE					
			ate Prepared		10-Jan-23	0	n Year (Budç	,	2023			_			
		Effecti	ve Price Leve	el:	1-Oct-22	Effectiv	e Price Leve	el Date:	1 OCT 22						
				RISK BASED											
WBS	Civil Works	COST	CNTG	CNTG	TOTAL	ESC	COST	CNTG	TOTAL	Mid-Point	INFLATED	COST	CNTG		
JMBER	Feature & Sub-Feature Description	(\$K)	(\$K)	(%)	(\$K)	(%)	(\$K)	(\$K)	(\$K)	Date	(%)	(\$K)	(\$K)		
Α	В	с	D	E	F	G	н	I	J	Р	L	М	N		
02	RELOCATIONS	\$2,285	\$0	0.0%	\$2.285	0.0%	\$2.285	\$0	\$2.285	2027Q3	12.5%	\$2.572	\$0		
	#N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0 \$0	\$0	0	0.0%	\$0	\$0		
	#N/A	\$0 \$0	\$0	0.0%	\$0 \$0	0.0%	\$0	\$0	\$0 \$0	0	0.0%	\$0 \$0	\$0		
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,166	36.0%	\$4,406	0.0%	\$3,240	\$1,166	\$4,406	2028Q1	14.0%	\$3,693	\$1,358		
07	POWER PLANT	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0		
12	NAVIGATION PORTS & HARBORS	\$182,170	\$65,581	36.0%	\$247,751	0.0%	\$182,170	\$65,581	\$247,751	2028Q3	15.5%	\$210,364	\$75,731		
18	CULTURAL RESOURCE PRESERVATION	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0		
	#N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0		
	CONSTRUCTION ESTIMATE TOTALS:	\$187,695	\$66,748	35.6%	\$254,443		\$187,695	\$66,748	\$254,443			\$216,628	\$77,089		
01	LANDS AND DAMAGES	\$90,846	\$0	0.0%	\$90,846	0.0%	\$90,846	\$0	\$90,846	2028Q3	15.5%	\$104,906	\$0		
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	2028Q3	15.5%	\$277	\$0		
01	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	2028Q3	15.5%	\$219	\$0		
30	PLANNING, ENGINEERING & DESIGN														
1.0%	Project Management	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q2	8.0%	\$2,027	\$730		
2.0%	r lanning a Einnichtan Gomphanoo	\$3,754	\$1,351	36.0%	\$5,105	0.0%	\$3,754	\$1,351	\$5,105	2026Q2	8.0%	\$4,054	\$1,459		
7.0%		\$13,139	\$4,730	36.0%	\$17,869	0.0%	\$13,139	\$4,730	\$17,869	2026Q2	8.0%	\$14,188	\$5,108		
1.0%		\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q2	8.0%	\$2,027	\$730		
1.0%	•)	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q2	8.0%	\$2,027	\$730 \$730		
1.0% 1.0%	5 1 5 1	\$1,877 \$1,877	\$676 \$676	36.0% 36.0%	\$2,553 \$2.553	0.0% 0.0%	\$1,877 \$1.877	\$676 \$676	\$2,553 \$2,553	2026Q2 2028Q3	8.0% 13.4%	\$2,027 \$2.129	\$730 \$766		
1.0%	Englissening Bannig Scholadelen	\$1,877	\$676 \$676	36.0% 36.0%	\$2,553 \$2,553	0.0%	\$1,877 \$1,877	\$676 \$676	\$2,553 \$2,553	2028Q3 2028Q3	13.4%	\$2,129 \$2,129	\$766 \$766		
0.5%	· · · · · · · · · · · · · · · · · · ·	\$938	\$338	36.0%	\$2,333	0.0%	\$938	\$338	\$2,555 \$1,276	2026Q3	8.0%	\$1,013	\$365		
1.0%	1 Tojeot Operations	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q4	8.0%	\$2,027	\$730		
31	CONSTRUCTION MANAGEMENT														
6.0%		\$11,262	\$4,054	36.0%	\$15,316	0.0%	\$11,262	\$4,054	\$15,316	2028Q3	13.4%	\$12,772	\$4,598		
0.0%	Contra a calor management	\$0	\$0	36.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0		
1.0%	r tojeot operation:	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2028Q3	13.4%	\$2,129	\$766		
	CONTRACT COST TOTALS:	\$323,080	\$82.627		\$405.707		\$323.080	\$82,627	\$405,707			\$370.577	\$94,566	-	

1/10/2023



OAKLAND HARBOR TURNING BASIN WIDENING, ALT. C, OUTER HARBOR ONLY PROJECT:

PROJECT NO: P2# 476976 LOCATION: OAKLAND, CALIFORNIA

DISTRICT: San Francisco District

POC: CHIEF, COST ENGINEERING, Warren Tan

This Estimate reflects the scope and schedule in report; OAKLAND HARBOR TURNING BASIN WIDENING

Civil	Works Work Breakdown Structure	ESTIMATED COST					PROJECT FIRST COST (Constant Dollar Basis)							TOTAL PROJECT (FULLY FUNDE			
WBS <u>NUMBER</u> A	Civil Works <u>Feature & Sub-Feature Description</u> B	COST 	CNTG (\$K) D	CNTG 	TOTAL (\$K) <i>F</i>	ESC (%) G	COST _(<u>\$K)</u> <i>H</i>		r (Budget EC): ce Level Date: TOTAL _(\$K)	2021 1 OCT 20 Spent Thru: 1-Oct-22 (\$K)	TOTAL FIRST COST 	NFLATE (%)	COST _(\$K)	CNTG 			
02	RELOCATIONS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
04	DAMS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
05	LOCKS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
06	FISH & WILDLIFE FACILITIES	\$0	\$0	36.0%	\$0	0.0%	\$0	\$0	\$0	\$0	\$0	-	\$0	\$29			
07	POWER PLANT	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
12	NAVIGATION PORTS & HARBORS	\$66,422	\$23,912	36.0%	\$90,334	0.0%	\$66,422	\$23,912	\$90,334	\$0	\$90,334	15.5%	\$76,702	\$27,613			
18	CULTURAL RESOURCE PRESERVATION	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
	#N/A	\$0	\$0		\$0	-	\$0	\$0	\$0	\$0	\$0		\$0	\$0			
	CONSTRUCTION ESTIMATE TOTALS:	\$66,422	\$23,912		\$90,334	0.0%	\$66,422	\$23,912	\$90,334	\$0	\$90,334	15.5%	\$76,702	\$27,642			
01	LANDS AND DAMAGES	\$0	\$0	0.0%	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
01	NFS Admin Cost	\$0	\$0	#DIV/0!	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
01	FED Admin Cost	\$0	\$0	#DIV/0!	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0			
30	PLANNING, ENGINEERING & DESIGN	\$10,958	\$3,945	36.0%	\$14,903	0.0%	\$10,958	\$3,945	\$14,903	\$0	\$14,903	8.6%	\$11,905	\$4,286			
31	CONSTRUCTION MANAGEMENT	\$4,649	\$1,674	36.0%	\$6,323	0.0%	\$4,649	\$1,674	\$6,323	\$0	\$6,323	13.4%	\$5,272	\$1,898			
	PROJECT COST TOTALS:	\$82,029	\$29,530	36.0%	\$111,559		\$82,029	\$29,530	\$111,559	\$0	\$111,559	14.5%	\$93,879	\$33,825			

CHIEF, COST ENGINEERING, Warren Tan

PROJECT MANAGER, Erika Powell

ESTIMATED TOTAL PROJECT COST:

CHIEF, REAL ESTATE, Adam Olso

CHIEF, PLANNING, Thomas Kendall

CHIEF, ENGINEERING, Son Ha

CHIEF, OPERATIONS, Nicholas Malasavage


CHIEF, CONSTRUCTION, Jere Harper

CHIEF, CONTRACTING, Mary Fronck

CHIEF, PM-PB, xxxx

CHIEF, DPM, xxx

PREPARED:



\$127,704

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING PROJECT NO: P2# 476976 LOCATION: OAKLAND, CALIFORNIA

DISTRICT: San Francisco District POC: CHIEF, COST ENGINEERING, Warren Tan

This Estimate reflects the scope and schedule in report;

OAKLAND HARBOR TURNING BASIN WIDENING

National Economic Development (NED)

Civil	Norks Work Breakdown Structure	ESTIMATED COST					PROJECT FIRST COST (Constant Dollar Basis)						TOTAL PROJECT COST (FULLY FUNDED)			
							Program Year (Budget EC): Effective Price Level Date: 1									
WBS NUMBER	Civil Works Feature & Sub-Feature Description	COST (\$K)	CNTG (\$K)	CNTG _(%)_	TOTAL _(\$K)	ESC (%)	COST (\$K)	CNTG _(\$K)	TOTAL _(\$K)	Spent Thru: 1-Oct-23 _(\$K)_	(\$K)	NFLATE(COST (\$K)	CNTG (\$K)	FULL (\$K)	
A	В	с	D	E	F	G	н	1	J		к	L	м	N	0	
02 06	RELOCATIONS	\$1,706	\$597	35.0%	\$2,303	0.0%	\$1,706	\$597	\$2,303	\$0	\$2,303	10.9%	\$1,892	\$662	\$2,555	
12	FISH & WILDLIFE FACILITIES NAVIGATION PORTS & HARBORS	\$3,240 \$320,275	\$1,134 \$112,096	35.0% 35.0%	\$4,374 \$432,371	0.0% 0.0%	\$3,240 \$320,275	\$1,134 \$112,096	\$4,374 \$432,371	\$0 \$0	\$4,374 \$432,371	11.6% 13.3%	\$3,594 \$362,949	\$1,287 \$127,032	\$4,881 \$489,981	
	CONSTRUCTION ESTIMATE TOTALS:	\$325,221	\$113,827	_	\$439,048	0.0%	\$325,221	\$113,827	\$439,048	\$0	\$439,048	13.3%	\$368,435	\$128,981	\$497,417	
01	LANDS AND DAMAGES	\$61,550	\$0	0.0%	\$61,550	0.0%	\$61,550	\$0	\$61,550	\$0	\$61,550	0.0%	\$61,550	\$0	\$61,550	
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	\$0	\$240	8.0%	\$259	\$0	\$259	
30	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	\$0	\$190	8.0%	\$205	\$0	\$205	
30	PLANNING, ENGINEERING & DESIGN	\$53,659	\$18,781	35.0%	\$72,440	0.0%	\$53,659	\$18,781	\$72,440	\$0	\$72,440	11.8%	\$59,982	\$20,994	\$80,976	
31	CONSTRUCTION MANAGEMENT	\$22,765	\$7,968	35.0%	\$30,733	0.0%	\$22,765	\$7,968	\$30,733	\$0	\$30,733	17.9%	\$26,845	\$9,396	\$36,241	
	PROJECT COST TOTALS:	\$463,625	\$140,576	30.3%	\$604,201		\$463,625	\$140,576	\$604,201	\$0	\$604,201	12.0%	\$517,277	\$159,371	\$676,648	

CHIEF, COST ENGINEERING, Warren Tan

ESTIMATED TOTAL PROJECT COST:

- PROJECT MANAGER, Erika Powell
- CHIEF, REAL ESTATE, Adam Olso
- CHIEF, PLANNING, Tessa Beach
- CHIEF, ENGINEERING, Barney Wair (Acting)
- CHIEF, OPERATIONS, Nicholas Malasavage
- CHIEF, CONSTRUCTION, Jere Harper
- CHIEF, CONTRACTING, Mary Fronck
- CHIEF, PM-PB, XXXX

Filename: TPCS_Alt D-0 Oakland Widening_Combo Inner and Outer Harbo

PREPARED:

\$676,648

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

OAKLAND HARBOR TURNING BASIN WIDENING PROJECT:

LOCATION: OAKLAND, CALIFORNIA

This Estimate reflects the scope and schedule in report;

OAKLAND HARBOR TURNING BASIN WIDENING

Civil W	orks Work Breakdown Structure		ESTIMATE	ED COST		PROJECT FIRST COST (Constant Dollar Basis) TOTAL PROJECT COST (FULLY FUNDED))		
			nate Prepared ive Price Leve		4-Dec-23 1-Oct-23	-	m Year (Bud ive Price Lev		2024 1 OCT 23					
			R	ISK BASED										
WBS	Civil Works	COST	CNTG	CNTG	TOTAL	ESC	COST	CNTG	TOTAL	Mid-Point	INFLATED	COST	CNTG	FULL
UMBER	Feature & Sub-Feature Description	(\$K)	(\$K)	(%)	(\$K)	(%)	(\$K)	(\$K)	(\$K)	Date	(%)	(\$K)	(\$K)	(\$K)
Α	В	с	D	E	F	G	н	1	J	P	L	м	N	0
02	RELOCATIONS	\$1,706	\$597	35.0%	\$2,303	0.0%	\$1,706	\$597	\$2,303	2028Q1	10.9%	\$1,892	\$662	\$2,5
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,134	35.0%	\$4,374	0.0%	\$3,240	\$1,134	\$4,374	2028Q1	10.9%	\$3,594	\$1,287	\$4,8
07	POWER PLANT	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	
12	NAVIGATION PORTS & HARBORS	\$320,275	\$112,096	35.0%	\$432,371	0.0%	\$320,275	\$112,096	\$432,371	2029Q2	13.3%	\$362,949	\$127,032	\$489,9
18	CULTURAL RESOURCE PRESERVATION	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	
	CONSTRUCTION ESTIMATE TOTALS:	\$325,221	\$113,827	35.0%	\$439,048		\$325,221	\$113,827	\$439,048			\$368,435	\$128,981	\$497,4
01	LANDS AND DAMAGES	\$61,550	\$0	0.0%	\$61,550	0.0%	\$61,550	\$0	\$61,550	2027Q1	0.0%	\$61,550	\$0	\$61,5
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	2027Q1	8.0%	\$259	\$0	\$2
30	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	2027Q1	8.0%	\$205	\$0	\$2
30	PLANNING, ENGINEERING & DESIGN													
1.0%		\$3,252	\$1,138	35.0%	\$4,390	0.0%	\$3,252	\$1,138	\$4,390	2027Q2	10.9%	\$3,608	\$1,263	\$4,8
2.0%		\$6,504	\$2,276	35.0%	\$8,780	0.0%	\$6,504	\$2,276	\$8,780	2027Q2	10.9%	\$7,215	\$2,525	\$9,7
7.0%	°	\$22,765	\$7,968	35.0%	\$30,733	0.0%	\$22,765	\$7,968	\$30,733	2027Q2	10.9%	\$25,255	\$8,839	\$34,0
1.0%		\$3,252 \$3,252	\$1,138 \$1,138	35.0%	\$4,390 \$4,390	0.0%	\$3,252 \$3,252	\$1,138 \$1,138	\$4,390 \$4,390	2027Q2 2027Q2	10.9% 10.9%	\$3,608 \$3,608	\$1,263	\$4,8
1.0%		\$3,252	\$1,138	35.0% 35.0%	\$4,390	0.0%	\$3,252	\$1,138	\$4,390	2027Q2	10.9%	\$3,608	\$1,263 \$1,263	\$4,8 \$4,8
1.0%		\$3,252	\$1,130	35.0%	\$4,390	0.0%	\$3,252	\$1,138	\$4,390	202702	17.9%	\$3,835	\$1,265	\$4,0
1.0%		\$3,252	\$1,138	35.0%	\$4,390	0.0%	\$3,252	\$1,138	\$4,390	2029Q2	17.9%	\$3,835	\$1,342	\$5,1
0.5%		\$1,626	\$569	35.0%	\$2,195	0.0%	\$1,626	\$569	\$2,195	2027Q2	10.9%	\$1,804	\$631	\$2,4
1.0%		\$3,252	\$1,138	35.0%	\$4,390	0.0%	\$3,252	\$1,138	\$4,390	2026Q4	10.9%	\$3,608	\$1,263	\$4,8
31	CONSTRUCTION MANAGEMENT													
6.0%	°	\$19,513	\$6,830	35.0%	\$26,343	0.0%	\$19,513	\$6,830	\$26,343	2029Q2	17.9%	\$23,010	\$8,054	\$31,0
0.0% 1.0%		\$0 \$3,252	\$0 \$1,138	35.0% 35.0%	\$0 \$4,390	0.0%	\$0 \$3,252	\$0 \$1,138	\$0 \$4,390	0 2029Q2	0.0% 17.9%	\$0 \$3,835	\$0 \$1,342	\$5,1
	CONTRACT COST TOTALS:	\$463,625	\$140,576		\$604,201		\$463,625	\$140,576	\$604,201			\$517,277	\$159,371	\$676,6

DISTRICT: San Francisco District

POC: CHIEF, COST ENGINEERING, Warren Tan

Printed:3/

Printed:5/13/2024 Page 2 of 2

PREPARED:

12/4/2023

**** TOTAL PROJECT COST SUMMARY ****

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING PROJECT NO P2# 476976 LOCATION: OAKLAND, CALIFORNIA

_

DISTRICT: San Francisco District POC: CHIEF, COST ENGINEERING, Warren Tan

This Estimate reflects the scope and schedule in report; Revised Draft Integrated Feasibility Report and Environmental Assessment

Civil Works Work Breakdown Structure ESTIMATED COST						PROJECT FIRST COST (Constant Dollar Basis)							TOTAL PROJECT COST (FULLY FUNDED)				
							F	Program Year Effective Price	r (Budget EC): ce Level Date:								
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL _(\$K) F	ESC (%) G	COST (\$K) H	CNTG _(\$K) _/	TOTAL _(\$K) 	Spent Thru: 1-Oct-23 _(\$K)_	TOTAL FIRST COST (<u>\$K)</u> K	NFLATEI _(%)_ L	COST (\$K) M	CNTG _(\$K)N	FULL (\$K) 		
02 06 12	RELOCATIONS FISH & WILDLIFE FACILITIES NAVIGATION PORTS & HARBORS CONSTRUCTION ESTIMATE TOTALS:	\$1,706 \$3,240 \$323,116 \$328,062	\$597 \$1,134 \$113,091 \$114,822	35.0% 35.0% 35.0%	\$2,303 \$4,374 \$436,207 \$442,884	0.0% 0.0% 0.0%	\$1,706 \$3,240 \$323,116 \$328,062	\$597 \$1,134 \$113,091 \$114,822	\$2,303 \$4,374 \$436,207 \$442,884	\$0 \$0 \$0	\$2,303 \$4,374 \$436,207 \$442,884	10.9% 11.6% 13.3%	\$1,892 \$3,594 \$366,169 \$371,655	\$662 \$1,287 \$128,159 	\$2,555 \$4,881 \$494,328 \$501,763		
01 01 30 30	LANDS AND DAMAGES NFS Admin Cost FED Admin Cost PLANNING, ENGINEERING & DESIGN	\$61,550 \$240 \$190 \$54,132	\$0 \$0 \$0 \$18,946	0.0% 0.0% 0.0% 35.0%	\$61,550 \$240 \$190 \$73,078	0.0% 0.0% 0.0% 0.0%	\$61,550 \$240 \$190 \$54,132	\$0 \$0 \$0 \$18,946	\$61,550 \$240 \$190 \$73,078	\$0 \$0 \$0 \$0	\$61,550 \$240 \$190 \$73,078	0.0% 8.0% 8.0% 11.8%	\$61,550 \$259 \$205 \$60,511	\$0 \$0 \$0 \$21,179	\$61,550 \$259 \$205 \$81,690		
31	CONSTRUCTION MANAGEMENT PROJECT COST TOTALS:	\$22,965 \$467,139	\$8,038 \$141,806	35.0%	\$31,003 \$608,945	0.0%	\$22,985 \$467,139	\$8,038 \$141,806	\$31,003 \$608,945	\$0 \$0	\$31,003 \$608,945	17.9%	\$27,081 \$521,261	\$9,478 \$160,765	\$36,559 \$682,026		

CHIEF, COST ENGINEERING, Warren Tan

DDO JECT MANAGED	F H D H
PROJECT MANAGER	. Erika Powell

- CHIEF, REAL ESTATE, Adam Olso
 - CHIEF, PLANNING, Tessa Beach
- CHIEF, ENGINEERING, Barney Wair (Acting)
- CHIEF, OPERATIONS, Nicholas Malasavage
- CHIEF, CONSTRUCTION, Jere Harper
 - CHIEF, CONTRACTING, Mary Fronck
 - CHIEF, PM-PB, xxxx
 - CHIEF, DPM, xxx

Filename: TPCS_Alt D-2 (Beneficial Use and NO Electric Dredging) Oakland Widening_Combo Inner and Outer Harbor - Corrected.xlsx TPCS

Printed:5/8/2024 Page 1 of 2

4/8/2024

PREPARED:

ESTIMATED TOTAL PROJECT COST:

\$682,026

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING LOCATION: OAKLAND, CALIFORNIA

DISTRICT: San Francisco District POC: CHIEF, COST ENGINEERING, Warren Tan


This Estimate reflects the scope and schedule in report; Revised Draft Integrated Feasibility Report and Environmental Assessment

Ci	vil Works Work Breakdown Structure		ESTIMAT	ED COST				FIRST COS t Dollar Basi			TOTAL PROJECT COST (FULLY FUNDED)				
			nate Prepareo ive Price Lev		8-Apr-24 1-Oct-23		m Year (Bud ve Price Lev	· ·	2024 1 OCT 23						
		RISK BASED													
WBS NUMBER		COST (SK)	CNTG (SK)	CNTG (%)	TOTAL _(SK)	ESC (%)	COST (SK)	CNTG (SK)	TOTAL (SK)	Mid-Point Date	INFLATED	COST (\$K)	CNTG (\$K)	FULL (\$K)	
Α	В	с	D	E	F	G	н	1	J	P	L	м	N	0	
02	RELOCATIONS	\$1,706	\$597	35.0%	\$2,303	0.0%	\$1,708	\$597	\$2,303	2028Q1	10.9%	\$1,892	\$662	\$2,55	
06		80.040		05.0%	84.974	0.0%	6 2 040		64.074		10.0%	eo 504	41 207	*4.00	
00	FISH & WILDLIFE FACILITIES POWER PLANT	\$3,240 \$0	\$1,134 \$0	35.0% 0.0%	\$4,374 \$0	0.0%	\$3,240 \$0	\$1,134 \$0	\$4,374 \$0	2028Q1	10.9% 0.0%	\$3,594 \$0	\$1,287 \$0	\$4,88: \$(
12	NAVIGATION PORTS & HARBORS	\$323,116	\$113.091	35.0%	\$436,207	0.0%	\$323,116	\$113.091	\$436,207	2029Q2	13.3%	\$366,169	\$128,159	\$494,32	
18	CULTURAL RESOURCE PRESERVATION	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$151,52	
	CONSTRUCTION ESTIMATE TOTALS:	\$328,062	\$114,822	35.0%	\$442,884		\$328,062	\$114,822	\$442,884			\$371,655	\$130,108	\$501,76	
01	LANDS AND DAMAGES	\$61,550	\$0	0.0%	\$61,550	0.0%	\$61,550	\$0	\$61,550	2027Q1	0.0%	\$61,550	\$0	\$61,550	
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	2027Q1	8.0%	\$259	\$0	\$25	
30	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	2027Q1	8.0%	\$205	\$0	\$20	
30	PLANNING, ENGINEERING & DESIGN			05.00		0.00					10.00		** 374		
	1.0% Project Management 2.0% Planning & Environmental Compliance	\$3,281 \$6,561	\$1,148 \$2,296	35.0% 35.0%	\$4,429 \$8,857	0.0%	\$3,281 \$6,561	\$1,148 \$2,296	\$4,429 \$8.857	2027Q2 2027Q2	10.9% 10.9%	\$3,640 \$7,279	\$1,274 \$2,548	\$4,91 \$9,82	
	7.0% Engineering & Design	\$22,964	\$2,290	35.0%	\$31,001	0.0%	\$22,964	\$8,037	\$31,001	2027Q2	10.9%	\$25,476	\$2,546 \$8,916	\$34,39	
	1.0% Reviews, ATRs, IEPRs, VE	\$3,281	\$1,148	35.0%	\$4,429	0.0%	\$3,281	\$1,148	\$4,429	202702	10.9%	\$3.640	\$1,274	\$4,91	
	1.0% Life Cycle Updates (cost, schedule, risks)	\$3,281	\$1,148	35.0%	\$4,429	0.0%	\$3,281	\$1,148	\$4,429	2027Q2	10.9%	\$3,640	\$1,274	\$4,91	
	1.0% Contracting & Reprographics	\$3,281	\$1,148	35.0%	\$4,429	0.0%	\$3,281	\$1,148	\$4,429	2027Q2	10.9%	\$3,640	\$1,274	\$4,91	
	1.0% Engineering During Construction	\$3,281	\$1,148	35.0%	\$4,429	0.0%	\$3,281	\$1,148	\$4,429	2029Q2	17.9%	\$3,869	\$1,354	\$5,22	
	1.0% Planning During Construction	\$3,281	\$1,148	35.0%	\$4,429	0.0%	\$3,281	\$1,148	\$4,429	2029Q2	17.9%	\$3,869	\$1,354	\$5,22	
	0.5% Project Operations	\$1,640	\$574	35.0%	\$2,214	0.0%	\$1,640	\$574	\$2,214	2027Q2	10.9%	\$1,819	\$637	\$2,45	
	1.0% Adaptive Management and Monitoring	\$3,281	\$1,148	35.0%	\$4,429	0.0%	\$3,281	\$1,148	\$4,429	2026Q4	10.9%	\$3,640	\$1,274	\$4,91	
31	CONSTRUCTION MANAGEMENT														
	6.0% Construction Management	\$19,684	\$6,889	35.0%	\$26,573	0.0%	\$19,684	\$6,889	\$26,573	2029Q2	17.9%	\$23,212	\$8,124	\$31,33	
	0.0% Project Operation:	\$0	\$0	35.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$	
	1.0% Project Management	\$3,281	\$1,148	35.0%	\$4,429	0.0%	\$3,281	\$1,148	\$4,429	2029Q2	17.9%	\$3,869	\$1,354	\$5,22	
	CONTRACT COST TOTALS:	\$467,139	\$141,806		\$608,945		\$467,139	\$141,806	\$608,945			\$521,261	\$160,765	\$682,02	

Printed:5/8/2024 Page 2 of 2

PREPARED: 4/8/2024 n Tan

ID	Task Name		Duration	Start	Finish	Half 2, 2027	S O N	Half 1, 2028 D J F		Half 2, 2028	s o N	н	lalf 1, 2029 J F
1	Contract 1 PED		675 days	Tue 6/1/27	Mon 12/31/29		S O N	DJJF	MAM	ALLL	SON		JF
2	Howard Terminal Cons	struction	284 days	Sun 8/15/27	Wed 9/13/28								
3	Concrete Pavement	Removal	45 days	Tue 6/1/27	Mon 8/2/27								
4	Concrete Pavement	Hauling	4 days	Mon 8/16/27	Thu 8/19/27	1							
5	Sheetpile/Builkhead	Installation	85 days	Mon 9/27/27	Fri 1/21/28	-	at the second se						
6	Howard Pile Remova	al Activity	40 days	Mon 9/27/27	Fri 11/19/27								
7	Pile Hauling		40 days	Mon 9/27/27	Fri 11/19/27	-	4						
8	Land Excavation		17 days	Mon 1/24/28	Tue 2/15/28								
9	Hauling		17 days	Mon 1/24/28	Tue 2/15/28			կատող					
10	Batter Pile Installation	on	22 days	Wed 2/16/28	Thu 3/16/28			*					
11	Bulkhead Installation	n - In water	9 days	Mon 5/29/28	Thu 6/8/28	-				-			
12	Batter Pile Installatio	on - In water	2 days	Fri 6/9/28	Mon 6/12/28	-				t,			
13	Dredging (Below 15')	41 days	Tue 6/13/28	Tue 8/8/28					*			
14	Rip Rap Installation		26 days	Wed 8/9/28	Wed 9/13/28	-				+			
15	Alameda		456 days	Mon 4/3/28	Mon 12/31/29	-							
16	Warehouse Demolit	ion	18 days	Mon 4/3/28	Wed 4/26/28	-							
17	Concrete Pavement	Removal	71 days	Mon 6/26/28	Mon 10/2/28	-				1			
18	Concrete Pavement	Hauling	39 days	Thu 6/1/28	Tue 7/25/28								
19	Sheetpile/Builkhead	Installation	119 days	Mon 5/22/28	Thu 11/2/28								
20	Land Excavation		107 days	Mon 8/21/28	Tue 1/16/29	-							
21	Hauling		107 days	Mon 8/21/28	Tue 1/16/29	-							
22	Alameda Pile Remov	al Activity	105 days	Mon 11/13/28	8 Fri 4/6/29	-							
23	Pile Hauling		105 days	Mon 11/13/28	8 Fri 4/6/29	-					l he		
24	Remove Existing Bat	ter Pile	11 days	Mon 5/28/29	Mon 6/11/29	-							
25	Sheetpile/Bulkhead	Removal	50 days	Mon 6/4/29	Fri 8/10/29								
26	Bulkhead Installation	n - In water	12 days	Mon 8/13/29	Tue 8/28/29	-							
27	Batter Pile Installatio	on - In water	14 days	Wed 8/29/29	Thu 9/20/29	-							
28	Dredging (Below 15)	82 days	Wed 4/25/29	Thu 8/16/29	-							
29	Rip Rap Installation		36 days	Mon 11/12/2	9 Mon 12/31/29	-							
30	Schnitzer		35 days	Mon 8/28/28	Fri 10/13/28	-							
31	Bulkhead Installation	n - In water	11 days	Mon 8/28/28	Mon 9/11/28	-					-h		
32	Batter Pile Installatio	on - In water	5 days	Tue 9/12/28	Mon 9/18/28						*		
33	Rip Rap Installation		19 days	Tue 9/19/28	Fri 10/13/28						+		
34	Inner Harbor Sedimen	ts	73 days	Mon 8/6/29	Wed 11/14/29	-							
35	Dredging (Below 15')	60 days	Mon 8/6/29	Fri 10/26/29	_							
36	Berth 10 Class Loadi	ng	2 days	Thu 10/25/29	Fri 10/26/29	-							
37	Hauling (Berth 10)		13 days	Mon 10/29/29	9 Wed 11/14/29	-							
38	Outer Harbor		356 days	Fri 6/2/28	Fri 10/12/29	-							
39	Dredging		224 days	Fri 6/2/28	Fri 10/12/29	-							
40													
		Task		P	roject Summary		Manual Task		Start-only	C	Deadline		+
-	t OHTB Schedule final 8J	Split			active Task		Duration-only		Finish-only	3	Progress		
Date:	Mon 1/8/24	Milestone	•		active Milestone	0	Manual Summary Rolls	P	External Tasks		Manual Pro	sgress	
		Summary	8	k	active Summary		Manual Summary		External Mileston	• \$			
								Page 1					



ted:3/