



US Army Corps  
of Engineers®

---

# Oakland Harbor Turning Basins Widening

Integrated Feasibility Report and Environmental Assessment

## **APPENDIX B5: Cost Engineering**

*December 2021  
Revised March 2024*

THIS PAGE WAS  
INTENTIONALLY LEFT  
BLANK

# Table of Contents

1. Introduction.....	3
Tables 1-4: Alternative Costs .....	3-6
2. Basis of Costs.....	7
2.1. Navigation Ports & Harbors.....	7
2.2. Sediment & Soil Assumption .....	7
2.3. Lands & Damages.....	8
2.4. Environmental Mitigation.....	8
2.5. Planning, Engineering and Design.....	8
2.6. Construction Management.....	8
3. Construction Contingency .....	9
4. Construction Equipment and Production .....	9-16
5. References .....	17
6. Total Project Cost Summary (TPCS) .....	18
TPCS Alternative Costs .....	19-26
7. Construction Schedule .....	27

# 1. Introduction

This cost appendix corresponds with the Oakland Harbor Turning Basins Widening Navigation feasibility study. The appendix provides a summary explanation of the project assumptions and other cost related aspects of the project. Greater detail on many project topics can be found in the other technical appendices.

**Table 1: First Costs Alternative B (IHTB Only)**

Alt B, Inner Harbor Turning Basins (IHTB) Only							
Navigation feasibility study							
October 2022 Price Level							
Feasibility Report Cost Estimate Summary							
Feat. Acct.	Description	Qty	UoM	Subtotal	Cont. %	Cont. \$\$	Total Cost
01	LANDS AND DAMAGES	1	LS	\$90,846,000	0%	\$0	\$90,846,000
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$430,000	0%	\$0	\$430,000
02	RELOCATIONS	1	LS	\$2,285,000	0%	\$0	\$2,285,400
06	FISH& WILDLIFE FACILITIES	1	LS	\$3,240,000	36.0%	\$1,166,000	\$4,406,000
12	NAVIGATION PORTS & HARBORS	1	LS	\$182,170,000	36.0%	\$65,581,000	\$247,751,000
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$30,970,000	36.0%	\$11,149,000	\$42,119,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$13,139,000	36.0%	\$4,730,000	\$17,869,000
	<b>TOTAL</b>			<b>\$323,835,000</b>	<b>25.6%</b>	<b>\$82,627,000</b>	<b>\$405,707,000</b>

**Table 2: First Costs Alternative C (OHTB Only)**

Alt C, Outer Harbor Turning Basins (OHTB) Only							
Navigation feasibility study							
October 2022 Price Level							
Feasibility Report Cost Estimate Summary							
Feat. Acct.	Description	Qty	UoM	Subtotal	Cont. %	Cont \$\$	Total Cost
01	LANDS AND DAMAGES	1	LS	\$0	0%	\$0	\$0
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$0	0%	\$0	\$0
02	RELOCATIONS	1	LS	\$0	0%	\$0	\$0
06	FISH& WILDLIFE FACILITIES	1	LS	\$0	0%	\$0	\$0
12	NAVIGATION PORTS & HARBORS	1	LS	\$66,422,000	36.0%	\$23,912,000	\$90,334,000
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$10,958,000	36.0%	\$3,945,000	\$14,903,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$4,649,000	36.0%	\$1,764,000	\$6,323,000
	<b>TOTAL</b>			<b>\$82,029,000</b>	<b>36.0%</b>	<b>\$29,530,000</b>	<b>\$111,559,000</b>

**Table 3: First Costs Alternative D (Combo Inner and Outer Harbor Turning Basins)**

Alt D, Combo Inner and Outer Harbor Turning Basins							
Navigation feasibility study							
October 2023 Price Level							
Feasibility Report Cost Estimate Summary							
Feat. Acct.	Description	Qty	UoM	Subtotal	Cont. %	Cont \$\$	Total Cost
01	LANDS AND DAMAGES	1	LS	\$61,550,000	0%	\$0	\$61,550,000
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$240,000	0%	\$0	\$240,000
02	RELOCATIONS	1	LS	\$1,706,000	0%	\$0	\$1,706,000
06	FISH& WILDLIFE FACILITIES	1	LS	\$3,240,000	33%	\$1,069,000	\$4,309,000
12	NAVIGATION PORTS & HARBORS	1	LS	\$285,705,000	33.0%	\$94,283,000	\$379,988,000
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$48,151,000	33.0%	\$15,827,000	\$63,978,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$20,346,000	33.0%	\$6,714,000	\$27,060,000
	<b>TOTAL</b>			<b>\$410,687,000</b>	<b>33.0%</b>	<b>\$114,509,000</b>	<b>\$538,831,000</b>

**Table 4: First Costs Alternative D-2, Recommended Plan, Combo Inner and Outer Harbor Turning Basins without Electric Dredging**

Alt D-2, Recommended Plan Combo Inner and Outer Harbor Turning Basins Navigation feasibility study October 2023 Price Level							
Feasibility Report Cost Estimate Summary							
Feat. Acct.	Description	Qty	UoM	Subtotal	Cont. %	Cont \$\$	Total Cost
01	LANDS AND DAMAGES	1	LS	\$61,550,000	0%	\$0	\$61,550,000
01	LANDS AND DAMAGES ADMIN COSTS	1	LS	\$240,000	0%	\$0	\$240,000
02	RELOCATIONS	1	LS	\$1,706,000	0%	\$0	\$1,706,000
06	FISH& WILDLIFE FACILITIES	1	LS	\$3,240,000	33%	\$1,069,000	\$4,309,000
12	NAVIGATION PORTS & HARBORS	1	LS	\$287,521,000	33.0%	\$94,882,000	\$382,403,000
30	PLANNING, ENGINEERING AND DESIGN	1	LS	\$48,449,000	33.0%	\$15,925,000	\$64,374,000
31	CONSTRUCTION MANAGEMENT	1	LS	\$20,473,000	33.0%	\$6,756,000	\$27,229,000
	<b>TOTAL</b>			<b>\$423,179,000</b>	<b>33.0%</b>	<b>\$118,632,000</b>	<b>\$541,811,000</b>

## 2. Basis of Costs

### 2.1 Navigation Ports & Harbors

The basis of the majority of the cost estimate for the recommended plan rests with the work associated with the excavation and removal of material to deepen and widen the harbor turning basins. These construction activities include concrete pavement removal, land excavation, bulkhead removal, bulkhead installation, dredging and hauling.

### 2.2 Sediment & Soil Assumptions

#### Howard Terminal:

- Top 15' (Below Ground Surface (BGS) to lowest level of groundwater contact); Assume 90% material will require disposal at a Class II Landfill; assume the remaining 10% of material requires Class 1 Landfill disposal.
- 15' BGS to contact with Old Bay Mud/Merritt Sand/Posey Formation (OBM/MS) Suitable for Wetland Non-Cover (Montezuma Wetlands).
- Below contact point with OBM/MS, suitable for any reuse (wetland cover, construction, ocean disposal)
- Groundwater can be released to the Bay during construction unless the historic sheetpile wall behind the wharf is breached for construction. In that case, groundwater will require treatment prior to release to the Bay (or alternative disposal). Further, the new bulkhead will need to be constructed to prevent discharges to the Bay unless the groundwater is completely remediated.

#### Alameda:

- Top 15' BGS to lowest level of groundwater contact; Assume 95% material will require disposal at a Class II Landfill and 5% of the volume will require Class I landfill disposal.
- 15' BGS to contact with OBM/MS Suitable for Wetland Non-Cover (Montezuma Wetlands).
- Below contact point with OBM/MS, suitable for any reuse (wetland cover, construction, ocean disposal).
- Groundwater can be released to the Bay during construction.

#### Schnitzer Steel:

- OBM/MS suitable for any reuse or disposal.
- Groundwater within the site liner will require treatment and offsite disposal. Groundwater below monitoring wells can be discharged to the Bay.

- Any bulkhead will need to be designed to meet environmental mitigation needs (contain and possibly treat groundwater).

**All Exposed Inner Harbor Sediments (currently not under land):**

- Young Bay Mud (and Recent Bay Mud) acceptable as Wetland Non-Cover at Montezuma Wetlands.
- OBM/MS Suitable for any reuse.
- For the basin area between Schnitzer and Howard Terminal assume 20% of the volume excavated between Schnitzer and Howard require Class II disposal. That is, this material will require placement at Berth 10 – dredge rehandling site – for drying prior to landfill disposal.

**All Exposed Outer Harbor Sediments (currently not under land):**

- Young Bay Mud (and Recent Bay Mud) acceptable as Wetland Non-Cover at Montezuma Wetlands.
- OBM/MS Suitable for any reuse.

## **2.3 Lands & Damages**

Cost estimates for real estate activities associated with the recommended plan were provided by the Real Estate specialists and appraisers of the PDT. Real Estate costs include all anticipated government labor, such as for property appraisers and attorneys, demolition and disposal of impacted private properties and estimated business impacts or required relocations (separate from utility relocations).

## **2.4 Environmental Mitigation**

Costs associated with environmental mitigation (Fish & Wildlife Facilities, WBS Account 06) were provided by biologists from the study PDT. See the appropriate appendices for discussion of these costs.

## **2.5 Planning, Engineering and Design**

The cost was developed for all activities associated with the planning, engineering and design effort. The cost for this account includes the preparation of Design Documentation Reports, plans, and specifications for the Oakland Harbor Turning Basins Widening Navigation, and engineering support during construction through project completion. It includes all the in-house labor based upon work-hour requirements, material and facility costs, travel, and overhead.

## **2.6 Construction Management**

The cost was developed for all construction management activities from pre-award requirements through final contract closeout. This cost includes the in-house labor based upon work-hour requirements, materials, facility costs, support contracts, travel and overhead. The cost was developed based on the input from the construction division in accordance with the Civil Works Breakdown Structure (CWBS) and includes, but is not limited to, anticipated items such as the salaries of the resident engineer and staff, surveyors, inspectors, drafters, clerical, and custodial personnel; operation, maintenance and fixed charges for transportation and for other field equipment; field supplies; construction management, general construction supervision; and project office administration, distributive cost of area office and general overhead charged to the project.

### 3. Contingencies

An Cost Schedule Risk Analysis (CSRA) has been performed to generate risk based contingency rates for utility relocations, environmental mitigations, construction, PED (planning, engineering and design), and construction management.

### 4. Construction Equipment and Production

The equipment, labor, and production rate assumptions (Table 12 to Table 28) were created using past construction experience from SPN Chief of Civil Design Section, as well as construction production rates from Texas Department of Transportation (2020).

**Table 1: Concrete Pavement Removal Activity**

<b><u>Concrete Pavement Removal Activity (01)</u></b>		
Production Rate /8-10 hours/crew	150	CY
<b>1 Crew Including:</b>		
Backhoe	1	each
Concrete Saw	1	each
Dozer/Front Loader	1	each
Dump Truck	2	each
Equipment Operator	4	person
Labor	4	person

**Table 2: Sheetpile/ Bulkhead Installation Activity**

<b><u>Sheetpile/ Bulkhead Installation Activity (02)</u></b>		
Production Rate /8-10 hours/crew	700	SF
<b>1 Crew Including:</b>		
Backhoe	1	each
Crane	1	each

Diesel Hammer (Delmag D30)	1	each
Dump Truck	1	each
Equipment Operator	3	person
Labor	5	person

**Table 3: Land Excavation Activity**

**Land Excavation Activity (03)**

Production Rate/8-10 hours/crew	1,500	CY
<b>1 Crew Including:</b>		
Excavator	2	each
Dozer	0	each
Dump Truck	2	each
Equipment Operator	4	person
Labor	6	person

**Table 4: Hauling Activity**

**Hauling Activity (04)**

Production Rate/8-10 hours/crew	1,500	CY
<b>1 Crew Including:</b>		
Excavator	2	each
Dump Truck with Trailers (10 CY)/ 2 Trips/Truck/day	75	each
Equipment Operator	2	each
Driver	75	person
Labor	4	person

*Table 5: Anchor/ Tie back Installation Activity*  
**Batter Pile Installation Activity – Land side (05)**

Production Rate /8-10 hours/crew	450	LF
<b>1 Crew Including:</b>		
Backhoe/Front Ldr	1	each
Drilling Rig	1	each
Crane	1	each
Pile Hammer	1	each
Vibrator	1	each
Equipment Operator	4	person
Labor	5	person

**Table 6: Howard Pile Removal Activity**

**Howard Pile Removal Activity (06H)**

Production Rate/8-10 hours/crew	10	each
<b>1 Crew Including:</b>		
Barge	1	each
Dive Vessel	1	each
Crane	1	each
Excavator	1	each
Vibrator	1	each
Dive Compressor	1	each
Generator	1	each
Equipment Operator	5	person
Labor	8	person

**Table 7: Alameda Pile Removal Activity**

**Alameda Pile Removal Activity (06A)**

Production Rate/8-10 hours/crew	20	each
<b>1 Crew Including:</b>		
Barge	1	each
Dive Vessel	1	each
Crane	1	each
Excavator	1	each
Vibrator	1	each
Dive Compressor	1	each
Generator	1	each
Equipment Operator	6	person
Labor	8	person

**Table 8: Batter Pile Removal Activity**

**AI Batter Pile Removal Activity (05A1)**

Production Rate/8-10 hours/crew	5	each
<b>1 Crew Including:</b>		
Barge	1	each
Dive Vessel	1	each
Crane	1	each
Excavator	1	each

Vibrator	1	each
Dive Compressor	1	each
Generator	1	each
Equipment Operator	5	person
Labor	8	person

**Table 9: Sheetpile/Bulkhead Removal Activity**

**Sheetpile/Bulkhead Removal Activity (06A-W)**

Production Rate/8-10 hours/crew	1,250	SF
<b>1 Crew Including:</b>		
Barge	2	each
Dive Vessel	1	each
Crane	1	each
Excavator	1	each
Torch	1	each
Dive Compressor	1	each
Generator	1	each
Equipment Operator	6	person
Labor	8	person

**Table 10: Dredging Activity**

**Dredging Activity (08)**

Production Rate/24-7/crew	6,000	CY
<b>1 Crew Including:</b>		
Dredge	1	each
Crane w/ Clamshell	1	each
Barge Ship/Scow	2	each
Equipment Operator	21	person
Labor	5	person
Tugboat	2	each

**Table 11: Warehouse Demo Activity**

**Warehouse Demo Activity (09) <sup>1</sup>**

Production Rate/8-10 hours/crew	10,000	SF
<b>1 Crew Including:</b>		
Excavator	1	each

Roll-off High Dumpster	4	each
Demo Dump Truck	2	each
Concrete Saw	2	each
Torch	2	each
Compressor	1	person
Equipment Operator	3	person
Labor	10	person
<b><sup>1</sup> - Does not include asbestos abatement. Assume 3-person crew, 4,000 SF per day abatement rate.</b>		

**Table 12: Pile Hauling Activity**

**Alameda Pile Hauling Activity (10A)**

Production Rate/8-10 hours/crew	20	each
<b>1 Crew Including:</b>		
Excavator	1	each
Dump Truck with Trailers/2Trip/Truck/day	1	each
Driver	1	person
Labor	4	person

**Table 13: Berth 10 Class II Loading Activity (11)**

**Berth 10 Class II Loading (11)**

Production Rate/24-7/crew	5,000	CY
<b>1 Crew Including:</b>		
Crane w/ Clamshell	1	each
Barge Ship/Scow	2	each
Excavator	1	each
Dozer	1	each
Equipment Operator	23	person
Labor	5	person
Tugboat	1	each

**Table 14: Berth 10 Class II Loading Activity (12)**

**Berth 10 Class II Hauling (12)**

Production Rate/24-7/crew	750	CY
---------------------------	-----	----

<b>1 Crew Including:</b>		
Excavator	1	each
Dozer	1	each
Dump Truck with Trailers (10 CY) 2 Trips/Truck/day	38	each
Driver	38	person
Equipment Operator	2	person
Labor	2	person

**Table 15: Pile Hauling Activity**

**Pile Hauling Activity (10H)**

Production Rate/8-10 hours/crew	10	each
<b>1 Crew Including:</b>		
Excavator	1	each
Dump Truck with Trailers/2Trip/Truck/day	1	each
Driver	1	person
Labor	4	person

**Table 16: In-water Pile Driving Activity**

**In-water Pile Driving Activity (07H2-W, 06A2-W)**

Production Rate/ /8-10 hours/crew	350	CY
1 Crew Including:		
Backhoe/Frontloader	1	each
Dive Vessel	1	each
Crane	1	each
Diesel Hammer (Delmag D30)	1	each
Equipment Operator	3	person
Labor	5	person

**Table 17: In-water Pile Driving Activity**

**In-water Pile Driving Activity (02S-W)**

Production Rate/ /8-10 hours/crew	350	CY
1 Crew Including:		
Backhoe/Frontloader	1	each
Dive Vessel	1	each
Crane	1	each
Diesel Hammer (Delmag D30)	1	each
Equipment Operator	3	person
Labor	5	person

Using the assumptions above, the construction phasing was created for each impacted area of the project (Table 29 to Table 33).

**Table 18: Howard Terminal Construction Phasing**

**Howard Terminal**

Item No.	Project Item	QTY		Crew No.	Working Days
01H	Concrete Pavement Removal Area	12,780	SY	1	13
02H	Sheetpile/ Bulkhead Installation	42,250	SF	1	121
06H	Howard Pile Removal Activity	300	EA	1	33
10H	Pile Hauling	300	EA	1	17
03H	Land Excavation	72,407	CY	1	48
04H	Hauling	72,407	CY	1	48
05H	Anchor/ Tie back Installation	1,300	LF	1	4
07H	Sheetpile/ Bulkhead Removal	58,500	SF	1	59
08H	Dredging	191,667	CY	1	27

**Table 19: Alameda Construction Phasing**

**Alameda**

Item No.	Project Item	QTY		Crew No.	Working Days
09A	Warehouse Demo Activity	260,000	SF	1	26
01A	Concrete Pavement Removal Area	24,000	SY	1	24
02A	Sheetpile/ Bulkhead Installation	68,250	SF	1	195
03A	Land Excavation	135,370	CY	1	90
04A	Hauling	135,370	CY	1	90
06A	Alameda Pile Removal Activity	2,300	EA	1	128
10A	Pile Hauling	2,300	EA	1	128
05A	Anchor/ Tie back Installation	2,100	LF	1	7
06A	Sheetpile/ Bulkhead Removal	81,250	SF	1	81
07A	Dredging	358,333	CY	1	51

**Table 20: Schnitzer Steel Construction Phasing**

**Schnitzer Steel**

Item No.	Project Item	QTY		Crew No.	Working Days
01S-W	Bulkhead Installation - In Water	23,100	SF	1	33
02S-W	Batter Pile Installation - In Water	2,380	LF	1	5
03S-W	Rip Rap Installation	5,997	CY	1	19

**Table 21: All Exposed Inner Harbor Sediments Construction Phasing**

**All Exposed Inner Harbor Sediments (Dredging)**

Item No.	Project Item	QTY		Crew No.	Working Days
07IN	Dredging	143,291	CY	1	24
11IN	Berth 10 Class II Loading	9,690	CY	1	2
12IN	Hauling (Berth 10)	9,690	CY	1	13

**Table 22: Outer Harbor Sediment Construction Phasing**

**Outer Harbor Sediment Dredging**

Item No.	Project Item	QTY		Crew No.	Working Days
07OH	Dredging - YBM	1,341,853	CY	1	224

## 5. Total Project Cost Summary (TPCS)

The TPCS was prepared using the latest TPCS excel spreadsheet provided by the USACE, Walla Walla District. The TPCS incorporates the construction cost developed in the MCACES (MII), the project markups, and the functional costs. The TPCS addresses inflation through project completion (accomplished by escalation to mid-point of construction of this project) per ER 1110-2-1302. It is based on the scope of the Recommended Plan and the official project schedule. The TPCS includes Federal and Non-Federal costs for Lands and Damages, all construction features, PED, S&A, along with the appropriate contingencies and escalation associated with each of these activities.

Note: The costs in the TPCS tables and attachments in this appendix reflect the most up to date project costs and currently do not match the last USACE Walla Walla MCX Cost Certification. Final cost certification will occur at the close of State and Agency Review

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING,  
ALT. B, INNER HARBOR ONLY

DISTRICT: San Francisco District

PREPARED: 1/10/2023

PROJECT NO: P2# 476976  
LOCATION: OAKLAND, CALIFORNIA

POC: CHIEF, COST ENGINEERING, Warren Tan

This Estimate reflects the scope and schedule in report, OAKLAND HARBOR TURNING BASIN WIDENING

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)					
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Program Year (Budget EC): 2023 Effective Price Level Date: 1 OCT 22		TOTAL FIRST COST (\$K) K	INFLATE (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
										Spent Thru: 1-Oct-22 (\$K)						
02	RELOCATIONS	\$2,285	\$0	0.0%	\$2,285	0.0%	\$2,285	\$0	\$2,285	\$0	\$2,285	12.5%	\$2,572	\$0	\$2,572	
04	DAMS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
05	LOCKS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,166	36.0%	\$4,406	0.0%	\$3,240	\$1,166	\$4,406	\$0	\$4,406	14.6%	\$3,693	\$1,358	\$5,051	
07	POWER PLANT	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
12	NAVIGATION PORTS & HARBORS	\$182,170	\$65,581	36.0%	\$247,751	0.0%	\$182,170	\$65,581	\$247,751	\$0	\$247,751	15.5%	\$210,364	\$75,731	\$286,094	
18	CULTURAL RESOURCE PRESERVATION #N/A	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
	<b>CONSTRUCTION ESTIMATE TOTALS:</b>	\$187,695	\$66,748		\$254,443	0.0%	\$187,695	\$66,748	\$254,443	\$0	\$254,443	15.4%	\$216,628	\$77,089	\$293,718	
01	LANDS AND DAMAGES	\$90,846	\$0	0.0%	\$90,846	0.0%	\$90,846	\$0	\$90,846	\$0	\$90,846	15.5%	\$104,906	\$0	\$104,906	
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	\$0	\$240	15.5%	\$277	\$0	\$277	
01	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	\$0	\$190	15.5%	\$219	\$0	\$219	
30	PLANNING, ENGINEERING & DESIGN	\$30,970	\$11,149	36.0%	\$42,119	0.0%	\$30,970	\$11,149	\$42,119	\$0	\$42,119	8.6%	\$33,646	\$12,113	\$45,758	
31	CONSTRUCTION MANAGEMENT	\$13,139	\$4,730	36.0%	\$17,869	0.0%	\$13,139	\$4,730	\$17,869	\$0	\$17,869	13.4%	\$14,900	\$5,364	\$20,265	
	<b>PROJECT COST TOTALS:</b>	\$323,080	\$82,627	25.6%	\$405,707		\$323,080	\$82,627	\$405,707	\$0	\$405,707	14.6%	\$370,577	\$94,566	\$465,143	

CHIEF, COST ENGINEERING, Warren Tan

ESTIMATED TOTAL PROJECT COST: \$465,143

PROJECT MANAGER, Erika Powell

CHIEF, REAL ESTATE, Adam Olso

CHIEF, PLANNING, Thomas Kendall

CHIEF, ENGINEERING, Son Ha

CHIEF, OPERATIONS, Nicholas Malasavage

CHIEF, CONSTRUCTION, Jere Harper

CHIEF, CONTRACTING, Mary Fronck

CHIEF, PM-PB, xxxx

CHIEF, DPM, xxx

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING

DISTRICT: San Francisco District

PREPARED: 1/10/2023

LOCATION:  
OAKLAND,  
CALIFORNIA

POC:

CHIEF,  
COST  
ENGINEER  
NG, Warren  
Tan

This Estimate  
reflects the  
scope and  
schedule in  
report;

OAKLAND  
HARBOR  
TURNING  
BASIN  
WIDENING

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
		Estimate Prepared: <b>10-Jan-23</b>				Program Year (Budget EC): <b>2023</b>								
		Effective Price Level: <b>1-Oct-22</b>				Effective Price Level Date: <b>1 OCT 22</b>								
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	RISK BASED				ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Mid-Point Date P	INFLATED (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
		COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F									
<b>02</b>	RELOCATIONS	\$2,285	\$0	0.0%	\$2,285	0.0%	\$2,285	\$0	\$2,285	2027Q3	12.5%	\$2,572	\$0	\$2,572
	#N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
	#N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>06</b>	FISH & WILDLIFE FACILITIES	\$3,240	\$1,166	36.0%	\$4,406	0.0%	\$3,240	\$1,166	\$4,406	2028Q1	14.0%	\$3,693	\$1,358	\$5,051
<b>07</b>	POWER PLANT	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>12</b>	NAVIGATION PORTS & HARBORS	\$182,170	\$65,581	36.0%	\$247,751	0.0%	\$182,170	\$65,581	\$247,751	2028Q3	15.5%	\$210,364	\$75,731	\$286,094
<b>18</b>	CULTURAL RESOURCE PRESERVATION	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
	#N/A	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
	<b>CONSTRUCTION ESTIMATE TOTALS:</b>	<b>\$187,695</b>	<b>\$66,748</b>	<b>35.6%</b>	<b>\$254,443</b>		<b>\$187,695</b>	<b>\$66,748</b>	<b>\$254,443</b>			<b>\$216,628</b>	<b>\$77,089</b>	<b>\$293,718</b>
<b>01</b>	LANDS AND DAMAGES	\$90,846	\$0	0.0%	\$90,846	0.0%	\$90,846	\$0	\$90,846	2028Q3	15.5%	\$104,906	\$0	\$104,906
<b>01</b>	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	2028Q3	15.5%	\$277	\$0	\$277
<b>01</b>	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	2028Q3	15.5%	\$219	\$0	\$219
<b>30</b>	PLANNING, ENGINEERING & DESIGN													
1.0%	Project Management	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q2	8.0%	\$2,027	\$730	\$2,756
2.0%	Planning & Environmental Compliance	\$3,754	\$1,351	36.0%	\$5,105	0.0%	\$3,754	\$1,351	\$5,105	2026Q2	8.0%	\$4,054	\$1,459	\$5,513
7.0%	Engineering & Design	\$13,139	\$4,730	36.0%	\$17,869	0.0%	\$13,139	\$4,730	\$17,869	2026Q2	8.0%	\$14,188	\$5,108	\$19,295
1.0%	Reviews, ATRs, IEPs, VE	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q2	8.0%	\$2,027	\$730	\$2,756
1.0%	Life Cycle Updates (cost, schedule, risks)	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q2	8.0%	\$2,027	\$730	\$2,756
1.0%	Contracting & Reprographics	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q2	8.0%	\$2,027	\$730	\$2,756
1.0%	Engineering During Construction	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2028Q3	13.4%	\$2,129	\$766	\$2,895
1.0%	Planning During Construction	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2028Q3	13.4%	\$2,129	\$766	\$2,895
0.5%	Project Operations	\$938	\$338	36.0%	\$1,276	0.0%	\$938	\$338	\$1,276	2026Q2	8.0%	\$1,013	\$365	\$1,378
1.0%	Adaptive Management and Monitoring	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2026Q4	8.0%	\$2,027	\$730	\$2,756
<b>31</b>	CONSTRUCTION MANAGEMENT													
6.0%	Construction Management	\$11,262	\$4,054	36.0%	\$15,316	0.0%	\$11,262	\$4,054	\$15,316	2028Q3	13.4%	\$12,772	\$4,598	\$17,370
0.0%	Project Operation:	\$0	\$0	36.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
1.0%	Project Management	\$1,877	\$676	36.0%	\$2,553	0.0%	\$1,877	\$676	\$2,553	2028Q3	13.4%	\$2,129	\$766	\$2,895
	<b>CONTRACT COST TOTALS:</b>	<b>\$323,080</b>	<b>\$82,627</b>		<b>\$405,707</b>		<b>\$323,080</b>	<b>\$82,627</b>	<b>\$405,707</b>			<b>\$370,577</b>	<b>\$94,566</b>	<b>\$465,143</b>

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING,  
ALT. C, OUTER HARBOR ONLY

DISTRICT: San Francisco District

PREPARED: 1/10/2023

PROJECT NO: P2# 476976  
LOCATION: OAKLAND, CALIFORNIA

POC: CHIEF, COST ENGINEERING, Warren Tan

This Estimate reflects the scope and schedule in report; OAKLAND HARBOR TURNING BASIN WIDENING

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)			
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	Program Year (Budget EC): 2021		TOTAL (\$K) J	Spent Thru: 1-Oct-22 (\$K) K	TOTAL FIRST COST (\$K) K	INFLATE (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
						ESC (%) G	COST (\$K) H							
02	RELOCATIONS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
04	DAMS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
05	LOCKS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
06	FISH & WILDLIFE FACILITIES	\$0	\$0	36.0%	\$0	0.0%	\$0	\$0	\$0	\$0	-	\$0	\$29	\$29
07	POWER PLANT	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
12	NAVIGATION PORTS & HARBORS	\$66,422	\$23,912	36.0%	\$90,334	0.0%	\$66,422	\$23,912	\$90,334	\$0	15.5%	\$76,702	\$27,613	\$104,314
18	CULTURAL RESOURCE PRESERVATION #N/A	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
	<b>CONSTRUCTION ESTIMATE TOTALS:</b>	\$66,422	\$23,912		\$90,334	0.0%	\$66,422	\$23,912	\$90,334	\$0	15.5%	\$76,702	\$27,642	\$104,343
01	LANDS AND DAMAGES	\$0	\$0	0.0%	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
01	NFS Admin Cost	\$0	\$0	#DIV/0!	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
01	FED Admin Cost	\$0	\$0	#DIV/0!	\$0	-	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
30	PLANNING, ENGINEERING & DESIGN	\$10,958	\$3,945	36.0%	\$14,903	0.0%	\$10,958	\$3,945	\$14,903	\$0	8.6%	\$11,905	\$4,286	\$16,190
31	CONSTRUCTION MANAGEMENT	\$4,649	\$1,674	36.0%	\$6,323	0.0%	\$4,649	\$1,674	\$6,323	\$0	13.4%	\$5,272	\$1,898	\$7,170
	<b>PROJECT COST TOTALS:</b>	\$82,029	\$29,530	36.0%	\$111,559		\$82,029	\$29,530	\$111,559	\$0	14.5%	\$93,879	\$33,825	\$127,704

CHIEF, COST ENGINEERING, Warren Tan

ESTIMATED TOTAL PROJECT COST: \$127,704

PROJECT MANAGER, Erika Powell

CHIEF, REAL ESTATE, Adam Olso

CHIEF, PLANNING, Thomas Kendall

CHIEF, ENGINEERING, Son Ha

CHIEF, OPERATIONS, Nicholas Malasavage

CHIEF, CONSTRUCTION, Jere Harper

CHIEF, CONTRACTING, Mary Fronck

CHIEF, PM-PB, xxxx

CHIEF, DPM, xxx

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING  
 PROJECT NO P2# 476976  
 LOCATION: OAKLAND, CALIFORNIA

DISTRICT: San Francisco District  
 POC: CHIEF, COST ENGINEERING, Warren Tan  
 PREPARED: 12/4/2023

This Estimate reflects the scope and schedule in report; OAKLAND HARBOR TURNING BASIN WIDENING

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Base)					TOTAL PROJECT COST (FULLY FUNDED)				
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	Program Year (Budget EC): 2024 Effective Price Level Date: 1 OCT 23				Spent Thru: 1-Oct-23 (\$K)	TOTAL FIRST COST (\$K) K	FLATEI (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
						ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J						
02	RELOCATIONS	\$1,706	\$0	0.0%	\$1,706	0.0%	\$1,706	\$0	\$1,706	\$0	\$1,706	10.9%	\$1,892	\$0	\$1,892
04	DAMS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
05	LOCKS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,069	33.0%	\$4,309	0.0%	\$3,240	\$1,069	\$4,309	\$0	\$4,309	11.6%	\$3,594	\$1,215	\$4,809
07	POWER PLANT	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
12	NAVIGATION PORTS & HARBORS	\$285,705	\$94,283	33.0%	\$379,988	0.0%	\$285,705	\$94,283	\$379,988	\$0	\$379,988	13.3%	\$323,773	\$106,845	\$430,618
18	CULTURAL RESOURCE PRESERVATION	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
	#N/A	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0
	<b>CONSTRUCTION ESTIMATE TOTALS:</b>	<b>\$290,651</b>	<b>\$95,352</b>		<b>\$386,003</b>	<b>0.0%</b>	<b>\$290,651</b>	<b>\$95,352</b>	<b>\$386,003</b>	<b>\$0</b>	<b>\$386,003</b>	<b>13.3%</b>	<b>\$329,259</b>	<b>\$108,060</b>	<b>\$437,319</b>
01	LANDS AND DAMAGES	\$61,550	\$0	0.0%	\$61,550	0.0%	\$61,550	\$0	\$61,550	\$0	\$61,550	0.0%	\$61,550	\$0	\$61,550
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	\$0	\$240	8.0%	\$259	\$0	\$259
30	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	\$0	\$190	8.0%	\$205	\$0	\$205
30	PLANNING, ENGINEERING & DESIGN	\$47,961	\$15,827	33.0%	\$63,788	0.0%	\$47,961	\$15,827	\$63,788	\$0	\$63,788	11.8%	\$53,613	\$17,692	\$71,305
31	CONSTRUCTION MANAGEMENT	\$20,346	\$6,714	33.0%	\$27,060	0.0%	\$20,346	\$6,714	\$27,060	\$0	\$27,060	17.9%	\$23,992	\$7,917	\$31,910
	<b>PROJECT COST TOTALS:</b>	<b>\$420,938</b>	<b>\$117,893</b>	<b>28.0%</b>	<b>\$538,831</b>		<b>\$420,938</b>	<b>\$117,893</b>	<b>\$538,831</b>	<b>\$0</b>	<b>\$538,831</b>	<b>11.8%</b>	<b>\$468,879</b>	<b>\$133,670</b>	<b>\$602,548</b>

- \_\_\_\_\_ CHIEF, COST ENGINEERING, Warren Tan
- \_\_\_\_\_ PROJECT MANAGER, Erika Powell
- \_\_\_\_\_ CHIEF, REAL ESTATE, Adam Olso
- \_\_\_\_\_ CHIEF, PLANNING, Tessa Beach
- \_\_\_\_\_ CHIEF, ENGINEERING, Barney Wair (Acting)
- \_\_\_\_\_ CHIEF, OPERATIONS, Nicholas Malasavage
- \_\_\_\_\_ CHIEF, CONSTRUCTION, Jere Harper
- \_\_\_\_\_ CHIEF, CONTRACTING, Mary Fronck
- \_\_\_\_\_ CHIEF, PM-PB, xxxx
- \_\_\_\_\_ CHIEF, DPM, xxx

ESTIMATED TOTAL PROJECT COST: **\$602,548**

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING  
 LOCATION: OAKLAND, CALIFORNIA  
 This Estimate reflects the scope and schedule in report; OAKLAND HARBOR TURNING BASIN WIDENING

DISTRICT: San Francisco District  
 POC: CHIEF, COST ENGINEERING, Warren Tan  
 PREPARED: 12/4/2023

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	Estimate Prepared: Effective Price Level:		4-Dec-23 1-Oct-23	TOTAL (\$K) F	Program Year (Budget EC): Effective Price Level Date:		2024 1 OCT 23	TOTAL (\$K) J	Mid-Point Date P	INFLATED (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
		COST (\$K) C	CNTG (\$K) D	CNTG (%) E		ESC (%) G	COST (\$K) H	CNTG (\$K) I						
02	RELOCATIONS	\$1,706	\$0	0.0%	\$1,706	0.0%	\$1,706	\$0	\$1,706	2028Q1	10.9%	\$1,892	\$0	\$1,892
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,069	33.0%	\$4,309	0.0%	\$3,240	\$1,069	\$4,309	2028Q1	10.9%	\$3,594	\$1,215	\$4,809
07	POWER PLANT	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
12	NAVIGATION PORTS & HARBORS	\$285,705	\$94,283	33.0%	\$379,988	0.0%	\$285,705	\$94,283	\$379,988	2029Q2	13.3%	\$323,773	\$106,845	\$430,618
18	CULTURAL RESOURCE PRESERVATION	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		<b>\$290,651</b>	<b>\$95,352</b>	<b>32.8%</b>	<b>\$386,003</b>		<b>\$290,651</b>	<b>\$95,352</b>	<b>\$386,003</b>			<b>\$329,259</b>	<b>\$108,060</b>	<b>\$437,319</b>
01	LANDS AND DAMAGES	\$61,550	\$0	0.0%	\$61,550	0.0%	\$61,550	\$0	\$61,550	2027Q1	0.0%	\$61,550	\$0	\$61,550
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	2027Q1	8.0%	\$259	\$0	\$259
30	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	2027Q1	8.0%	\$205	\$0	\$205
30	PLANNING, ENGINEERING & DESIGN													
1.0%	Project Management	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2027Q2	10.9%	\$3,225	\$1,064	\$4,289
2.0%	Planning & Environmental Compliance	\$5,813	\$1,918	33.0%	\$7,731	0.0%	\$5,813	\$1,918	\$7,731	2027Q2	10.9%	\$6,449	\$2,128	\$8,577
7.0%	Engineering & Design	\$20,346	\$6,714	33.0%	\$27,060	0.0%	\$20,346	\$6,714	\$27,060	2027Q2	10.9%	\$22,571	\$7,449	\$30,020
1.0%	Reviews, ATRs, IEPs, VE	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2027Q2	10.9%	\$3,225	\$1,064	\$4,289
1.0%	Life Cycle Updates (cost, schedule, risks)	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2027Q2	10.9%	\$3,225	\$1,064	\$4,289
1.0%	Contracting & Reprographics	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2027Q2	10.9%	\$3,225	\$1,064	\$4,289
1.0%	Engineering During Construction	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2029Q2	17.9%	\$3,428	\$1,131	\$4,559
1.0%	Planning During Construction	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2029Q2	17.9%	\$3,428	\$1,131	\$4,559
0.5%	Project Operations	\$1,453	\$479	33.0%	\$1,932	0.0%	\$1,453	\$479	\$1,932	2027Q2	10.9%	\$1,612	\$532	\$2,144
1.0%	Adaptive Management and Monitoring	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2026Q4	10.9%	\$3,225	\$1,064	\$4,289
31	CONSTRUCTION MANAGEMENT													
0.0%	Construction Management	\$17,439	\$5,755	33.0%	\$23,194	0.0%	\$17,439	\$5,755	\$23,194	2029Q2	17.9%	\$20,564	\$6,786	\$27,351
0.0%	Project Operation:	\$0	\$0	33.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
1.0%	Project Management	\$2,907	\$959	33.0%	\$3,866	0.0%	\$2,907	\$959	\$3,866	2029Q2	17.9%	\$3,428	\$1,131	\$4,559
<b>CONTRACT COST TOTALS:</b>		<b>\$420,938</b>	<b>\$117,893</b>		<b>\$538,831</b>		<b>\$420,938</b>	<b>\$117,893</b>	<b>\$538,831</b>			<b>\$468,879</b>	<b>\$133,670</b>	<b>\$602,548</b>

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING  
 PROJECT NO: P2# 470076  
 LOCATION: OAKLAND, CALIFORNIA

DISTRICT: San Francisco District  
 POC: CHIEF, COST ENGINEERING, Warren Tan  
 PREPARED: 12/4/2023

This Estimate reflects the scope and schedule in report; OAKLAND HARBOR TURNING BASIN WIDENING

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)					
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Program Year (Budget EC): Effective Price Level Date: 2024 1 OCT 23		TOTAL FIRST COST (\$K) K	FLATEI (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
										Spent Thru: 1-Oct-23 (\$K)						
02	RELOCATIONS	\$1,706	\$0	0.0%	\$1,706	0.0%	\$1,706	\$0	\$1,706	\$0	\$1,706	10.9%	\$1,892	\$0	\$1,892	
04	DAMS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
05	LOCKS	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,069	33.0%	\$4,309	0.0%	\$3,240	\$1,069	\$4,309	\$0	\$4,309	11.6%	\$3,594	\$1,215	\$4,809	
07	POWER PLANT	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
12	NAVIGATION PORTS & HARBORS	\$287,521	\$94,882	33.0%	\$382,403	0.0%	\$287,521	\$94,882	\$382,403	\$0	\$382,403	13.3%	\$325,831	\$107,524	\$433,355	
18	CULTURAL RESOURCE PRESERVATION #N/A	\$0	\$0	-	\$0	-	\$0	\$0	\$0	\$0	\$0	-	\$0	\$0	\$0	
	<b>CONSTRUCTION ESTIMATE TOTALS:</b>	<b>\$292,467</b>	<b>\$95,951</b>		<b>\$388,418</b>	<b>0.0%</b>	<b>\$292,467</b>	<b>\$95,951</b>	<b>\$388,418</b>	<b>\$0</b>	<b>\$388,418</b>	<b>13.3%</b>	<b>\$331,317</b>	<b>\$108,739</b>	<b>\$440,056</b>	
01	LANDS AND DAMAGES	\$61,550	\$0	0.0%	\$61,550	0.0%	\$61,550	\$0	\$61,550	\$0	\$61,550	0.0%	\$61,550	\$0	\$61,550	
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	\$0	\$240	8.0%	\$259	\$0	\$259	
30	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	\$0	\$190	8.0%	\$205	\$0	\$205	
30	PLANNING, ENGINEERING & DESIGN	\$48,259	\$15,925	33.0%	\$64,184	0.0%	\$48,259	\$15,925	\$64,184	\$0	\$64,184	11.8%	\$53,946	\$17,802	\$71,748	
31	CONSTRUCTION MANAGEMENT	\$20,473	\$6,756	33.0%	\$27,229	0.0%	\$20,473	\$6,756	\$27,229	\$0	\$27,229	17.9%	\$24,142	\$7,967	\$32,109	
	<b>PROJECT COST TOTALS:</b>	<b>\$423,179</b>	<b>\$118,633</b>	<b>28.0%</b>	<b>\$541,812</b>		<b>\$423,179</b>	<b>\$118,633</b>	<b>\$541,812</b>	<b>\$0</b>	<b>\$541,812</b>	<b>11.8%</b>	<b>\$471,420</b>	<b>\$134,508</b>	<b>\$605,928</b>	

- \_\_\_\_\_ CHIEF, COST ENGINEERING, Warren Tan
- \_\_\_\_\_ PROJECT MANAGER, Erika Powell
- \_\_\_\_\_ CHIEF, REAL ESTATE, Adam Olso
- \_\_\_\_\_ CHIEF, PLANNING, Tessa Beach
- \_\_\_\_\_ CHIEF, ENGINEERING, Barney Wair (Acting)
- \_\_\_\_\_ CHIEF, OPERATIONS, Nicholas Malasavage
- \_\_\_\_\_ CHIEF, CONSTRUCTION, Jere Harper
- \_\_\_\_\_ CHIEF, CONTRACTING, Mary Fronck
- \_\_\_\_\_ CHIEF, PM-PB, xxxx
- \_\_\_\_\_ CHIEF, DPM, xxx

ESTIMATED TOTAL PROJECT COST: **\$605,928**

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*


\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: OAKLAND HARBOR TURNING BASIN WIDENING  
 LOCATION: OAKLAND, CALIFORNIA  
 This Estimate reflects the scope and schedule in report;

OAKLAND HARBOR TURNING BASIN WIDENING

DISTRICT: San Francisco District  
 POC: CHIEF, COST ENGINEERING, Warren Tan  
 PREPARED: 12/4/2023

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	Estimate Prepared: Effective Price Level:		4-Dec-23 1-Oct-23	TOTAL (\$K) F	Program Year (Budget EC): Effective Price Level Date:		2024 1 OCT 23	TOTAL (\$K) J	Mid-Point Date P	INFLATED (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
		COST (\$K) C	CNTG (\$K) D	RISK BASED CNTG (%) E		ESC (%) G	COST (\$K) H	CNTG (\$K) I						
02	RELOCATIONS	\$1,706	\$0	0.0%	\$1,706	0.0%	\$1,706	\$0	\$1,706	2028Q1	10.9%	\$1,892	\$0	\$1,892
06	FISH & WILDLIFE FACILITIES	\$3,240	\$1,069	33.0%	\$4,309	0.0%	\$3,240	\$1,069	\$4,309	2028Q1	10.9%	\$3,594	\$1,215	\$4,809
07	POWER PLANT	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
12	NAVIGATION PORTS & HARBORS	\$287,521	\$94,882	33.0%	\$382,403	0.0%	\$287,521	\$94,882	\$382,403	2029Q2	13.3%	\$325,831	\$107,524	\$433,355
18	CULTURAL RESOURCE PRESERVATION	\$0	\$0	0.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		<b>\$292,467</b>	<b>\$95,951</b>	<b>32.8%</b>	<b>\$388,418</b>		<b>\$292,467</b>	<b>\$95,951</b>	<b>\$388,418</b>			<b>\$331,317</b>	<b>\$108,739</b>	<b>\$440,056</b>
01	LANDS AND DAMAGES	\$61,550	\$0	0.0%	\$61,550	0.0%	\$61,550	\$0	\$61,550	2027Q1	0.0%	\$61,550	\$0	\$61,550
01	NFS Admin Cost	\$240	\$0	0.0%	\$240	0.0%	\$240	\$0	\$240	2027Q1	8.0%	\$259	\$0	\$259
30	FED Admin Cost	\$190	\$0	0.0%	\$190	0.0%	\$190	\$0	\$190	2027Q1	8.0%	\$205	\$0	\$205
30	PLANNING, ENGINEERING & DESIGN													
1.0%	Project Management	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2027Q2	10.9%	\$3,245	\$1,071	\$4,316
2.0%	Planning & Environmental Compliance	\$5,849	\$1,930	33.0%	\$7,779	0.0%	\$5,849	\$1,930	\$7,779	2027Q2	10.9%	\$6,489	\$2,141	\$8,630
7.0%	Engineering & Design	\$20,473	\$6,756	33.0%	\$27,229	0.0%	\$20,473	\$6,756	\$27,229	2027Q2	10.9%	\$22,712	\$7,495	\$30,207
1.0%	Reviews, ATRs, IEPRs, VE	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2027Q2	10.9%	\$3,245	\$1,071	\$4,316
1.0%	Life Cycle Updates (cost, schedule, risks)	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2027Q2	10.9%	\$3,245	\$1,071	\$4,316
1.0%	Contracting & Reprographics	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2027Q2	10.9%	\$3,245	\$1,071	\$4,316
1.0%	Engineering During Construction	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2029Q2	17.9%	\$3,449	\$1,138	\$4,587
1.0%	Planning During Construction	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2029Q2	17.9%	\$3,449	\$1,138	\$4,587
0.5%	Project Operations	\$1,462	\$482	33.0%	\$1,944	0.0%	\$1,462	\$482	\$1,944	2027Q2	10.9%	\$1,622	\$535	\$2,157
1.0%	Adaptive Management and Monitoring	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2026Q4	10.9%	\$3,245	\$1,071	\$4,316
31	CONSTRUCTION MANAGEMENT													
0.0%	Construction Management	\$17,548	\$5,791	33.0%	\$23,339	0.0%	\$17,548	\$5,791	\$23,339	2029Q2	17.9%	\$20,693	\$6,829	\$27,522
0.0%	Project Operation:	\$0	\$0	33.0%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
1.0%	Project Management	\$2,925	\$965	33.0%	\$3,890	0.0%	\$2,925	\$965	\$3,890	2029Q2	17.9%	\$3,449	\$1,138	\$4,587
<b>CONTRACT COST TOTALS:</b>		<b>\$423,179</b>	<b>\$118,633</b>		<b>\$541,812</b>		<b>\$423,179</b>	<b>\$118,633</b>	<b>\$541,812</b>			<b>\$471,420</b>	<b>\$134,508</b>	<b>\$605,928</b>



Project: OHTB Schedule final 8J Date: Mon 1/8/24	Task	Project Summary	Manual Task	Start-only	Deadline
Split	Inactive Task	Manual Summary Rollup	Duration-only	Finish-only	Progress
Milestone	Inactive Milestone	Manual Summary	Manual Summary	External Tasks	Manual Progress
Summary	Inactive Summary			External Milestone	