# CALIFORNIA TROUT INC.


# EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT ON


# THE WILDLANDS CONSERVANCY'S EEL RIVER ESTUARY PRESERVE

**65% DESIGN PLANS** 

**MARCH 2017** 







Revision Note: \* indicates signatures on original issue of drawir

# **TIDAL DATUM TABLE**

OUTER MARSH TIDAL DATUM	ELEVATION FT - NAVD 1988
MEAN HIGHER HIGH WATER (MHHW)	6.52
MEAN HIGH WATER (MHW)	5.83
MEAN TIDE LEVEL (MTL)	3.73
MEAN LOW WATER (MLW)	1.64
MEAN LOWER LOW WATER (MLLW)	0.98

SOURCE: KAMMAN HYDROLOGY & ENGINEERING DRAFT HYDRAULIC DESIGN REPORT, JUNE

APPROX. EARTHWORK QUANTITIES	

EARTHWORK TYPE	Cut [CY]	Fill (CY)
CHANNEL/SLOUGH EXCAVATION	148,100	
SEDIMENT MANAGEMENT AREA EXCAVATION	151,000	
ACCESS ROADS		13,000
BERM		6,500
BACKFILL AND FILL IN UPLAND SEDIMENT REUSE AREA (APPX 6 FT DEPTH)		279,600
DUNE RECONFIGURATION	3,000	3,000
TOTAL	302,100	302,100

POWER POLE

# **DESIGN INFORMATION PROVIDED BY OTHERS**

- DESIGN DEVELOPED BASED ON DRAFT HYDRAULIC DESIGN REPORT PREPARED BY KAMMAN HYDROLOGY & ENGINEERING, JUNE 2016 AND BASIS OF DESIGN REPORT PREPARED BY GHD, MARCH 2017.
- 2. GEOTECHNICAL INVESTIGATION PROVIDED BY LACO ASSOCIATES, DATE: DEC. 12, 2016
- EXISTING TIDE GATE STRUCTURE DRAWINGS STAMPED AND SIGNED BY JOHN BURNS

# TOPOGRAPHIC SURVEY NOTES

- TOPOGRAPHIC DATA IS BASED ON NOAA LIDAR AND SUPPLEMENTED BY LACO ASSOCIATES (2013) AND GRAHAM MATTHEWS & ASSOCIATES (2016).
- 2. HORIZONTAL DATUM: NAD 83. CALIFORNIA ZONE 1, U.S. SURVEY FEET, VERTICAL DATUM NAVD 88. SEE HORIZONTAL CONTROL SHEETS C-XXX FOR MORE INFORMATION.

## **UTILITY NOTES**

- THE LOCATION FOR UTILITIES ON THESES PLANS IS APPROXIMATE ONLY. IT SHALL BE THE RESPONSIBILTY OF THE CONTRACTOR TO VERIFY LOCATION, DEPTH AND HEIGHT. THEIR VERIFICATION SHALL BE COORDINATED BY THE CONTRACTOR WITH THE APPROPRIATE UTILITY COMPANY, A MINIMUM OF SEVENTY-TWO HOURS BEFORE BEGINING IN ANY AREA. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT NORTH (USA), AT 1-800-227-2600, TO DETERMINE LOCATIONS OF EXISTING LITH LITES. THE CONTRACTOR SHALL COOPERATE WITH LITH ITY OWNERS TO EXPEDITE THE RELOCATION OR ADJUSTMENT OF THEIR UTILITIES TO MINIMIZE INTERRUPTION OF SERVICE AND DUPLICATION OF WORK. THE CONTRACTOR SHALL EXERCISE CARE WHEN WORKING NEAR EXISTING UTILITIES AND SHALL BE RESPONSIBLE FOR ALL DAMAGE. BREAKS, AND/OR LEAKS. IF DAMAGE OCCURS, THE CONTRACTOR SHALL REPAIR UTILITY AT NO ADDITIONAL EXPENSE TO THE HCRCD.
- PRIOR TO RELOCATION, ALL UTILITIES TO BE RELOCATED WITHIN THE COUNTY RIGHT OF WAY SHALL BE STAKED AND APPROVED BY THE COUNTY, IF NEEDED.
- LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE PLOTTED FROM RECORD INTERPOLATION OF PHYSICAL EVIDENCE ON THE SITE AND ARE SUBJECT TO FIELD VERIFICATION BY THE CONTRACTOR.
- CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO UTILITIES, FEATURES, AND STRUCTURES LOCATED ON THE SITE. LOCATE, PROTECT, AND AVOID DISRUPTION OF ALL ABOVE AND BELOW GRADE UTILITIES DURING CONSTRUCTION.
- CONSTRUCTION ACTIVITY WILL TAKE PLACE IN THE VICINITY OF ELECTRIC LINES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO BE AWARE OF, AND OBSERVE, THE MINIMUM CLEARANCES FOR WORKERS AND EQUIPMENT OPERATING NEAR HIGH VOLTAGE ELECTRIC LINES AS SET OUT IN THE HIGH VOLTAGE SAFETY ORDERS OF THE CALIFORNIA DIVISION OF INDUSTRIAL SAFETY AS WELL AS OTHER APPLICABLE SAFETY

# **DEFINITION OF "LIMITS" SHOWN ON THE PLANS**

APPROXIMATE LIMITS OF GRADING:
DEFINES THE APPROXIMATE LIMITS OF PERMANENT GRADING OR LAND DISTURBANCE (EXCAVATING/FILLING).

## APPROXIMATE LIMITS OF CONSTRUCTION DISTURBANCE:

DEFINES THE APPROXIMATE LIMITS OF TEMPORARY CONSTRUCTION DISTURBANCES AND INCLUDES POTENTIAL HAUL ROADS, STAGING AREAS, AND STOCKPILING AREAS THAT SHALL BE RESTORED BACK TO PRE-CONTRUCTION CONDITIONS.

# ABBREVIATIONS:


NOTE: CONTACT ENGINEER FOR ABBREVIATIONS NOT LISTED.

AGGREGATE BASE

AC	ASPHALT CONCRETE	FS	FINISH SURFACE	PT	POINT OF TANGENT
ACP	ASBESTOS CONCRETE PIPE	FT	FOOT OR FEET	PCV	POLYVINYL CHLORIDE
AGG	AGGREGATE			PVI	POINT OF VERTICAL INTERSECTION
APPROX	APPROXIMATE	G	GAS		
		GALV	GALVANIZED	R	RIGHT
В	BERM	GB	GRADE BREAK	RB	RUSS BERM
BFP	BACKFLOW PREVENTER	GR	GRADE	RC	RUSS CREEK
BMPS	BEST MANAGEMENT PRACTICES	GRD	GROUND	REQ'D	REQUIRED
				RCP	REINFORCED CONCRETE
CS	CENTERVILLE SLOUGH	H. HORZ	HORIZONTAL		PIPE
CB	CENTERVILLE BERM	HMMP	HABITAT MITIGATION AND MONITORING PLAN	RSP	ROCK SLOPE PROTECTION
CBC	CALIFORNIA BUILDING CODE	HYD	FIRE HYDRANT	RT	RIGHT
CL, C	CENTER LINE			RWL	RAIN WATER LEADER
CLR	CLEAR	IMB	INNER MARSH BERM	R/W	RIGHT OF WAY
CM	CONSTRUCTION MANAGER	IMS	INNER MARSH SLOUGH		
CMP	CORRUGATED METAL PIPE	INV/IE	INVERT ELEVATION	SCHED	SCHEDULE
CO	CLEANOUT	INTX	INTERSECTION	SD	STORM DRAIN
CONC	CONCRETE	IR	IRRIGATION	SET	SOUTHEAST TRIBUTARY
CONT'D	CONTINUED			SF	SQUARE FOOT/FEET
COORD	COORDINATE	JCT	JUNCTION	SHT	SHEET
COR	CONTRACTING OFFICER'S REPRESENTATIVE	001	0011011011	SIM	SIMILAR
			LENGTH		
COR	CORNER	L	LENGTH	SMA	SEDIMENT MANAGEMENT AREA
CPP	CORRUGATED PLASTIC PIPE	LF	LINEAR FOOT/FEET	SS	SANITARY SEWER
CU	CUBIC	LP	LOW POINT	SSFM	SANITARY SEWER FORCE
CY	CUBIC YARD	LT	LEFT		MAIN
0.	00510 1711.5	LWD	LARGE WOOD	SST	STAINLESS STEEL
DIA	DIAMETED	LIVE	OR LARGE WOODY DEBRIS		
DIA	DIAMETER		OR LARGE WOOD! DEBRIS	STA	STATION
DTL	DETAIL			STL	STEEL
DI	DROP (DRAINAGE) INLET	MAX	MAXIMUM	SWPPP	STORM WATER POLLUTION PREVENTION PLAN
DI	DUCTILE IRON	MIN	MINIMUM	SY	SQUARE YARD
DWG	DRAWING	MISC	MISCELLANEOUS		
50	5.0	MTR	MUTED TIDEGATE REGULATOR	Т	TELEPHONE
_	FAST	IVITIX	MOTED TIDEGATE REGULATOR		
E	EAST			TBD	TO BE DETERMINED
(E)	EXISTING	N	NORTHING	TBM	TEMPORARY BENCH MARK
EA	EACH	NO.	NUMBER	TYP	TYPICAL
EC	END CURVE	(N)	NEW		
ĒĒ	EACH FACE	NIC	NOT IN CONTRACT	UNO	UNLESS NOTED OTHERWISE
EL. ELEV	ELEVATION	NTS	NOT TO SCALE	0110	ONEEGO NOTED OTTENMOL
		INIO	NOT TO SCALE		VEDTICAL
EG	EXISTING GRADE			V, VERT	VERTICAL
ENGR	ENGINEER	OC	ON CENTER		
EP	EDGE PAVING	OD	OUTSIDE DIAMETER	W/	WITH
EQ	EQUAL	OHE	OVERHEAD ELECTRIC	W	WIDE
ER	EDGE ROAD			W	WIDTH
		PE	POLYETHYLENE	w	
EVC	END VERTICAL CURVE				WEST
EW	EACH WAY	PI	POINT OF INTERSECTION	WM	WATER MAIN
		PL, P	PROPERTY LINE	WV	WATER VALVE
FG	FINISH GRADE	PLCS	PLACES		
FIN	FINISH	POC	POINT OF CONNECTION	XS	CROSS SECTION
				,,,,	
				YD	YARD
				עז	TARD

FLOW LINE

					Reuse of Documents This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	BAR IS ONE INCH ON ORIGINAL DRAWING O 1"
						65% SUBMITTAL
	-			-		MARCH. 2017
ing or last revision of drawing	Drawn	Job Manager	Project Director	Date		WAITOIT, 2017
ard	Con	LEilo No: r	:\LIS\Eurak	a\Drojecte\I	agacu/Drojecte/1000208 caltrout/8/10882 aren acceuetament	nancement\06_CAD\Sheets\1000298_A1_G1.dwg



CALTROUT

EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT

LEGEND, ABBREVIATIONS, **AND GENERAL NOTES** 

ntract No. 84-10882

This Drawing shall not be used for Construction unless Signed and Sealed For Construction and Sealed For Construction.

Sht 2 of 44

## GENERAL AND GRADING NOTES

- PROJECT REQUIRES A CLASS A GENERAL ENGINEERING CONTRACTOR'S LICENSE IN
- CONTRACTOR SHALL FIELD VERIFY ALL EXISTING SITE CONDITIONS PRIOR TO THE COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES TO THE CONSTRUCTION MANAGER. SHOULD EXISTING CONDITIONS DIFFER FROM THOSE SHOWN OR INDICATED, OR IF IT APPEARS THAT THESE PLANS DO NOT ADEQUATELY DETAIL THE WORK TO BE DONE, CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER PRIOR TO CONTINUING WITH ANY RELATED WORK, NO ALLOWANCE WILL MANAGER FRIOR TO CONTINUES WITH ANY RELATED WORK. NO ALCOWANCE WITH BE MADE ON CONTRACTOR'S BEHALF FOR ANY EXTRA EXPENSE RESULTING FROM FAILURE OR NEGLECT IN DETERMINING THE CONDITIONS UNDER WHICH WORK IS TO BE PERFORMED. NOTED DIMENSIONS TAKE PRECEDENCE OVER SCALE.
- QUANTITIES OF ITEMS, LENGTH OF PROJECT, AND SITE CONDITIONS SHOWN IN THE PLANS ARE APPROXIMATE, ALL MATERIALS SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR UNLESS OTHERWISE NOTED.
- CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD THE OWNER, GHD, AND THEIR REPRESENTATIVES HARMLESS FROM ANY AND ALL LIABILITY, REAL AND/OR ALLEGED, IN CONJUNCTION WITH THE PERFORMANCE OF THIS PROJECT.
- CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY AND ALL DAMAGES TO EXISTING STRUCTURES, ROADS, AND UTILITIES DURING CONSTRUCTION. ALL DAMAGE SHALL BE RESTORED TO EQUAL OR BETTER CONDITION AT THE CONTRACTOR'S EXPENSE.
- A SET OF SIGNED CONTRACT DOCUMENTS (PLANS AND SPECIFICATIONS) WILL BE KEPT AT ALL TIMES AT THE JOB SITE ON WHICH ALL CHANGES OR VARIATIONS IN THE WORK ARE TO BE RECORDED AND/OR CORRECTED DAILY AND SUBMITTED TO THE OWNER WHEN THE WORK TO BE DONE IS COMPLETED.
- CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER AT LEAST 72 HOURS IN ADVANCE OF COMMENCEMENT OF ANY PART OF THE WORK AND SHALL COORDINATE CONSTRUCTION SCHEDULE UPDATES ACCORDINGLY.
- THE DESIGN FEATURES SHOWN ON THESE DESIGN PLANS SHALL NOT BE ALTERED. OR MODIFIED IN ANY WAY DURING CONSTRUCTION WITHOUT THE EXPRESSED WRITTEN DIRECTION AND APPROVAL OF THE CONSTRUCTION MANAGER.
- ANY INFORMATION DERIVED FROM THE MAPS, PLANS, SPECIFICATIONS, PROFILES, DRAWINGS OR FROM THE ENGINEER WILL NOT RELIEVE THE CONTRACTOR FROM ANY RISK OR FROM FULFILLING THE TERMS OF THE CONTRACT
- NO WORK SHALL BE PERFORMED OUTSIDE OF THE DESIGNATED AREAS WITHOUT THE APPROVAL OF THE CONSTRUCTION MANAGER.
- THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ADDITIONAL STAGING AREAS WITH THE OWNER BEYOND WHAT IS SHOWN ON THE PLANS
- UPON COMPLETION OF THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL LEAVE THE PROJECT AREA FREE OF DEBRIS AND UNUSED MATERIAL U.N.O. ALL DAMAGE CAUSED BY THE CONTRACTOR SHALL BE RESTORED TO AN "AS GOOD OR
- THE CONTRACTOR SHALL PROTECT EXISTING SURVEY MONUMENTS WITHIN WORK LIMITS. ANY MONUMENT DAMAGED BY THE CONTRACTOR SHALL BE RESET IN ACCORDANCE WITH THE CALIFORNIA PROFESSIONAL LAND SURVEYORS ACT
- THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE CONSTRUCTION MANAGER UPON DISCOVERING DISCREPANCIES, ERRORS OR OMISSIONS IN THE PLANS. PRIOR TO PROCEEDING, THE DISCREPANCY SHALL BE RESOLVED TO THE SATISFACTION OF THE CONSTRUCTION MANAGER.
- HOURS OF WORK: THE CONTRACTOR SHALL CONDUCT ALL WORK BETWEEN THE HOURS OF 7:00 A.M. AND 7:00 P.M., MONDAY THROUGH FRIDAY. A WORKING DAY IS DEFINED AS MONDAY THROUGH FRIDAY EXCLUDING WEEKENDS AND HOLIDAYS. WEEKEND AND HOLIDAY WORK WILL ONLY BE CONDUCTED AFTER PRIOR AUTHORIZATION FROM THE OWNER. IF WEEKEND/HOLIDAY WORK IS AUTHORIZED, IT SHALL BE LIMITED TO 9:00 A.M. - 6 P.M. EQUIPMENT DELIVERY SHALL BE DURING
- CONTRACTOR SHALL MAINTAIN DAILY COMMUNICATIONS WITH THE CONSTRUCTION MANAGER TO DISCUSS DETAILS OF IMPLEMENTATION, ORDER OF WORK, METHODS OF MINIMIZING ENVIRONMENTAL IMPACTS AND OTHER RELEVANT COMPONENTS OF CONSTRUCTION. CONTRACTOR AND OWNER SHALL MEET DAILY ON-SITE TO DISCUSS PROJECT DETAILS.
- ANY MODIFICATIONS FROM PLANS NEED TO BE COMPLETED AND/OR APPROVED BY THE CONSTRUCTION MANAGER PRIOR TO IMPLEMENTATION
- THE CONTRACTOR SHALL COMPLETELY REVIEW, BE FAMILIAR WITH, AND ADHERE TO THE TERMS OF ALL PERMITS AND AGENCY APPROVALS FOR THIS PROJECT. THE OWNER WILL BE RESPONSIBLE FOR SECURING AND PROVIDING TO THE CONTRACTOR COPIES OF ALL PERMITS, CERTIFICATIONS, OR AUTHORIZATIONS UNLESS NOTED OTHERWISE, FROM THE FOLLOWING AGENCIES INCLUDING, BUT

NOT LIMITED TO: COUNTY OF HUMBOLDT U.S. ARMY CORPS OF ENGINEERS. THE CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD SECTION 401, THE U.S. FISH AND WILDLIFE SERVICE, THE NATIONAL MARINE FISHERIES SERVICE, CALIFORNIA DEPARTMENT OF FISH AND WILDLIFE, AND THE CALIFORNIA COASTAL COMMISSION. COPIES OF ALL PERMITS WILL BE AVAILABLE UPON REQUEST AND SHALL REMAIN ONSITE THROUGHOUT THE DURATION OF CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP). THE CONTRACTOR IS RESPONSIBLE TO OBTAIN A COUNTY OF HUMBOLDT ENCROACHMENT PERMIT.

- PROJECT PERMITS SHALL REMAIN ON SITE AT ALL TIMES.
- NO SHUTDOWN OF THE PROJECT SITE IS ANTICIPATED. HOWEVER, UNFORESEEABLE CONDITIONS INCLUDING BUT NOT LIMITED TO FIRE, GEO-HAZARD CONDITIONS, OR RAINS COULD REQUIRE THE CONSTRUCTION MANAGER TO SUSPEND CONSTRUCTION ACTIVITIES AT ALL OR PART OF THE SITE FOR SAFETY REASONS AT NO COST TO THE OWNER OR THEIR REPRESENTATIVES
- PERFORM GRADING IN ACCORDANCE WITH THE LATEST EDITION OF THE CALIFORNIA BUILDING CODE AND APPLICABLE HUMBOLDT COUNTY REGULATIONS.
- THE CONTRACTOR SHALL BE AWARE OF THE SOFT AND SATURATED SOI CONDITION THAT MAY BE ENCOUNTERED DURING THE CONSTRUCTION. SEE
- IN THE EVENT CULTURAL RESOURCES (I.E., HISTORICAL, ARCHAEOLOGICAL, AND PALEONTOLOGICAL RESOURCES, AND HUMAN REMAINS) ARE DISCOVERED DURING CONSTRUCTION ACTIVITIES. WORK SHALL BE HALTED. A QUALIFIED ARCHEOLOGIST SHALL BE CONSULTED FOR AN ON-SITE EVALUATION. IF HUMAN BURIALS OR HUMAN REMAINS ARE ENCOUNTERED, THE CONTRACTOR SHALL ALSO NOTIFY THE COUNTY CORONER
- SHOULD GRADING OPERATIONS ENCOUNTER HAZARDOUS MATERIALS, OR WHAT APPEAR TO BE HAZARDOUS MATERIALS, STOP WORK IN THE AFFECTED AREA IMMEDIATELY AND CONTACT THE CONSTRUCTION MANAGER OR THE APPROPRIATE AGENCY FOR FURTHER INSTRUCTION.
- ALL CONSTRUCTION SITES AND HAUL ROADS SHALL BE MAINTAINED, AS NECESSARY, TO MINIMIZE THE EMISSION OF DUST AND PREVENT CREATION OF NUISANCE TO ADJACENT PROPERTIES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL CONSTRUCTION ADEQUATE SHORING, BRACING, TIES, AND SUPPORTS SHALL BE USED TO PROVIDE PROPER TEMPORARY INTEGRITY DURING ALL PHASES OF CONSTRUCTION.
- ALL EXISTING PASTURE AND STAGING/STOCKPILE AREAS WHICH ARE DISTURBED BY CONSTRUCTION OR EARTHWORK OPERATIONS SHALL BE RETURNED TO ORIGINAL EXISTING CONDITIONS OR BETTER
- ALL DITCHES, SWALES, CULVERTS, ETC. SHOULD BE CONSIDERED ACTIVE STORM CONVEYANCES UNLESS OTHERWISE INDICATED. CONTRACTOR IS RESPONSIBLE FOR ADDRESSING STORM WATER DRAINAGE AND DEWATERING OF WORK AREAS DURING CONSTRUCTION
- DURING WET WEATHER PERIODS, CONTRACTOR IS RESPONSIBLE FOR SEQUENCING CONSTRUCTION IN A MANNER TO MINIMIZE IMPACT ON OPEN EARTHWORK AND COMPACTION OPERATIONS.
- THE OWNER'S REPRESENTATIVE WILL PROVIDE GRADING INSPECTION PER HUMBOLDT COUNTY CODE SECTION 331-14 H.5 AND UPON COMPLETION OF WORK THE OWNER WILL PROVIDE REPORT PER HUMBOLDT COUNTY CODE
- ANY MATERIAL NOT UTILIZED ON SITE SHALL BE REMOVED FROM SITE AND DISPOSED OF IN A LEGAL MANNER CONSISTENT WITH APPLICABLE REGULATIONS SUCH AS COUNTY GRADING ORDINANCES AND PROJECT PERMITS, CONTRACTOR IS RESPONSIBLE FOR PROPER LEGAL DISPOSAL OF ALL MATERIALS TAKEN FROM SITE
- EXISTING VEGETATION SHALL BE PROTECTED AND LEFT UNDISTURBED AS MUCH AS PRACTICAL. EXISTING NATIVE PLANTS IN AREAS TO BE DISTURBED WILL BE FLAGGED BY PROJECT BOTANIST FOR SALVAGE AND STORAGE IN TEMPORARY NURSERY TO BE REPLANTED AFTER FINAL GRADING HAS OCCURRED.
- THE CONTRACTOR SHALL NOTE THAT PREHISTORIC MATERIALS THAT COULD BE ENCOUNTERED INCLUDE: OBSIDIAN AND CHERT FLAKES OR CHIPPED STONE
  TOOLS, GRINDING IMPLEMENTS, (E.G., PESTLES, HANDSTONES, MORTARS, SLABS),
  BEDROCK OUTCROPS AND BOULDERS WITH MORTAR CUPS, LOCALLY DARKENED MIDDEN DEPOSITS OF SHELL DIFTARY BONE AND HUMAN BURIALS HISTORIC MATERIALS THAT COULD BE ENCOUNTERED INCLUDE: CERAMICS/POTTERY, GLASS, METAL, CAN AND BOTTLE DUMPS, CUT BONE, BARBED WIRE FENCES, BUILDING PADS, STRUCTURES, TRAILS/ROADS, RAILROAD RAILS AND TIES, TRESTLES, ETC. IN THE EVENT CULTURAL RESOURCES (I.E., HISTORICAL, ARCHAEOLOGICAL, AND PALEONTOLOGICAL RESOURCES, AND HUMAN REMAINS) ARE DISCOVERED DURING GRADING OR OTHER CONSTRUCTION ACTIVITIES, WORK SHALL BE HALTED WITHIN A 100 FOOT RADIUS OF THE FIND. A QUALIFIED ARCHEOLOGIST SHALL BE CONSULTED FOR AN ON-SITE EVALUATION. ADDITIONAL MITIGATION MAY BE REQUIRED BY THE COUNTY PER THE ARCHEOLOGIST'S RECOMMENDATIONS. IF HUMAN BURIALS OR HUMAN REMAINS ARE ENCOUNTERED. THE CONTRACTOR SHALL ALSO NOTIFY THE COUNTY CORONER

- THE CONTRACTOR SHALL SUBMIT A DUST CONTROL PLAN FOR REVIEW AND THE DUST CONTROL PLAN SHALL INCLUDE CASOA BMPS.
- BIOLOGICAL RESTRICTIONS WILDLIFE: PRIOR TO START OF CONSTRUCTION, THE ENVIRONMENTAL MONITOR OR REPRESENTATIVES WILL GIVE CONTRACTOR'S STAFF A PRESENTATION REGARDING SPECIAL STATUS SPECIES AND RESTRICTIONS REQUIRED IN TERMS OF CONSTRUCTION START CLEARANCE SURVEYS, AND CONSTRUCTION MONITORING, BECAUSE OF THE HIGH NUMBER OF SPECIAL STATUS SPECIES THAT OCCUR IN THE AREA, MOST, IF NOT ALL, ELEMENTS MAY NOT BE IMPLEMENTED UNTIL AFTER CERTAIN DATES AND AFTER CONSTRUCTION CLEARANCE SURVEYS HAVE BEEN PERFORMED AND COMPLETED.
- REQUIRED CLEARANCE SURVEYS: IF SPECIAL STATUS SPECIES ARE LOCATED DURING CLEARANCE SURVEYS, REQUIRED ACTIONS COULD INCLUDE, BUT ARE NOT LIMITED TO: 1) TEMPORARY DELAY IN CONSTRUCTION WHILE SPECIES ARE RELOCATED BY QUALIFIED BIOLOGISTS; OR 2) DELAY OF CONSTRUCTION UNTIL PREDETERMINED DATE A OF BREEDING SEASON WITH NO CONSTRUCTION OCCURRING WITHIN A BUFFER ZONE AROUND THE AREA WHERE SPECIES WERE
- SCHEDULING OF REQUIRED CLEARANCE SURVEYS: AT THE START OF CONSTRUCTION, THE CONTRACTOR WILL BE REQUIRED TO PROVIDE A CONSTRUCTION SCHEDULE ON A WEEKLY BASIS THE CONTRACTOR CONSTRUCTION SCHEDULE: ON A WEERLY BASIS, THE CONTRACTOR,
  CONSTRUCTION MANAGER, AND ENVIRONMENTAL MONITOR WILL MEET AND
  DISCUSS THE STATUS OF THE PROJECT AND UPDATES TO SCHEDULES. CLEARANCE
  SURVEYS WILL BE SCHEDULED WITH THE BASIS OF THIS REVISED WEEKLY SCHEDULE. THE CONTRACTOR WILL NOT BE ALLOWED TO START CONSTRUCTION UNTIL ALL THE APPROVED CLEARANCE SURVEYS HAVE BEEN PERFORMED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE THE ENVIRONMENTAL MONITOR AND UPDATED SCHEDULE THAT ALLOW FOR ADEQUATE TIME TO SCHEDULE THE CLEARANCE SURVEYOR SURVEYS REQUIRED

## **DEWATERING NOTES**

- ALL IN-STREAM CONSTRUCTION ACTIVITIES WITHIN THE EREP, INCLUDING CHANNEL EXCAVATION AND DEWATERING, MAY BE CONDUCTED BETWEEN 15 JUNE AND 15 OCTOBER AND IN ACCORDANCE TO ALL PROJECT PERMITS AND RELATED CONDITIONS OF APPROVAL.
- WHERE DEWATERING IS REQUIRED, A DEWATERING PLAN SHALL BE DEVELOPED BY THE CONTRACTOR AND SUBMITTED FOR APPROVAL BY THE CONSTRUCTION MANAGER TO MINIMIZE IMPACTS TO WATER QUALITY OF AQUATIC HABITATS IN THE PROJECT AREA. IN GENERAL, COFFER DAMS AND/OR SHEET PILING ARE REQUIRED IN AREAS WHERE FULL DEWATERING WILL BE CONDUCTED, WITH ADDITIONAL MEASURES TO REDUCE WATER QUALITY IMPACTS DURING CONSTRUCTION DEWATERING, INSTALLATION OF SILT FENCING AND TURRIDITY CURTAINS MAY ALSO BE REQUIRED TO CONTROL SEDIMENT. AT THE END OF CONSTRUCTION, THE CONTRACTOR SHALL REMOVE ALL BYPASSES, COFFER DAMS, SHEET PILING, TURBIDITY CURTAINS, AND SILT FENCING AND RESTORE THE SLOUGH CHANNEL BOTTOM IN THOSE LOCATIONS TO ITS PRE-CONSTRUCTION CONTOURS UNLESS OTHERWISE DESIGNATED BY
- IN SCHEDULING DEWATERING ACTIVITIES. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER A MINIMUM OF TEN (10) DAYS PRIOR TO PLANNED DEWATERING ACTIVITY TO ENSURE THAT THE ENVIRONMENTAL MONITOR CAN SCHEDULE THE APPROPRIATE STAFF FOR CLEARANCE SURVEYS, MONITORING, AND RELOCATION OF NATIVE AQUATIC VERTEBRATES AND LARGE INVERTEBRATES TO NEARBY SUITABLE HABITAT PRIOR TO IMPLEMENTATION OF CONSTRUCTION.
- COFFER DAMS AND FISH SCREENS MUST BE INSTALLED AND FISH REMOVED FROM THE PROJECT AREA. CONTRACTOR SHALL COORDINATE WITH FISHERIES BIOLOGIST RESPONSIBLE FOR REMOVING FISH FOR SCHEDULING PLACEMENT OF FISH SCREENS, COFFER DAM AND DEWATERING PLAN. FISHERIES
  BIOLOGIST IS RESPONSIBLE FOR SITING THE BEST LOCATION FOR FISH
- ANY PUMPS USED ON-SITE (DEWATERING ETC) SHALL BE PLACED ON ABSORBENT PADS. THE CONTRACTOR SHALL HAVE SPILL CONTAINMENT MATERIALS LOCATED AT THE SITE, WITH OPERATORS TRAINED IN SPILL CONTROL PROCEDURES. PUMPS SHALL BE SCREENED TO PREVENT INTAKE OF SALMON, TIDEWATER GOBY, AND OTHER SPECIES.

## TRAFFIC CONTROL AND COUNTY ENCROACHMENT NOTES:

- ALL FUELING, EQUIPMENT MAINTENANCE, STAGING AND CONSTRUCTION MANAGEMENT SHALL BE LOCATED OUTSIDE THE COUNTY ROAD RIGHT OF WAY. NO CONSTRUCTION MATERIALS (CONSTRUCTION TRAILERS, STORAGE CONTAINERS, EQUIPMENT, ETC.) SHALL BE ALLOWED WITHIN THE COUNTY
- ALL EQUIPMENT AND LOADS OVER WEIGHT, LENGTH, WIDTH LIMITS WILL REQUIRE A TRANSPORTATION PERMIT FROM THE COUNTY OF HUMBOLDT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING THESE PERMITS IF NECESSARY AND PAYING ALL PERMIT FEES.
- ALL PUBLIC ROADS AND BRIDGES IMPACTED BY THE CONSTRUCTION ACTIVITIES SHALL BE CLEARED OF ALL SEDIMENT AND DEBRIS ON A DAILY BASIS OR AS DIRECTED BY COUNTY OF HUMBOLDT AND THE ENGINEER
- ALL ACTIVE CONSTRUCTION AREAS SHALL BE WATERED AT A RATE SUFFICIENT TO KEEP SOIL MOIST AND PREVENT FORMATION OF WIND-BLOWN DUST.
- ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS SHALL BE COVERED, OR ALL TRUCKS SHALL BE REQUIRED TO MAINTAIN AT LEAST 2 FEET OF FREEBOARD, OR SHALL HAVE MOISTURE CONTENT, OR LITTLIZE SOME OTHER METHODS THAT PREVENTS GENERATION OF FUGITIVE DUST
- EXPOSED STOCKPILES OF DIRT. SAND, AND SIMILAR MATERIAL SHALL BE SOIL BINDERS AS NECESSARY TO PREVENT GENERATION OF FUGITIVE DUST
- TRAFFIC SPEEDS ON UNPAVED ROADS SHALL BE LIMITED TO 10 MILES PER
- OUTDOOR DUST-PRODUCING ACTIVITIES SHALL BE SUSPENDED WHEN HIGH VINDS (>15 MPH) CREATE VISIBLE DUST PLUMES IN SPITE OF CONTROL
- REASONABLE PRECAUTIONS SHALL BE TAKEN TO PREVENT THE ENTRY OF UNAUTHORIZED VEHICLES INTO THE CORRIDOR DURING NON-WORK HOURS.
- THE CONTRACTOR SHALL COMPLY WITH AIR QUALITY MANAGEMENT DISTRICT (AOMD) RULE 420 (PARTICULATE MATTER) AND RULE 430 (FLIGHTIVE DUST MANAGEMENT PROGRAM FOR PARTICULATE MATTER.
- ALL EQUIPMENT SHALL OPERATE WITH FACTORY-EQUIPPED MUFFLERS.
- TO THE DEGREE FEASIBLE, HAUL TRUCKS SHALL USE HAUL ROUTES ALONG THE EXISTING CHANNEL EXCAVATION PATH, OR ALONG ROADWAYS DISTANT FROM SENSITIVE RECEPTORS

L									
							Reuse of Documents This document and the ideas and designs incorporated	BAR IS ONE INCH ON	
1							herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	ORIGINAL DRAWING	
							in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	0 1"	
L								65% SUBMITTAL	
ı	-	-	-			-		MARCH, 2017	
Ī	ю	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		WARGIT, 2017	
-	Plot Date: 13 March 2017, 3-15 PM Pintled by Reentan Burd Cast District No. Pul (Signific Act) Project Significant Cast Cast District No. Pul (Signific Act) Project Significant Cast District No. Pul (Signific Act) Project Signific No. Pul (Signific Act) Project Significant Cast District No. Pul (Signific Act) Project Significant Cast								



Designer GK, JS, BV Drafting JS Design Check JS roject Director) MARCH 9, 2017 This Drawing shall not be used AS SHOWN

CALTROUT EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT **GENERAL NOTES CONTINUED** 

ontract No. 84-10882

for Construction unless Signed Ansi D Drawing No: C-003

## EROSION, SEDIMENT, POLLUTION AND WASTE CONTROL NOTES

- THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE NATIONAL POLITIANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL PERMIT WASTE DISCHARGE REQUIREMENTS FOR DISCHARGES OF STORM WATER RUNOFF ASSOCIATED WITH CORRIDOR CONSTRUCTION ACTIVITY. THE SITE DISTURBANCE IS GREATER THAN 1 ACRE, THEREFORE THE CONTRACTOR IS RESPONSIBLE TO COMPLY WITH THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR THE PROJECT. THE SWPPP SHALL BE DEVELOPED BY A QUALIFIED SWPPP DEVELOPER (QSD) AND BMP MONITORING AND REPORTING SHALL BE OVERSEEN BY A QUALIFIED SWPPP PRACTITIONER (QSP)
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MINIMIZE EROSION AND PREVENT THE TRANSPORT OF SEDIMENT TO THE ADJACENT STREAM AND SENSITIVE AREAS
- PERFORM EROSION PREVENTION AND SEDIMENT CONTROL IN ACCORDANCE WITH THE LATEST EDITION OF CHAPTER 33 OF THE CALIFORNIA BUILDING CODE, APPLICABLE HUMBOLDT COUNTY REGULATIONS, AND SECTION 20 OF THE CALTRANS STANDARD SPECIFICATIONS.
- AT A MINIMUM, THE CONTRACTOR SHALL EMPLOY THE FOLLOWING BEST MANAGEMENT PRACTICES (BMPS) AS DESCRIBED IN THE CURRENT CALTRANS STORM WATER QUALITY HANDBOOK AS NEEDED:

SS-2 PRESERVATION OF EXISTING VEGETATION SS-10 OUTLET PROTECTION/VELOCITY DISSIPATION DEVICES SC-1 SILT FENCE
NS-2 DEWATERING OPERATIONS

NS-3 PAVING AND GRINDING OPERATIONS NS-5 CLEAR WATER DIVERSION

NS-9 VEHICLE EQUIPMENT AND FUELING WM-1 MATERIALS DELIVERY AND STORAGE WM-2 MATERIAL USE WM-4 SPILL PREVENTION AND CONTROL WM-8 CONCRETE WASTE MANAGEMENT WM-9 SANITARY/SEPTIC WASTE MANAGEMENT

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIX ANY EROSION, SEDIMENT, POLLUTION, & WASTE CONTROL DEFICIENCIES IDENTIFIED BY THE OWNER OR THE OWNERS REPRESENTATIVE
- PRIOR TO FINAL ACCEPTANCE ALL DISTURBED AREAS OF THE SITE WILL BE VEGETATED OR PERMANENTLY STABILIZED AND ALL TEMPORARY SEDIMENT CONTROL MEASURES SHALL BE
- ALL DISTURBED EARTH AREAS SHALL BE MULCHED AND SEEDED PER THE RE-VEGETATION AND PLANTING SPECIFICATIONS.

- IF DISCREPANCIES OCCUR BETWEEN THESE NOTES, MATERIAL REFERENCED HEREIN OR MANUFACTURERS RECOMMENDATIONS, THEN THE MOST PROTECTIVE SHALL APPLY.
- PRESERVATION OF EXISTING VEGETATION SHALL OCCUR TO THE MAXIMUM EXTENT
- DISCHARGES OF POTENTIAL POLLUTANTS FROM CONSTRUCTION SITES SHALL BE PREVENTED USING SOURCE CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE. POTENTIAL POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO: SEDIMENT, TRASH, NUTRIENTS, PATHOGENS PETROLEUM HYDROCARBONS, METALS, CONCRETE, CEMENT, ASPHALT, LIME, PAINT, STAINS, GLUES, WOOD PRODUCTS, PESTICIDES, HERBICIDES, CHEMICALS, HAZARDOUS WASTE, SANITARY WASTE, VEHICLE OR EQUIPMENT WASH WATER, CIGARETTE BUTTS, AND CHI ORINATED WATER
- WHENEVER IT IS NOT POSSIBLE TO UTILIZE EROSION PREVENTION MEASURES, EXPOSED SLOPES SHALL EMPLOY SEDIMENT CONTROL DEVICES, SUCH AS FIBER ROLLS AND SILT FENCES. FIBER ROLLS AND SILT FENCES SHALL BE TRENCHED AND KEYED INTO THE SOIL AND INSTALLED ON CONTOUR. SILT FENCES SHALL BE INSTALLED APPROXIMATELY 2 TO 5 FEET FROM TOF OF SLOPE.
- 12. ENERGY DISSIPATERS SHALL BE INSTALLED AT STORM DRAIN OUTLETS WHICH MAY CONVEY STORM WATER FLOW LEADING TO SOIL EROSION.
- SOIL AND MATERIAL STOCKPILES SHALL BE PROPERLY PROTECTED TO MINIMIZE SEDIMENT AND POLLUTANT TRANSPORT FROM THE CONSTRUCTION SITE.
- 14 SOLID WASTE SUCH AS TRASH AND DEBRIS SHALL BE PLACED IN DESIGNATED COLLECTION AREAS OR CONTAINERS. THE CONSTRUCTION SITE SHALL BE CLEARED OF SOLID WASTE DAILY, OR AS NECESSARY, AND REGULAR REMOVAL AND PROPER DISPOSAL SHALL BE
- 15. PROPER APPLICATION, CLEANING AND STORAGE OF POTENTIALLY HAZARDOUS MATERIALS, SUCH AS PAINTS AND CHEMICALS, SHALL BE CONDUCTED TO PREVENT THE DISCHARGE OF
- 16. WHEN UTILIZED, TEMPORARY RESTROOMS AND SANITARY FACILITIES SHALL BE LOCATED AND MAINTAINED TO PREVENT THE DISCHARGE OF POLLUTANTS.

- 17 APPROPRIATE VEHICLE STORAGE FLIELING MAINTENANCE AND CLEANING AREAS SHALL BE DESIGNATED AND MAINTAINED TO PREVENT DISCHARGE OF POLLUTANT
- 18. ENTRANCE(S) TO THE CONSTRUCTION SITE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF POTENTIAL POLLUTANTS OFFSITE. POTENTIAL POLLUTANTS DEPOSITED ON PAVED AREAS WITHIN THE COUNTY RIGHT-OF-WAY, SUCH AS ROADWAYS AND SIDEWALKS, SHALL BE PROPERLY DISPOSED OF EACH WORKING DAY OR MORE FREQUENTLY AS NECESSARY
- 19. CHANGES TO THE STORM WATER POLLUTION PREVENTION PLAN MAY BE MADE TO RESPOND TO FIELD CONDITIONS. CHANGES SHALL BE NOTED ON THE PLAN WHEN MADE
- 20. BECAUSE COFFER DAMS WILL BE INSTALLED AND THE CHANNEL WILL BE DEWATERED PRIOR TO EXCAVATION, EQUIPMENT WILL NOT BE OPERATED DIRECTLY WITHIN TIDAL WATERS OR STREAM CHANNELS OF FLOWING STREAMS, PRIOR TO FISH REMOVAL EFFORTS BEING
- 21. SILT FENCES AND OR SILT CURTAINS WILL BE DEPLOYED IN THE VICINITY OF THE COFFER DAMS AND AT EXCAVATION OF SLOUGHS AT CULVERT INSTALLATION AND REMOVAL AREAS TO PREVENT ANY SEDIMENT FROM FLOWING INTO THE CREEK OR WETTED CHANNELS. IF THE SILT FENCES ARE NOT ADEQUATELY CONTAINING SEDIMENT. CONSTRUCTION ACTIVITY WILL CEASE UNTIL REMEDIAL MEASURES ARE IMPLEMENTED THAT PREVENTS SEDIMENT FROM ENTERING THE ADJACENT WATERS.
- SEDIMENT SOURCES SHALL BE CONTROLLED USING BMPS SUCH AS FIBER ROLLS, SEDIMENT BASINS, AND/OR CHECK DAMS THAT WILL BE INSTALLED PRIOR TO OR DURING GRADING ACTIVITIES AND REMOVED ONCE THE SITE HAS STABILIZED.
- 23. EROSION CONTROL MAY INCLUDE REUSE OF ONSITE NATIVE TOP SOIL AND ORGANIC MULCH SEEDING, EROSION CONTROL BLANKETS, PLASTIC COVERINGS, AND GEOTEXTILES OR OTHER BMPS AS APPROVED OF BY THE ENGINEER.
- EXCESS NUISANCE WATER ENCOUNTERED DURING EXCAVATION WILL BE PUMPED INTO THE SURROUNDING FIELDS OR INTO TEMPORARY SETTLING BASINS WITHIN THE CORRIDOR TO PREVENT SEDIMENT-LADEN WATER FROM ENTERING THE DOWNSTREAM CHANNEL
- 25. APPROPRIATE ENERGY DISSIPATION DEVISES WILL BE UTILIZED TO REDUCE OR PREVENT EROSION AT DISCHARGE END OF DEWATERING ACTIVITY
- CONSTRUCTION MATERIALS, DEBRIS, AND WASTE WILL NOT BE PLACED OR STORED WHERE IT CAN ENTER INTO OR BE WASHED BY RAINFALL INTO WATERS OF THE U.S./STATE.

- 27 OPERATORS OF HEAVY FOLIPMENT VEHICLES, AND CONSTRUCTION WORK WILL BE INISTRUCTED TO AVOID SENSITIVE HABITAT AREAS. TO ENSURE CONSTRUCTION OCCURS IN THE DESIGNATED AREAS AND DOES NOT IMPACT ENVIRONMENTALLY SENSITIVE AREAS, THE BOUNDARIES OF THE WORK AREA WILL BE FENCED OR MARKED WITH FLAGGING.
- 28. EQUIPMENT WHEN NOT IN USE WILL BE STORED OUTSIDE OF THE CHANNEL AND ABOVE HIGH
- ALL CONSTRUCTION EQUIPMENT WILL BE MAINTAINED TO PREVENT LEAKS OF FUELS, LUBRICANTS OR OTHER FLUIDS INTO THE CHANNEL. SERVICE AND REFUELING PROCEDURES WILL BE NOT CONDUCTED WHERE THERE IS POTENTIAL FOR FUEL SPILLS TO SEEP OR WASH
- 30. EXTREME CAUTION WILL BE USED WHEN HANDLING AND/OR STORING CHEMICALS AND HAZARDOUS WASTES (E.G., FUEL AND HYDRAULIC FLUID) NEAR WATERWAYS, AND ANY AND ALL APPLICABLE LAWS AND REGULATIONS WILL BE FOLLOWED. APPROPRIATE MATERIALS WILL BE ON SITE TO PREVENT AND MANAGE SPILLS.
- THE CONTRACTOR SHALL TAKE PREVENTATIVE MEASURES TO AVOID ANY SPILLS OR LEAKS ON THE SITE FROM PETROLEUM PRODUCTS. THE CONTRACTOR SHALL PREPARE A SPILL PREVENTION AND RESPONSE PLAN THAT WILL BE APPROVED BY THE CONSTRUCTION MANAGER AND ENVIRONMENTAL MONITOR. THIS MUST BE IMPLEMENTED AND ADHERED TO BY THE CONTRACTOR. AT A MINIMUM, THIS PLAN SHALL REQUIRE THAT STAGING, STORAGE, AND REFUELING AREAS AND ANY EQUIPMENT REPAIR OR SIMILAR ACTIVITY TAKE PLACE WHEN EQUIPMENT IS AT LEAST 100-FEET FROM ANY ACTIVE CREEK CHANNEL, DITCH, POND, OR FENCED SENSITIVE AREA. REFUELING SHALL ONLY OCCUR IN AREAS APPROVED BY THE CONSTRUCTION MANAGER OR ENVIRONMENTAL MONITOR. THE CONTRACTOR SHALL INSPECT AND FULLY CLEAN UP ANY SUCH LEAKS OR SPILLS THAT OCCUR ON THE SITE.
- 32. AT THE CONCLUSION OF CONSTRUCTION OF CERTAIN TASK ELEMENTS, THE CONTRACTOR WILL BE REQUIRED TO IMPLEMENT ADDITIONAL POST-CONSTRUCTION EROSION CONTROL WILL BE REQUIRED TO HIM/LEMENT ADDITIONAL FOR JOINED ROUTED TO STRUCTURE OF THE CONSTRUCTION MANAGER OR ENVIRONMENTAL MANAGER IN ORDER TO PROTECT NATURAL RESOURCES. THESE MEASURES INCLUDE, BUT ARE NOT LIMITED TO, INSTALLING WEED-FREE STRAW MULCH AND TACKIFIER. WEED-FREE STRAW WATTLES OR STRAW LOGS, AND EROSION CONTROL BLANKET AND CONSISTENT WITH THE SWPPP AND RE-VEGETATION PLANS

## EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ECOSYSTEM ENHANCEMENT PROJECT - EREP CONSTRUCTION SEQUENCE

ITEM 2018: INVASIVE SPECIES REMOVAL AND SITE PREP	1-Jun	15-Jun	1-Jul	15-Jul	1-Aug	15-Aug	1-Sep	15-Sep	1-Oct	15-Oct	1-Nov	15-Nov	1-Dec
1 Site Preparation (i.e. fence and gate removal/relocation)													
2 Place temporary surcharge gravel fill within new tidegate footprint to pre-load native foundation soils													
3 Invasive Species Removal				100			1 - 1		1000	Ham.			
ITEM 2019: TIDE GATES, INNER MARSH PONDS/CHANNELS AND SAND DUNE RECONFIGURATION	1-Jun	15-Jun	1-Jul	15-Jul	1-Aug	15-Aug	1-Sep	15-Sep	1-Oct	15-Oct	1-Nov	15-Nov	1-Dec
1 Establish site access and temporary haul routes	100000					-						7 2	
2 Identify and relocate or install temporary exclusions for sensitive species and temporary hotwire fencing for livestock								H 1				,	
3 Install and maintain fish screens/coffer dams to isolate work areas													
4 Install new Inner Marsh Tidegate													
5 Retrofit existing tidegate		-			-							7	
6 Excavate Inner Marsh Ponds and Side Channels													
7 Raise existing berms around Inner Marsh to final grade and replace culverts													
8 Sand dune reconfiguration and revegetation													
9 Seed, mulch and revegetate								7, 2 = 4 1					
10 Site clean-up/rehab temporary roads/final punch list items/demobilization						-							
ITEM 2020: REMAINING INNER MARSH, CENTERVILLE SLOUGH, RUSS CREEK	1-Jun	15-Jun	1-Jul	15-Jul	1-Aug	15-Aug	1-Sep	15-Sep	1-Oct	15-Oct	1-Nov	15-Nov	1-Dec
1 Establish site access and temporary haul routes	B 1 C 1 C 1	1		- 1			CXALL	HILL I	A COLUMN	12.	107-07	-282.33	- 7.7
2 Identify and relocate or install temporary exclusions for sensitive species								4 1					
Install and maintain fish screens, coffer dams, temporarily divert Russ Creek flow to isolate work areas													
4 Excavate Centerville Slough, Inner Marsh Slough, Russ Creek and Sediment Management Area													
5 Install log structures, and similar elements													
6 Install new bridge and culverts													
7 Seed, mulch and revegetate													
8 Site clean-up/rehab temporary roads/final punch list items/demobilization													

						Reuse of Documents  This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	BAR IS ONE INCH ON ORIGINAL DRAWING O 1"		
							65% SUBMITTAL		
-	-	-			-		MARCH, 2017		
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		1717 (11011, 2017		
Plot	Volt Date: 10 April 2017 - 10:08 AM Plotted by: Brendan Byrd Cad File No: N:\US\Eureka\Projects\Legacv\Projects\100298 CalTrout\8410882 EREP EcosystemEnhancement\06-CAD\Sheets\100298 A1 G1.dwg								



esigner GK, JS, BV rafting JS Design JS MARCH 9, 2017 AS SHOWN

CALTROUT EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT

**EROSION CONTROL NOTES AND** CONSTRUCTION SCHEDULE Contract No. 84-10882

This Drawing shall not be used for Construction unless Signed Ansi D Drawing No: C-004

Sht 4 of 44 Rev:



# LIST OF PARCELS\* BISECTED BY APPROXIMATE LIMITS OF CONSTRUCTION DISTURBANCE

NOTE	APN#	PROPERTY OWNER
1	10012104	The Wildlands Conservancy
2	10012103	LD O'Rourke Foundation
3	10012105	The Wildlands Conservancy
4	10013104	The Wildlands Conservancy
5	10013101	LD O'Rourke Foundation
6	10013103	The Wildlands Conservancy
7	10014202	Harville Ranch Co LLC CO.
8	10014301	The Wildlands Conservancy

\*PARCEL INFORMATION OBTAINED FROM HUMBOLDT COUNTY GIS DATA, NOT A PRODUCT OF SURVEY.
\*DEED LINE PER RON HUNT EXHIBIT IN 2008 RECORDED DRAINAGE EASEMENT (2008-24826-32)

						Reuse of Documents This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of CHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	BAR IS ONE INCH ON ORIGINAL DRAWING O 1 1"
							65% SUBMITTAL
Ŀ	-	-			-		MARCH, 2017
	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		1717 (1 (0) 1, 2017

GHD Inc. 718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com

Drawn BB		Designer	GK, JS, BV	С
Diawii DD		Designer	O11, 00, D1	Pi
Drafting JS Check		Design Check	JS	Ti
Approved (Project Director)	SA			
Date	MARCH	9, 2017		С
Scale AS SHO	)WN	This D	rawing shall not be used	Ori

Client CALTROUT Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT SITE PLAN 2017

This Drawing shall not be used for Construction unless Signed and Sealed For Construction

This Drawing shall not be used of Construction unless Signed Ansi D

Drawing No: C-005

# OUTER MARSH DRAWING C-007 SHEET 7 DRAWING C-017 SHEET 17 DRAWING C-008 SHEET 8 APPROX. PROJECT LIMITS OF — DISTURBANCE, TYP. SALT RIVER DRAWING C-009 . SHEET 9 DRAWING C-011 SHEET 11 DRAWING C-010 SHEET 10 (N) CENTERVILLE -SLOUGH ALIGNMENT DRAWING C-013 SHEET 13 — (N) RUSS CREEK ALIGNMENT DRAWING C-012/ SHEET 12. DRAWING C-014 SHEET 14 DRAWING C-015 SHEET 15 DRAWING C-018/ SHEET 18 DRAWING C-020 SHEET 20 This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012 BAR IS ONE INCH ON ORIGINAL DRAWING

# INDEX OF DRAWINGS

	Brownites	
SHEET#	DRAWING#	DRAWING TITLE
1	C-001	COVER SHEET
2	C-002	LEGEND, ABBREVIATIONS, AND GENERAL NOTES
3	C-003	GENERAL NOTES CONTINUED
4	C-004	EROSION CONTROL NOTES AND CONSTRUCTION SCHEDULE
5	C-005	SITE PLAN - EXISTING CONDITIONS AND SITE ACCESS
6	C-006	SITE PLAN SHEET INDEX
7	C-007	SITE PLAN SHEET (1 OF 10)
8	C-008	SITE PLAN SHEET (2 OF 10)
9	C-009	SITE PLAN SHEET (3 OF 10)
10	C-010	SITE PLAN SHEET (4 OF 10)
11	C-011	SITE PLAN SHEET (5 OF 10)
12	C-012	SITE PLAN SHEET (6 OF 10)
13	C-013	SITE PLAN SHEET (7 OF 10)
14	C-014	SITE PLAN SHEET (8 OF 10)
15	C-015	SITE PLAN SHEET (9 OF 10)
16	C-016	SITE PLAN SHEET (10 OF 10)
17	C-017	SITE PLAN - NEW TIDE GATE
18	C-018	SITE PLAN - DUNE RECONFIGURATION NORTHERN SITE
19	C-019	SITE PLAN - AMMOPHILA REMOVAL
20	C-020	SITE PLAN - NEW CENTERVILLE SLOUGH BRIDGE
21	C-021	PROFILES SHEET (1 OF 2)
22	C-022	PROFILES SHEET (2 OF 2)
23	C-023	CROSS SECTIONS - RUSS CREEK AND SMA
24	C-024	CROSS SECTIONS - INNER MARSH POND
25	C-025	TYPICAL CROSS SECTIONS SHEET (1 OF 2)
26	C-026	TYPICAL CROSS SECTIONS SHEET (2 OF 2)
27	C-027	CIVIL DETAILS SHEET (1 OF 6)
28	C-028	CIVIL DETAILS SHEET (2 OF 6)
29	C-029	CIVIL DETAILS SHEET (3 OF 6)
30	C-030	CIVIL DETAILS SHEET (4 OF 6)
31	C-031	CIVIL DETAILS SHEET (5 OF 6)
32	C-032	CIVIL DETAILS SHEET (6 OF 6)
33	C-033	REVEGETATION DETAILS
34	S-1	STRUCTURAL SITE PLAN - NEW TIDE GATE
35	S-2	STRUCTURAL ELEVATION - NEW TIDE GATE
36	S-3	STRUCTURAL DETAILS - NEW TIDEGATE SHEET (1 OF 2)
37	S-4	STRUCTURAL DETAILS - NEW TIDEGATE SHEET (2 OF 2)
38	S-5	STRUCTURAL SITE PLAN - EXISTING TIDE GATE
39	S-6	STRUCTURAL SITE PLAN - CENTERVILLE SLOUGH BRIDGE
40	S-7	STRUCTURAL DETAILS - CENTERVILLE SLOUGH BRIDGE
41	S-8	EXISTING TIDE GATE DRAWINGS (1 OF 4)
42	S-9	EXISTING TIDE GATE DRAWINGS (2 OF 4)
43	S-10	EXISTING TIDE GATE DRAWINGS (3 OF 4)
44	S-11	EXISTING TIDE GATE DRAWINGS (4 OF 4)
		,

Drawn BB		Designer	GK, JS, BV	С
Drafting JS Check		Design Check	JS	Ti
Approved (Project Director)	SA			
Date	MARCH	9, 2017		О

Scale AS SHOWN

Client CALTROUT Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT Title SITE PLAN SHEET INDEX

2017 Contract No. 84-10882

This Drawing shall not be used Original Size for Construction unless Signed and Sealed For Construction Drawing No: C-006 Sht 6 of 44


Revision Note: \* indicates signatures on original issue of drawing or last revision of drawing


65% SUBMITTAL


MARCH, 2017


GHD Inc.


718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com



































BAR IS ONE INCH ON ORIGINAL DRAWING

MARCH, 2017

# **AMMOPHILA REMOVAL NOTES**

HAND REMOVAL

ZONE

- (E) GROUND, TYP.

NOTES:
1. DEFINITION OF "DIRTY SAND": THE 4.0 FT LAYER OF SAND LOCATED DIRECTLY BENEATH AMMOPHILA (EUROPEAN BEACH GRASS). SAND MAY ALSO BE CONSIDERED "DIRTY" IF AMMOPHILA RHIZOMES ARE PRESENT.

- DEFINITION OF "CLEAN SAND": SAND LOCATED BENEATH THE 4.0 FT LAYER OF "DIRTY SAND" AS DEFINED ABOVE AND ANY SANDY AREAS OUTSIDE OF THE AMMOPHILA HAND AND MECHANICAL REMOVAL ZONES. SANDY ZONES OUTSIDE OF AMMOPHILA REMOVAL AREAS MAY NOT BE CONSIDERED "CLEAN" IF AMMOPHILA RHIZOMES ARE PRESENT.
- THE BIOLOGICAL MONITOR WILL DETERMINE IF SAND OUTSIDE OF 3. THE BIOLOGICAL MONITOR WILL DIE TERMINE IT SAIND OUTSIDE OF AMMOPHILA MECHANICAL AND HAND REMOVAL ZONES IS CLASSIFIED AS "CLEAN" OR "DIRTY". GENERALLY SAND WILL BE "CLEAN" IN THESE AREAS, BUT MAY BE CONSIDERED "DIRTY" IF THE BIOLOGICAL MONITOR FINDS AMMOPHILA RHIZOMES ARE PRESENT.
- 4. CUT AND FILL SHOULD BE BALANCED. THE "CLEAN SAND" LAYER (AND OTHER FILL AREAS LOCATED OUTSIDE OF AMMOPHILA REMOVAL ZONES) SHALL COME FROM THE SAME SOURCE AS THE "CLEAN SAND" USED TO COVER THE AMMOPHILA DISPOSAL PIT. IF THE NECESSARY QUANTITY OF "CLEAN SAND" IS NOT ACHIEVED, THE PROJECT ENGINEER AND BIOLOGICAL MONITOR WILL DETERMINE APPROPRIATE ACTION TO BE TAKEN.
- 5. PROGRESS OF WORK:
- 5. PROGRESS OF WORN.

  5.1. STAKE AMMOPHILA REMOVAL, VEHICULAR ACCESS, AND DIRTY SAND AND CLEAN SAND STOCKPILE AREAS. MEET WITH ENVIRONMENTAL MONITOR AND PROJECT ENGINEER TO REVIEW LOCATIONS AND PROTECTION METHODS. INSTALL FLAGGING AND/OR FENCING TO DELINEATE AREA OF DISTURBANCE AND PROTECTED ESHA AREAS.
- ESHA ARLEAS.

  5.2. SECURE DIRTY SAND STOCKPILE AREAS TO ENSURE REMOVED DIRTY SAND WILL NOT ESCAPE OR CONTAMINATE ADJACENT ESHA THIS INCLUDES ASSESSING AND SECURING TRACKED VEHICLES AND TIRES USE TEMPORARY FENCING AND TARPS AS NECESSARY.
- 5.3. DIG OUT DIRTY SAND AND STOCKPILE IN PROTECTED STORAGE AREA. WHERE INDICATED ON PLANS, USE HAND METHODS.
- 5.4. DIG CLEAN SAND TO CREATE AMMOPHILA BURIAL TRENCHES. STOCKPILE CLEAN SAND FOR BACKFILL.
- 5.5. FILL AMMOPHILA BURIAL TRENCHES WITH DIRTY SAND. BACKFILL WITH CLEAN SAND.

  5.6. CLEAN UP STOCKPILE AREAS, TAKING CARE TO REMOVE ALL
- TRACES OF DIRTY SAND.

rawn JH, BB Designer GK, JS, BV Drafting JS Check Design Check JS Approved (Project Director) SA GHD Inc. 718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com MARCH 9, 2017 cale AS SHOWN

CALTROUT EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT SITE PLAN AMMOPHILA REMOVAL

ntract No. 84-10882


This Drawing shall not be used for Construction unless Sligned and Sealed For Construction Sligned Ansi D Drawing No: C-019


Sht 19 of 44 Rev:

document and the ideas and designs incorporated n, as an instrument of professional service, is the erty of GHD Inc. and shall not be reused in whole or

part for any other project without GHD Inc.'s written uthorization. © GHD Inc. 2012


euse of Documents






# PROFILE: CENTERVILLE SLOUGH VERTICAL EX.: 10:1









# PROFILE: CENTERVILLE SLOUGH VERTICAL EX.: 10:1 VERTICAL SCALE HORIZONTAL SCALE


						Reuse of Documents This document and the ideas and designs incorporated	BAR IS ONE INCH ON	
						herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written	ORIGINAL DRAWING  0   1"	
						authorization. © GHD Inc. 2012	65% SUBMITTAL	
-		-			-			
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		MARCH, 2017	


GHD
GHD Inc. 718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330

Drawn BB	Designer GK, JS, BV	Client CALTROUT
Drafting JS Check	Design Check JS	Project EEL RIVER ESTUARY AND CEN
Approved (Project Director) SA Date MARCH	9, 2017	SHEET (1 OF 2) Contract No. 84-10882
Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed and Sealed For Construction	Original Size Ansi D Drawing No: C-021


Client CALTROUT Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT **PROFILES** 


Sht 21 of 44











# PROFILE: CENTERVILLE SLOUGH SECONDARY CHANNEL VERTICAL EX.: 10:1 SCALE: 0\_\_\_\_\_\_


HORIZONTAL SCALE


PROFILE: RUSS CREEK SIDE CHANNEL 2  VERTICAL EX.: 10:1								
SCALE: 0	200'	400'	0	20'	40'			
но	RIZONTAL SCALE			VERTICAL SCALE				


						Reuse of Documents This document and the ideas and designs incorporated	BAR IS ONE INCH ON	
						herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	ORIGINAL DRAWING  O 1"	
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012		
							65% SUBMITTAL	
-	-	-			-		MARCH, 2017	
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		WALGET, 2017	
Plot	ot Date: 13 March 2017 - 3:35 PM Plotted by: Brendan Byrd Cad File No: n:\USiEurekai\Projects\Legacy\Projects\1000298 caltrout\8410882 erep ecosystemenhancement\06-CAD\Sheets\8410882_PROFILES.dwg							


	Drawn BB Designer GK, JS, I
GHD	Drafting JS Design Check JS
GHD Inc.	Approved (Project Director) SA
718 Third Street Eureka California 95501 USA	Date MARCH 9, 2017
T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com	This Drawing shall Scale AS SHOWN for Construction un


Client CALTROUT Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT **PROFILES** SHEET (2 OF 2)
Contract No. 84-10882 This Drawing shall not be used for Construction unless Signed and Sealed For Construction Unless Signed Ansi D Drawing No: C-022 Sht 22 of 44

















Reuse of Documents This document and the ideas and d herein, as an instrument of professi property of GHD lnc. and shall not lin part for any other project without authorization. Get Plb Inc. 2012	onal service, is the ORIGINAL DRAWING be reused in whole or	GHD	Drawn BB Designer GK, JS, BV  Drafting JS Design JS Check JS	Cilent Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT Title CROSS SECTIONS
	65% SUBMITTAL	GHD Inc.	(Project Director) SA  Date MARCH 9, 2017	RUSS CREEK AND SMA Contract No. 84-10882
No Revision Note: *indicates signatures on original issue of drawing or last revision of drawing Drawn Manager Director Date	MARCH, 2017	718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com	This Drawing shall not be us	ed Original Size Sht 23 of 44




























F	INNER MA	RSH P	OND 5	5A CROS	SS SECT	ION
C-008 C-024	SCALE: 0	100'	200*	0	10' 2	o' 
_	н	ORIZONTAL SCAL	F	VERTIC	AL SCALE	

						Reuse of Documents	DAD TO OVER EVEN OV	
						This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	BAR IS ONE INCH ON ORIGINAL DRAWING 0 1"	
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012		
							65% SUBMITTAL	
Ŀ	-	-			-		MARCH, 2017	
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		WATOT, 2017	
Plot	Plot Date: 13 March 2017 - 3.38 PM Plotted by: Brendan Byrd Cad File No: n:\USiEureka\Projects\Legacy\Projects							




Designer GK, JS, BV	Client Project	CALTROUT							
Design Check JS	Title	EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT CROSS SECTIONS							
, 2017	Contract	INNER MAR No. 84-10882	SH POND	ENHANCEMENT	S				
This Drawing shall not be used for Construction unless Signed and Sealed For Construction	Original Size Ansi D	Drawing No:	C-024		Sht 24	l ₀ 44 Rev:			




# 1 IMPROVED EXISTING ACCESS ROAD BETWEEN HQ BARN AND INNER MARSH BERM

SCALE: 1" TO 20'




# 1 INNER MARSH BERM WITH IMPROVED ACCESS ROAD TYPICAL SECTION




# WETLAND CREATION TYPICAL SECTION NOT TO SCALE

# EXISTING GROUND FINISH GRADE MATCH EXITING GROUND AT LIMITS OF GRADING, TYP BOTH SIDES PROFILE BOTTOM ELEVATION 2, TYP.

# INNER MARSH CHANNEL COMPLEX 1, 3, 4, AND 5 TYPICAL SECTION



# KAYAK LAUNCH CHANNEL TYPICAL SECTION NOT TO SCALE



# **TABLE 1: TYPICAL SLOUGH CHANNEL GEOMETRY**

REACH	STATION	BOTTOM WIDTH (FT)
CENTERVILLE SLOUGH: TP 1	CS-0+00 TO CS-15+00 & CS-39+65 TO CS-57+65	40
CENTERVILLE SLOUGH: TP 2	CS-57+90 TO CS-79+65	35
CENTERVILLE SLOUGH: TP 3	CS-80+45 TO CS-118+51	28
CENTERVILLE SLOUGH SECONDARY CHANNEL	CS2-0+00 TO RC-7+33	16


						Reuse of Documents This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD line, and shall not be reused in whole or in part for any other project without GHD line's written authorization. © GHD line: 2012	BAR IS ONE INCH ON ORIGINAL DRAWING O 1"
							65% SUBMITTAL
Ŀ	-	-			-		MARCH, 2017
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		1017 (11011, 2017



Scale	AS SHO	WN	This D for Co	rawing shall not be used nstruction unless Signed	Origin
Date		MARCH	9, 2017		Con
Approve (Project		SA			
Drafting Check	JS		Design Check	JS	Title
Drawn	ВВ		Designer	GK, JS, BV	Clie

Client Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT
Title TYPICAL CROSS SECTIONS
SHEET (1 OF 2)
Contract No. 84-10882


This Drawing shall not be used for Construction unless Signed Ansi D Drawing No: C-025



EXISTING GROUND DAYLIGHT SLOPES TYP BOTH SIDES DAYLIGHT TO SMA GRADING, TYP BOTH SIDES EXISTING GROUND -— FINISH GRADE

NOT TO SCALE

8 RUSS CREEK SIDE CHANNEL TYPICAL SECTION
NOT TO SCALE



**RUSS CREEK CHANNEL TYPICAL SECTION** NOT TO SCALE LOOKING UPSTATION ON RUSS CREEK PROFILE

						Reuse of Documents  This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	BAR IS ONE INCH ON		
							ORIGINAL DRAWING		
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	0 1"		
							65% SUBMITTAL		
-	-	-			-		MARCH, 2017		
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		WAITOTT, 2017		
Diot	of Date: 13 March 2017 - 2:30 DM Plotted by Brandon Burd Cod Ellis No. In VISIE uraks/Draigets/Language/Draigets/Languag								

CHD
dill
GHD Inc.
718 Third Street Eureka California 95501 USA
T 1 707 443 8326 F 1 707 444 8330
W www.ahd.com

Drawn BB		Designer	GK, JS, BV	Clie
Diami. DD		Doorginon	G11, 00, D1	Proj
Drafting JS Check		Design Check	JS	Title
Approved (Project Director)	SA	•		
Date	MARCH	9, 2017		Con
			rawing shall not be used	
Scale AS SHC	OWN	for Co	nstruction unless Signed	l۸ne


lient CALTROUT oject EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT TYPICAL CROSS SECTIONS 2017 SHEET (2 OF 2)
Contract No. 84-10882

This Drawing shall not be used for Construction unless Signed and Sealed For Construction

This Drawing Shall not be used for Construction unless Signed Ansi D

Drawing No: C-026

Sht 26 of 44 Rev:



- NOTES:

  1. THE FOLLOWING MATERIALS SHALL BE USED IN ALL FENCE


  THE FOLLOWING MATERIALS SHALL BE USED IN ALL FENCE

  THE FOLLOWING SOCIETY OF THE PROPERTY OF TH
- CONSTRUCTION UNLESS OTHERWISE NOTED:

   ALL WOOD POSTS SHALL BE REDWOOD OR APPROVED EQUAL UNO, OR UNLESS APPROVED BY THE CONSTRUCTION MANAGER.
- 5-INCH (DIAMETER) BY 8-FOOT (LENGTH) POSTS (FOR H BRACE, IN-LINE, AND RISE AND DIP POSTS)
- 4 INCH (DIAMETER) BY 8-FOOT (LENGTH) (FOR HORIZONTAL BRACES)
- 12.5 GAUGE GALVANIZED BARBLESS
- 1.5-INCH DOUBLE HOT DIPPED GALVANIZED FENCE STAPLES
- WIRE GATES SHALL BE INSTALLED TO ALLOW ACCESS THROUGH THE FENCED AREA AT LOCATION SHOWN ON PLANS. FOR TYPE 1 & 2 FENCES, WIRE GATES ARE COMPRISED OF FIVE STRANDS OF BARBED

WIRE CONNECTING TO WOODEN END POSTS (4 FOOT LENGTH) WITH WOODEN POSTS A MINIMUM OF EVERY FOUR FEET BETWEEN THE END POSTS. THE WIDTH OF THE GATE SHALL BE MIN 10' FOR TYPE 3, 4 OR 5 FENCES. WIRE GATES SHALL CONSIST OF TWO STRAIGHT WIRE GALVANIZED CABLES WITH INSULATED SPRING LOADED HANDLE TO MAINTAIN SAME VOLTAGE FOR THE GATE. GATE SHALL BE NON-ELECTRIFIED WHEN OPEN. UNDERGROUND DOUBLE INSULATED WIRES (INSULATED FOR MIN, 15,000 VOLTS) SHALL BE USED TO CARRY

PRIOR TO INSTALLATION, ALL FENCE ALIGNMENTS SHALL BE STAKED IN THE FIELD AND APPROVED BY THE CONSTRUCTION MANAGER, AND ALL MATERIALS SHALL BE APPROVED BY THE CONSTRUCTION



DETAIL: DOUBLE H LINE BRACE

# **DETAIL: SINGLE H GATE** AND LINE BRACE

## NOTES:


- 1. SINGLE H BRACES SHALL BE INSTALLED AT ENDS, BOTH SIDES OF GATES, AND AT A MAXIMUM OF 300-FOOT INTERVALS.
- 2. DOUBLE H BRACES SHALL BE INSTALLED AT DIRECTION
- 3. WOODEN RISE AND DIP POSTS SHALL BE INSTALLED AS
- 4. ALL WOODEN POSTS (H BRACE POST, INLINE POST, AND RISE AND DIP POSTS) SHALL BE SOLIDLY SET OR DRIVEN IN COMPACTED SOIL TO A DEPTH OF 3.5 FEET. THE HEIGHT OF ALL POSTS AFTER INSTALLATION SHALL BE 4.5 FEET.

5. WHEN CONSTRUCTING H BRACES, HORIZONTAL BRACES SHALL BE INSTALLED AT A MINIMUM OF 3.5 FEET FROM THE GROUND.
A TENSION MEMBER COMPOSED OF TWO COMPLETE LOOPS OF NUMBER 12.5 GAUGE GALVANIZED DOUBLE STRAND SMOOTH WIRE SHALL EXTEND FROM A POINT APPROXIMATELY SIX INCHES BELOW THE TOP OF THE BRACE POST TO GROUND LEVEL OF THE POST BEING BRACED. THE BRACE WIRE SHALL BE TWISTED TO SECURE THE BRACE AND PROVIDE NEEDED RIGIDITY. IN-LINE H BRACES SHALL BE CONSTRUCTED WITH 2 TENSION WIRES PER BRACE.



# FENCE H GATE & LINE BRACE DETAIL

# FENCE INSTALLATION DETAIL




## **GATE INSTALLATION**

# NOTES:


evision Note: \* indicates signatures on original issue of drawing or last revision of drawin

- 1. (E) FENCE BETWEEN GATE POSTS SHALL BE REMOVED AND DISPOSED OF OFF-SITE BY THE CONTRACTOR UNI ESS
- 2. FOR ELECTRIC FENCES, SEE FENCE INSTALLATION NOTES FOR

Job



- 1. FILTER FABRIC SHALL BE INSTALLED IN A CONTINUOUS ROLL TO AVOID THE USE OF JOINTS. WHERE JOINTS ARE NECESSARY SPLICE FABRIC TOGETHER ONLY AT A SUPPORT POST WITH A MINIMUM 6'
- 1. POSTS SHALL BE SPACED A MAXIMUM OF 6' APART AND DRIVEN SECURELY INTO THE GROUND A
- 2. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4" WIDE AND 6" DEEP ALONG THE LINE OF POSTS UPHILL FROM THE BARRIER. TRENCH SHALL FOLLOW THE CONTOUR
- 3. TRENCH SHALL BE BACKFILLED WITH NATIVE MATERIAL
- 4. INSPECT AND REPAIR AFTER EACH RAINFALL, INSPECT DAILY DURING PROLONGED RAINFALL.
- 5. REMOVE SEDIMENT WHEN IT REACHES APPROXIMATELY ONE THIRD THE HEIGHT ABOVE GROUND PORTION OF THE FENCE.
- 6. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE FILTER FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE AND SEEDED.



- 1. CONTRACTOR SHALL INSPECT WATTLES AFTER EACH RAINFALL. REPLACE WATTLES WHEN THEY HAVE DECOMPOSED, COLLAPSED, OR BEEN DAMAGED
- 2. WATTLES SHOULD BE PLACED ON THE CONTOUR AND IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT WATTLE.
- 3. THE DIRECTION OF RUNOFF FLOW TO THE WATTLES SHOULD BE PERPENDICULAR TO THE STAKED WATTLE LOCATION.
- 4. REMOVE UPON SITE STABILIZATION AND AS DIRECTED BY THE CONSTRUCTION MANAGER.
- 5. WATTLES/FIBER ROLLS SHALL BE COMPRISED OF BIODEGRADABLE MATERIALS.

WATTLES/FIBER ROLL SEDIMENT BARRIER

# TYPICAL CONSTRUCTION ACCESS GATE





W www.ghd.com

Drafting JS roject Director) AS SHOWN

MARCH 9, 2017 This Drawing shall not be used for Construction unless Signed and Sealed For Construction

(14)


CALTROUT EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT **CIVIL DETAILS SHEET** 


SHEET (1 OF 6) ntract No. **84-1088**2

Sht 27 of 44 Ansi D Drawing No: C-027 Rev:

Plotted by: Brendan By

euse of Documents





CRUSHED OR RIVER RUN AGGREGATE GREATER THAN 3"
BUT SMALLER THAN 6"


CORRUGATED STEEL PANELS

ORIGINAL GRADE

8" MIN, UNO

SECTION A - A

(AT GRADE)



15 BERM TURN-AROUND (TYP)

PLAN VIEW

12'

6" COMPACTED
CRUSHED AGGREGATE

MAX 2 HORIZONTAL TO 1
VERTICAL SIDE SLOPE, TYP

SCARIFY & RECOMPACT UPPER 6"
WOVEN GEOTEXTILE FABRIC,
MIRAFI 500x OR APPROVED EQUAL

IMPROVED (E) GRAVEL ACCESS ROAD SECTION

## NOTES:

- ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC ROADWAY, AND DEGRADATION OF EXISTING PAVEMENT.
- 2. INSTALL CORRUGATED STEEL PANEL GRATES OR TIRE WASHING STATION AS NEEDED TO PREVENT TRACKING OF MUD ONTO PUBLIC ROAD.
- 3. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS MUST BE REMOVED IMMEDIATELY.
- 4. ACCESSES SHALL BE INSPECTED DAILY AND AFTER EACH RAINFALL WITH MAINTENANCE PROVIDED BY THE CONTRACTOR AS NECESSARY.
- 5. ALL TEMPORARY CONSTRUCTION ENTRANCES SHALL BE LEFT IN PLACED AT THE CONCLUSION OF CONSTRUCTION, UNO.
- 6. GEOTEXTILE FABRIC SHALL BE WOVEN, MIRAFI 500x OR APPROVED EQUAL.

CONSTRUCTION ENTRANCE

BAR IS ONE INCH ON ORIGINAL DRAWING

MARCH, 2017

GHD Inc. 718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com

(17)

Drawn BB

Designer GK, JS, BV

Drafting JS
Check

Design JS
Check

Approved
(Project Director)
Date

MARCH 9, 2017

This Drawing shall not be used for Construction unless Signed af Sealed For Construction unless Signed Ansi D

Drawing No: C-028

Client Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT
Title CIVIL DETAILS SHEET
SHEET (2 OF 6)
Contract No. 84-10882

Sht 28 of 44

Rev:


No Revision Note: \* indicates signatures on original issue of drawing or last revision of drawin

Plot Date: 13 March 2017 - 3:40 PM Plotted by: Brendan Byrd

File No: n:\US\Eureka\Projects\Legacy\Projects\1000298 caltrout\8410882 erep ecosystemenhancement\06-CAD\Sheets\8410882\_CIVIL\_DETAILS.dw


his document and the ideas and designs incorporated trein, as an instrument of professional service, is the operty of GHD Inc. and shall not be reused in whole or

part for any other project without GHD Inc.'s written uthorization. © GHD Inc. 2012




6" THICK COMPACTED CLASS II AGG BASE, SEE DETAIL C-025 - SUITABLE NATIVE FILL, COMPACTED TO 90% RC COMPACTED TO 90% RC (N) 60" HDPE CULVERT WITH MIN. PER PIPE SIDE HINGE OPENING, TYP 1 MANUFACTURERS SPECIFICATIONS **BEDDING DETAIL** 

CULVERT WITH SIDE HINGE GATE



- REMOVE (E) VEGETATION AND ANY DEBRIS OR DELETERIOUS MATERIAL ENCOUNTERED WITHIN FOOTPRINT OF NEW BERM. FINISHED BERM WIDTH 16' AND ELEVATION 8' FOR BERM IMPROVEMENT LOCATIONS BETWEEN INNER MARSH BERM STA 0+00 AND 11+00. FINISHED BERM WIDTH 12' AND ELEVATION 8' FOR BERM IMPROVEMENT LOCATIONS BETWEEN INNER MARSH BERM STA 11+00 AND 60+00. FINISHED BERM WIDTH 12' AND ELEVATION 15' FOR BERM IMPROVEMENT LOCATIONS BETWEEN INNER MARSH BERM STA STA 11+00 AND 60+00. FINISHED BERM WIDTH 12' AND ELEVATION 15' FOR BERM IMPROVEMENT LOCATIONS BETWEEN INNER MARSH BERM STA 60+00 AND 96+00
  - TYPICAL BERM REHABILITATION DETAIL



# TYPICAL NEW ACCESS ROAD CULVERT DETAIL

						Reuse of Documents	BAR IS ONE INCH ON		
						This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	ORIGINAL DRAWING		
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	0 1"		
							65% SUBMITTAL		
-	-	-			-		MARCH, 2017		
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		WATOTI, 2017		
Plot	lot Date: 13 March 2017 - 3:50 DM Plotted by Brandan Burd Cod Eila Nov. m/US/Eurak/a)Projected anguy/Drojected anguy/Drojected 1000000000000000000000000000000000000								




Drawn BB		Decigner	GK, JS, BV	Clie
Diawii DD		Designer	GR, 35, BV	Proj
Drafting JS Check		Design Check	JS	Title
Approved (Project Director)	SA			
Date	MARCH	9, 2017		Con
			rawing shall not be used	
Scale AS SHC	WN	for Co	nstruction unless Signed	l۸na

lient CALTROUT oject EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT **CIVIL DETAILS SHEET** SHEET (3 OF 6) ontract No. 84-10882 Sht 29 of 44

Rev:

Institution unless Signed for Construction unless Signed and Sealed For Construction United Signed Ansi D Drawing No: C-029



LOG COVER STRUCTURE

ORIENT ROOT FAN TO FACE SLIGHTLY UPSTREAM AND EMBED INTO BANK

TOP OF BANK

ROOT WAD MIN 10' LONG, 2.5' DIAMETER, EMBEDDED INTO BANK

LENGTH FROM ENDS OR EVERY 5' IF LOG
LENGTH GREATER THAN 10'

LENGTH GREA

ROOT WAD DEFLECTOR

NTS

BOLTED AND MUSHROOMED END OF THREADED
REBAR, BOTH ENDS OF REBAR
STEEL WASHER PLATE

BURED REBAR 1 HOUGH
STEEL WASHER PLATE

BURED REBAR 1 HOUGH
CENTER OF BOTH LOGS
RECESSED MIN JANCH INTO LOGS, BOTH ENDS

THROUGH-BOLT

FRICTION AND MISHROOMED
END OF THREADED
REBAR 7 FRICTION AND MISHROOMED
FRICTION AND MISHROOMED
END OF THREADED
REBAR 7 FRICTION AND MISHROOMED
FRI

BOLTED AND MUSHROOMED END OF THREADED REBAR. SIDE OPPOSITE SOIL ANCHOR RECESSES INTO LOG

4 JINCH X 4 JINCH X 3 JINCH X 3 JINCH DEEP CUT SIDE OPPOSITE SOIL ANCHOR

FINISHED GRADE OR THENCH BOTTOM

U-CLAMP TO FORM CABLE LOOP. TYP 2 PLACES, 4 TO 6 INCHES APART

NOTE:

INSTALL PER MANUFACTURER'S WRITTEN INSTRUCTIONS.

ANCHOR DEPTH MIN 8'

WASHER PLATE BOTH SIDE OF CABLE LOOP
THREADED REBAR

U-CLAMP TO FORM CABLE LOOP. TYP 2 PLACES, 4 TO 6 INCHES APART

THIMBLE EYE

NOTE:

INSTALL PER MANUFACTURER'S WRITTEN INSTRUCTIONS.

ANCHOR DEPTH MIN 8'

SOIL ANCHOR

LOG / ROOT WAD

THREADED REBAR THROUGH CENTER OF LOG

STEEL WASHER


TYPICAL SOIL ANCHORING SYSTEM

LOG TO LOG ANCHOR

						Reuse of Documents  This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	BAR IS ONE INCH ON	
							ORIGINAL DRAWING	
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	0 1"	
							65% SUBMITTAL	
-	•	-			-		MARCH, 2017	
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		100 01 101 1, 2017	




Drawn BB	Designer GK, JS, BV	David and	CALTROUT	DDO IFOT
Drafting JS Check	Design Check JS	'	EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT CIVIL DETAILS SHEET	PROJECT
Approved (Project Director) SA Date MARCH	19, 2017		SHEET (4 OF 6)	
Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed	Original Size Ansi D	Drawing No: C-030	30 of 44



# TYPICAL TARGET RESTORATION DUNE SECTION NTS

EXISTING DUNE SOILS (SAND) TO REMAIN.



SAND FENCE DETAIL

Reuse of Documents
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012

BAR IS ONE INCH ON ORIGINAL DRAWING
O INCHANGE
O INCHINATION ORIGINAL DRAWING
O INCHINATION ORIGI

ENSTAND

TRANL

SORBERTO

OVERLEGE

ACCESS

EACH


BASE

# DUNE OVERLOOK CONCEPT NTS

	Drawn BB, JG, JH	Designer GK, JS, BV, JH	Client Project	CALTROUT
GHD	Drafting JS Check	Design Check JS	Title	EEL RIVER ESTUARY AND CEN CIVIL DETAILS SHEET
GHD Inc.	Approved (Project Director) SA Date MARCH	9 2017	C44	SHEET (5 OF 6) No. 84-10882
718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com	Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed and Sealed For Construction	Original Size	0.004

Client	CALTROUT
Project	EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT
Title	CIVIL DETAILS SHEET
	SHEET (5 OF 6)
Contract	No. 84-10882

Sht 31 of 44





NOTES:


1. PLAN AND PROFILE DIMENSIONS APPROXIMATE, ADJUSTED TO ACCOMMODATE TO EXISTING CONDITIONS.

2. MAINTAIN 20:1 CROSS SLOPE AS LONG AS PRACTICAL, STEEPEN TO 5:1 AS NEED TO RETURN TO EXISTING GRADE.











- OUTLET OF WATER DIVERSION PIPE TO BE PLACED ON A WASHED COBBLE ENERGY DISSIPATER
  AT LEAST 3' x 3' IN SIZE PLACED IN CHANNEL UPSTREAM OF THE DOWNSTREAM FISH SCREEN.
- 2. USE GRAVITY LINE AS MUCH AS PRACTICAL.
- 3. WATER MANAGEMENT PLAN CAN PROPOSE AN ALTERNATIVE COFFER DAM FOR APPROVAL.





NOTE: FISH EXCLUSION SCREENS TO BE PLACED AT DIRECTION OF BIOLOGIST AND CONSTRUCTION MANAGER



						Reuse of Documents This document and the ideas and designs incorporated	BAR IS ONE INCH ON
						herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	ORIGINAL DRAWING
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	0 1"
							65% SUBMITTAL
-	-	-			-		MARCH, 2017
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		1417-411-011, 2017
Plo	t Date: 13 March 2017 - 3:40 PM Plotted by: Brendan Byrd	Car	Eile No: 1	n:\US\Eurek	a\Projects\I	enacy/Projects/1000298 caltrout/8410882 eren ecosystement	nancement\06.CAD\Sheets\8410882_CIVII_DETAILS dwg



Drafting JS  Approved (Project Director) SA	Designer GK, JS, BV  Design Check JS	Client CALTROUT Project EEL RIVER ESTUARY AND CENTITUDE TITUDE CIVIL DETAILS SHEET SHEET (6 OF 6)
Date MARCH	9, 2017	Contract No. 84-10882
Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed and Sealed For Construction	Ansi D Drawing No: C-032

Client CALTROUT roject EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT **CIVIL DETAILS SHEET** SHEET (6 OF 6) Contract No. 84-10882 Sht 32 of 44

Table 1. Freshwater Wetland Seed Mix (40lbs/AC)

Common Name	Scientific Name	Pounds of Pure Live Seed/Acre
Tufted hairgrass	Deschampsia despitosa	5
Slender hairgrass	Deschampsia elongata	5
Common spikerush	Eleocharis macrostachya	2
Meadow barley	Hordeum brachyantherum	8.5
Creeping wild rye	Leymus triticoides	8.5
Vancouver wildrye	Leyrnus vancouverensis	11
	Total	40

Table 2. Tidal/Brackish Wetland Seed Mix (40lbs/AC)

Common Name	Scientific Name	Pounds of Pure Live Seed/Acre
Tufted hairgrass	Deschampsia despitosa	6.5
Saltgrass	Distichtis spicata	6.5
Regreen hybrid wheatgrass	Elymus x triticum	11
Gumplant	Grindelia stricta	2
Meadow barley	Hordeum brachanytherum	4
Jaumea	Jaumea carnosa	1
Marsh rosemary	Limonium californicum	05
Arrowgrass	Triglochin maritima	8.5
	Total	1 40

Table 3 Organic Pasture Seed Mix (40)hs/AC)

Common Name	Scientific Name	Pounds of Pure Live Seed/Acre
tetraploid perennial ryegrass	Lotium perenne	
berseem clover	Trifolium alexandrinum	
Festuca x Lolium hybrid	Festucafolium braunii	
red clover	Trifolium pratense	!
white clover (ladino type)	Trifolium repens	
diploid perennial ryegrass	Lotium perenne	
white clover (New Zealand type)	Trifalium repens	:
	Total	3:

Table 4. Riparian Habitat Planting


Common Name	Scientific Name	On-Center Plant Spacing (ft.)	Propagule Type
Sitka spruce	Picea sitchensis	16-25 feet apart groupings of 2-3	DP
Shore pine	Pinus contorta var. contorta	16-20 feet apart groupings of 2-3	DP
Pacific wax myrtle	Morella californica	12-16 feet apart in groupings of 3-5	DP
Red alder	Alnus rubra	same as above	DP
Sitka willow	Salix sitchensis	same as above	OP
Coastal willow	Salix hookeriana	same as above	DP
Pacific willow	Salix lucida	same as above	DP
Red elderberry	Sembucus racemose	Singly or 10 feet apart in pairs	DP
Cascara	Frangula purshiena	same as above	T8
Pacific rhododendron	Rhododendron	same as above	TB
	macrophyllum		
Western azalea	Rhododendron occidentale	same as above	T8
Twinberry	Lonicera involucrata	10 feet apart in groupings of 2-3	TB
Flowering current	Ribes sanguineum	same as above	T8
	glutinosum		
Evergreen huckleberry	Veccinium ovatum	same as above	TB
Spirea	Spirea densiflora	6 feet apart in groupings of 5-7	T8
Nootka rose	Rosa nutkana	same as above	T8
Salmonberry	Rubus spectabilis	same as above	T8
Thimbleberry	Rubus parviflorus	same as above	TB

Table 5. Tidal and Brackish Wetland Habitat Plug Planting


	Wetland Habitat Plug Planti	٥,	1	
Tidal Marsh Zone	Common Name	Scientific Name	On-Center Spacing (ft.)	
Low/Mid	Pickleweed	Salicornia pacifica	in stands of 10-15 plants at 1-2 ft apart	Cuttings rooted in Tree Bands (TB)
Mid	Saltgrass	Distichlis spicata	in bands of plants at 1 foot apart	transplant plant plugs or clumps
High	Coastal tufted hairgrass	Deschampsia caespitosa ssp beringensis	groupings 5-10 plants at 2 feet apart	transplant whole plant or plant divisions
Mid:High	Coastal gumplant	Grindelia stricte var stricte	groupings of 5 to 7 plants at 3-4 foot spacing	Rooted cuttings in DP to 1-gallon
Mid/High	Marsh jaurnea	Jaumea carnosa	groupings of 5 to 7 plants at 3-4 foot specing	Rooted cuttings in DPs to 1-gallon
Mid	Pale spikerush	Eleocharis macrostachya	in stands of 15-25 at 1 foot apart	transplant divisions or plant plugs
Mid	Slender arrowgrass	Triglochlin concinna	same as above	same as above
Mid	Three-square bulrush	Choenoplectos pugens var. longisoicatus	same as above	Transplant rhizome divisions
Mid	Alkalı bulrush	Bolbaschoenus maritimus ssp. paludosus	same as above	Transplant rhizome divisions
Low	Lyngbye's sedge	Carex lyngbyei,	same as above	same as above
Low	Slough sedge	Carex obnupta	same as above	transplant divisions or plant plugs

						Reuse of Documents This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. 9 GHD Inc. 2012	BAR IS ONE INCH ON ORIGINAL DRAWING O 11 1"
							65% SUBMITTAL
Ŀ	-	-			-		MARCH, 2017
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		1417 (1 (8) 1 ), 20 1 7
Plot	Date: 13 March 2017 - 3:41 PM Plotted by: Brendan Byrd	Car	file No: 1	n:\US\Furek	a\Projects\I	egacy\Projects\1000298 caltrout\8410882 erep ecosystement	hancement\06-CAD\Sheets\8410882 CIVII DETAILS dw

GHD Inc. 718 Third Street Eureka California 95501 USA T 1 707 443 8326 F 1 707 444 8330 W www.ghd.com



# **CONTAINER PLANT INSTALLATION**



# **PLUG INSTALLATION**

Table 6. Dune Habitat Plug Planting


Common Name	Scientific Name	RATIO	SPACING	CONTAINER SIZE
Sand Verbena	Abronia Latifolia	15%	36"	
Silver Beach Bur	Ambrosia Chamissonis	15%	36"	Plugs, 4", suppercell deepat 16,
Beach Morning Glory	Calystegia Soldanella	10%	24"	Area Acceptable Sizes
American Dunegrass	Elymus Mollis	60%	36"	


REVEGETATION NOTES


- PLANT MATERIAL TO BE NURSERY PROPAGATED FROM LOCAL GENETIC STOCK (FROM COASTAL HUMBOLDT COUNTY).

  CONTRACTOR SHALL CONFIRM TOTAL AREA OF COVERAGE TO ESTIMATE TOTAL PLANT COUNT NEEDED. USE RATIO OF PLANTS AND SPACING AS GUIDE FOR PLANT TOTALS.

Drawn BB, JH	Designer JH	Don't said	CALTROUT	VENT DDG IEGT
Drafting JS Check	Design Check JS	'	EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCE! REVEGETATION DETAILS	WENT PROJECT
Approved (Project Director) SA Date MARCH	9, 2017	Contract N	No. 84-10882	
Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed and Sealed For Construction	Original Size Ansi D	Drawing No: C-033	Sht 33 of 44 Rev:







WALL SECTION

# NOTE 1: SIDE HINGE GATE

- A. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR REVIEW AND APPROVAL
- B. GATES SHALL BE FURNISHED AND INSTALLED PER MANUFACTURER RECOMMENDATIONS UNDER THE SUPERVISION OF THE ENGINEER
- C. SIDE HINGE TIDE GATES AND RELATED APPURTENANCES SHALL BE ALUMINUM OR TYPE 316 STAINLESS STEEL
- D. GATES AND REGULATING SYSTEM SHALL MEET THE FOLLOWING OPERATING SPECIFICATIONS:
- i. GATES SHALL OPEN ON OUTGOING FLOW WHENEVER WATER LEVELS IN THE ESTUARY ARE GREATER THAN THE INBOARD
- ii. GATES SHALL CLOSE ON INCOMING FLOW USING AN ADJUSTABLE REGULATING SYSTEM ACTUATED FROM INBOARD WATER LEVELS RANGING BETWEEN 1 AND 4 FEET

# NOTE 2: SLIDE GATE


- A. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR REVIEW AND APPROVAL
- B. GATES SHALL BE FURNISHED AND INSTALLED PER MANUFACTURER RECOMMENDATIONS UNDER THE SUPERVISION OF THE ENGINEER
- C. SLIDE TIDE GATES AND RELATED APPURTENANCES SHALL BE ALUMINUM OR TYPE 316 STAINLESS STEEL
- D. SLIDE GATE SHALL MEET THE FOLLOWING OPERATING SPECIFICATIONS:
- i. SLIDE GATE SHALL BE TOP HINGED AND OPEN ON OUTGOING FLOW WHENEVER WATER LEVELS IN THE ESTUARY ARE GREATER THAN THE INBOARD
- ii. SLIDE GATE SHALL BE VERTICALLY ADJUSTABLE WITH MANUAL ACTUATION
- E. SLIDE GATE AND OPERATOR SHALL MEET AWWA C513 SPECIFICATIONS


						Reuse of Documents	BAR IS ONE INCH ON
						This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or	ORIGINAL DRAWING
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	0 1"
							65% SUBMITTAL
-	-	-			-		MARCH, 2017
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		177 (110) 1, 2017
Plo	t Date: 5 April 2017 - 4:25 PM Plotted by Brendan Burd	Car	d Eile No: I	N:\LIS\Eurok	a\Drojecte\I	egacy/Projects/1000208 caltrout/8/10882 eren ecosystemen	ancement(06-CAD)Sheete(8/10882 STRUCTURAL DETAIL





Drawn SD		Designer	SP	Clie
Drafting JS Check		Design Check	JS	Title
Approved (Project Director)	SA			
Date	MARCH	9, 2017		Con
Scale AS SH	OWN	for Co	rawing shall not be used nstruction unless Signed	Origin <b>An</b> s


ient CALTROUT oject EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT te STRUCTURAL ELEVATION **NEW TIDE GATE** Contract No. 84-10882
Inginal Size
Ansi D Drawing No: S-2 Sht 35 of 44

















KEYWAY GROUT DETAIL

SCALE: NTS



herein, as an instrum property of GHD Inc.	he ideas and designs incorporated hent of professional service, is the and shall not be reused in whole or project without GHD Inc.'s written OFFICE AND THE PROFESSION OF THE	GHD Drawn Drafting Check		Client Project EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT Title STRUCTURAL DETAILS
	65% SUBMITTAL	Approve GHD Inc. 718 Third Street Eureka California 95501 USA Date	red tt Director) SA MARCH 9, 2017	CENTERVILLE SLOUGH BRIDGE Contract No. 84-10882
Revision Note: *indicates signatures on original issue of drawing or last revision of drawing Drawn Manager Director Date	MARCH, 2017	T 1 707 443 8326 F1 707 444 8330 Www.ghd.com Scale	AS SHOWN This Drawing shall for Construction ur and Sealed For Co	ot be used Original Size ses Signed Apps D Drawing No: \$-7






						Reuse of Documents  This document and the ideas and designs incorporated herein, as an instrument of professional service, is the	BAR IS ONE INCH ON ORIGINAL DRAWING
						property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	0 1"
							65% SUBMITTAL
-	-	-			-		MARCH, 2017
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		WATOT, 2017



Drawn	Designer	Client CALTROUT
Drafting Check	Design Check	Title EXISTING TIDE GA
Approved (Project Director) SA Date MARCH	9, 2017	(2 OF 4) Contract No. 84-10882
Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed and Sealed For Construction	Original Size Ansi D Drawing No: <b>S-9</b>

Client Project EL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT
Title EXISTING TIDE GATE DRAWINGS
(2 OF 4)
Contract No. 84-10882
Cligical Sizes
Cligical Sizes




						Reuse of Documents This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of CHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012	BAR IS ONE INCH ON ORIGINAL DRAWING O 11 1"
							65% SUBMITTAL
Ŀ	-	-			-		MARCH, 2017
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date		1017 (1 (3) 1, 2017
Plot	Plot Date: 13 March 2017 - 3:12 PM Plotted by: Brendan Byrd Cad File No: n:\US\Eureka\Projects\Legacy\Projects\1000298 caltrout\8410882 erep ecosystemenhancement\06-CAD\Sheets\8410882_STRUCTURAL_DETAILS.c						

GHD
GHD Inc.
718 Third Street Eureka California 95501 USA
T 1 707 443 8326 F 1 707 444 8330
W www.ghd.com

Drawn	Designer	Client CALTROUT	.,
Drafting Check	Design Check	Title EXISTING TIDE GAT	_
Approved (Project Director) SA Date MARCH	9, 2017	(3 OF 4) Contract No. 84-10882	
Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed and Sealed For Construction	original Size Ansi D Drawing No: S-10	

EEL RIVER ESTUARY AND CENTERVILLE SLOUGH ENHANCEMENT PROJECT **EXISTING TIDE GATE DRAWINGS** (3 OF 4) t No. 84-10882 Sht 43 of 44



| New Indicates signatures of original asset of charming of least refraction or charming of least refraction or charming of least refraction or charming or or ch